ARCH 9, 1953

STEEL

THE WEEKLY MAGAZINE OF METALWORKING

TRADE ASSOCIATIONS
How To Grow with Them

Are you getting the most benefit out of your trade association? See page 76

STEEL WAREHOUSES
Still Plagued by Imbalances, p. 65

STRETCHING NICKEL SUPPLY
Structural Strength Retained, p. 94

CONTENTS — PAGE 5

B & W BULLETIN 6-F

Properties of Carbon, Alloy and Stainless Steel Tubing for High-Temperature and High-Pressure Service



The Story of the Croloys

New data contained in the seventh, revised edition of B&W's Technical Bulletin 6-F make it must reading for technical personnel concerned with the properties of tubing for high-temperature and high-pressure service. TB-6F contains up-to-the-minute information on:

- Requirements of Tubing for High-Temperature Service
- Influence of Alloying Elements
- Chemical Composition
- Room-Temperature Properties
- Short-Time Tensile Properties
- Stress-Rupture
- Creep
- Thermal Expansion
- Thermal Conductivity
- Impact Properties
- Microstructure—Transformation Temperatures
- Air-Hardening Properties
- Effect of Hydrogen
- Common Causes of Tube Failures
- Upset, Formed and Machined Tube-Ends

On such grades as

B&W	NOMINAL ALLOY CONTENT	MAXIMUM SERVICE TEMPERATURE
Carbon Steel (Killed)		
Carbon-Moly	0.50% Mo	1050F
Croloy ½	0.60% Cr 0.50% Mo	1075F
Croloy 1	1% Cr ½% Mo	1150F
Croloy 1¼	1.25% Cr 0.50% Mo	1100F
Croloy 2	2% Cr 0.50% Mo	1150F
Croloy 2¼	2.25% Cr 1.00% Mo	1175F
Croloy 3-M	3% Cr 0.90% Mo	1175F
Croloy 5	5% Cr 0.50% Mo	1200F
Croloy 5-Si	5% Cr 0.50% Mo 1.50% Si	1300F
Croloy 7	7% Cr 0.50% Mo	1250F
Croloy 9-M	9% Cr 1% Mo	1300F
Croloy 16-13-3	16% Cr 13% Ni 3% Mo	1600F
Croloy 18-8	18% Cr 8% Ni	1600F
Croloy 25-20	25% Cr 20% Ni	2100F

Write for your copy
—on company letterhead, please.



Chemical



Oil

Power

TA-1739 (P)



THE BABCOCK & WILCOX COMPANY
TUBULAR PRODUCTS DIVISION
Beaver Falls, Pa.—Seamless Tubing; Welded Stainless Steel Tubing
Alliance, Ohio—Welded Carbon Steel Tubing

YES, IT IS POSSIBLE...
HIGH-STRENGTH GEAR BLANKS without EXCESSIVE WEIGHT





Whenever we ask a customer what
: rates highest in a gear blank, he
ually answers "Strength." Some-
nes he'll add as an afterthought,
strength, yes. And when I can get
heavy-duty blank without a lot of
tra weight, so much the better.
hat's a real advantage."

Bethlehem is turning out that
nd of gear blanks every working
ıy of the year. Blanks for spur,
evel, miter, herringbone, and other
pes of gears. Strong, sturdy, dura-
e blanks for gears that will carry
e wickedest loads. Yet they are
ot encumbered with pounds and
ounds of excess weight that can
equently cause some genuine
roblems for the machine-designer.

How is this possible?

One important factor is Bethlehem's unique manufacturing process. At Bethlehem, the blanks are forged and rolled, with the attendant benefits of *both* operations. What's more, forging and rolling are combined in a single step that gives better grain flow.

As a result, there's high homogeneity and strength in the finished blank. Yes, strength at every point —without excessive weight.

Bethlehem gear blanks are available in sizes from 10 to 42 in. OD—treated or untreated, as you specify. Ask for full details and a copy of illustrated Booklet 216.

BETHLEHEM STEEL COMPANY
BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation. Export Distributor: Bethlehem Steel Export Corporation

BETHLEHEM STEEL

BETHLEHEM ROLLED-and-FORGED CIRCULAR PRODUCTS



Ex-Cell-O Style 2112-A Precision Boring Machine.



Partial sectional view of assembly shows the operation in heavy lines.

Precision Turning

ON AN EX-CELL-O BORING MACHINE

Accurate Radii Turned at High Speed on Stainless Valve Plunger Assemblies

There are many jobs on Ex-Cell-O Precision Boring Machines that have nothing to do with boring. For example, here's a Style 2112-A single-end machine equipped for precision turning the radius on a valve and stem assembly.

The stainless steel assemblies are held in a collet chuck on the spindle. The turning tool is held in a tool block on a turret which is actuated by a hydraulic cylinder through a rack and pinion. Net production is 109 pieces per hour.

For further information on the many uses to be made of Ex-Cell-O Precision Boring Machines, see your local Ex-Cell-O representative or write for Bulletin 31205.

Close-up of spindle and tool block on Ex-Cell-O Style 2112-A Precision Boring Machine equipped for precision turning an accurate radius.



XLO

EX-CELL-O *for* PRECISION

EX-CELL-O

CORPORATION

DETROIT 32, MICHIGAN

52-14

This Week in Metalworking

STEEL

Vol. 132 No. 10 Mar. 9, 1952

✓NEWS ✓PRODUCTION-ENGINEERING ✓MARKETS

✓ **Metalworking Outlook** 57

As the Editor Views the News 61
Editor-in-Chief E. L. Shaner expresses his thoughts about industrial and political events of interest to businessmen

Windows of Washington 72

Mirrors of Motordom 79
What's doing in the motor capital? Detroit Editor Floyd G. Lawrence points up significant developments

The Business Trend 83

Men of Industry 87

✓ **Production-Engineering News at a Glance** 93

New Stainless Stretches Nickel 94
A 1 per cent nickel stainless is doing the job of type 301 at Budd. Properties are very nearly identical

Modifications Speed Short-Run Operations 98
Plant engineering department at Douglas alters standard production machines to fit aircraft peculiarities

Production Is Heavy on Lightweight Engines 102
Aluminum engines for portable power saws stream from well-integrated lines. Special machines do the job

Troubles Down—Output Up with Welded Studs 110
Multiple-gun unit welds five studs every 40 seconds to farm machinery rasp bars.

Progress in Steelmaking 115
Small 2-High Reversing Mills Gain Favor—Big reason for the switch by specialty steelmakers is lower cost

New Products and Equipment 147

✓ **The Market Outlook** 175
Metal Prices and Composites begin on Page 176

Metal Market 187

Behind the Scenes	6	Obituaries	90
Letters to the Editors	10	Calendar of Meetings	134
Subcontract Summary	70	Helpful Literature	171
Checklist on Controls	71	Metalworking Notes	197

Editorial, Business Staffs—16. Advertising Index—203. Editorial Index available semiannually. STEEL also is indexed by Engineering Index Inc., 29 West 39th St., New York 18.

Published every Monday by the Penton Publishing Company, Penton Building, Cleveland 13, Ohio. Subscription in the United States and possessions, Canada, Mexico, Cuba, Central and South America, one year $7.50; two years $15; all other countries, one year $20. Single copies (current issues) 50 cents. Metalworking Yearbook issue $2.00. Entered as second class matter at the postoffice in Cleveland, under the Act of March 3, 1879. Copyright 1953 by Penton Publishing Co.

XLO
EX-CELL-O *for* PRECISION

PRECISION MACHINE TOOLS

CONTINENTAL CUTTING TOOLS



PRECISION GRINDING SPINDLES

DRILL JIG BUSHINGS



AIRCRAFT AND PRECISION PARTS



HYDRAULIC POWER UNITS

Products of

EX-CELL-O
CORPORATION
DETROIT 32, MICHIGAN

51-18

Unsurpassed Synthetic RUBBER COMPONENT PARTS



Users of Acadia Synthetic Rubber component parts in hundreds of industries have found them unsurpassed. No matter what function synthetic rubber must perform, depend on Acadia parts. They best meet exacting specifications and operating conditions such as moisture, oil, heat, wear and age resistance. Molded, extruded, die-cut to close limits—compounded to meet specific conditions. Acadia engineers will gladly cooperate.

Seals • Gaskets • Washers • Cups • Channel • Strip
"O" Rings • Sheet • Tubing • Roll Goods • Cut Parts
Lathe Cut Washers

Sheet and Roll Felt Manufactured for Special Purposes and To Meet All S.A.E. and Military Specifications.

ACADIA Synthetic PRODUCTS

Processors of Synthetic Rubber and Plastics
Sheets • Extrusions • Molded Parts

DIVISION WESTERN FELT WORKS
4035-4117 OGDEN AVENUE
CHICAGO 23, ILLINOIS

Behind the Scenes...

Miserable Skunks

One of the darndest addresses we've seen in a long time is on the letterhead of Specialties, Inc., whose Paul H. Reiser this week wrote in about Specifications Handbook. They are located on *Skunks Misery Road, Syosset, Long Island.*

Bouquets Galore

Incidentally, the comments that are piling in every day on the Specifications Handbook are enough to warm the cockles of everyone's heart who even had the least little bit to do with the creation of it. Just listen:

Unquestionably the finest and most complete publication of specifications I've ever seen. . . very grateful. . . certainly arranged for easy reference . . . of great value to our engineers . . . very excellent and much needed publication. . . of real benefit. . . an indispensable tool. . . best source of information published. . . very helpful . . . been hunting this for years. . . a real service to the industry..... finest thing ever developed. . . excellent reference. . . exactly what we have needed. . . congratulations on making this available. . .

Yes, it is true that every subscription to STEEL entered during the year will receive a copy of the Handbook free of charge.

Iss Swiss

Since our grandpappy came from Switzerland we got a particular kick out of the story one of our good readers from Milwaukee told on himself when he stopped in to say hello the other day. Seems he just got back from a trip abroad during the course of which he had made a special trip to Switzerland to pick up some of his favorite delicacy—cheese. At his first meal in the hotel he asked for "Swiss cheese", noticed the waiter's confusion and then realized that in Switzerland all cheese is naturally "Swiss". After an elaborate explanation, the light finally dawned and the waiter smiled. "Iss Emmenthaler", he said, and served our friend a huge slice. It really was excellent, and our connoisseur praised it lavishly. "Iss very special," said the delighted waiter, "What you call eemport." He paused, then proudly proclaimed, "Eet come from Wees-consin!"

Collector's Item

Ever since the Universal Match Company delivered our new supply of match books some months ago, we felt they were most attractive but we didn't realize just how attractive until Earle B. Lafean of Pittsburgh wrote us the other day. It seems that Mr. Lafean is an officer in an organization whose purpose in life is the collection of paper match books. They meet quarterly in different cities of every state and their next national convention is slated for Richmond, Virginia this coming September. We are happy to send along an ample supply of STEEL book matches to be distributed at their next meeting. Incidentally, if you would like a handful for yourself, or for your kid's collection, let us know and we will get them off to you pronto.

Autosyncracies

What make car do you drive? If it's a Buick, you're right in style. At least that's the car most STEEL readers have, according to a recent survey conducted by our Market Research Department. A cross-section of 1350 readers of STEEL came up with this list of cars:

1.	Buick	262 readers
2.	Ford	221 readers
3.	Chevrolet	215 readers
4.	Plymouth	130 readers
5.	Chrysler	106 readers
6.	Dodge	99 readers
7.	Pontiac	97 readers
8.	Cadillac	87 readers
9.	Mercury	69 readers
10.	Studebaker	58 readers

One out of three of you has another car for the little woman to get the kids over to school and to do her shopping with, and a few characters have a three-car garage that's full!

Puzzle Corner

Those trains that we told you about last week are still racing from New York to Chicago and back again so we'll give you another week to work on it.

Shrdlu

(Metalworking Outlook—Page 57)



just what is dead burned dolomite?

IT is a hearth maintenance refractory made from a relatively inexpensive raw material (dolomite). Under properly controlled manufacturing processes, dead burned dolomite develops certain inherent qualities advantageous to efficient, low cost maintenance—qualities which have led to a steadily widening acceptance by the steel industry.

Typically, dolomite suitable for dead burning shows a chemical analysis of lime 30.4%, magnesia 21.6%, silica 0.3%, other oxides 0.2% and carbon dioxide 47.5%. Prior to dead burning, quarried dolomite is classified to proper sizes and the very fine particles, along with clay and silt, are removed by washing.

The sized, washed dolomite granules, proportioned with a small percentage of iron oxide, travel through rotary kilns heated to above 3000°F. As they pass through the hot gases, the particles are first calcined, giving up approximately half their weight of carbon dioxide, and then sintered and shrunk to dense, hard clinkers. High temperature reactions convert calcium oxide to crystalline lime and magnesium oxide to periclase. Some lime also combines with iron oxide and silica to serve the refractory as a bonding agent.

The resultant product has been variously called "double burned", "roasted", "sintered", "clinkered", "prepared", "black" and "dead burned" dolomite. Of these designations, dead burned is now the generally accepted term, indicating as it does the characteristic hard, dense, inert, crystalline, highly refractory quality of the material.

Dependable dead burned dolomite, marketed under the well-known trade names Magnefer and Syndolag, is manufactured by Basic Refractories at its Ohio Works—recently expanded to meet the industry's ever increasing use of this refractory.

GRANULAR BASIC REFRACTORIES

Basic Refractories Incorporated

845 HANNA BUILDING, CLEVELAND 15, OHIO

Exclusive Agents in Canada: REFRACTORIES ENGINEERING AND SUPPLIES, LTD., Hamilton and Montreal

THREADING COSTS CUT BY OVER 75%



DIE HEAD CUTS COST OF PRODUCTION & ASSEMBLY OF STABILIZER SCREWS

Time Study and Methods Department records of a large aviation equipment company furnish data of still another job where LANDMATIC Heads have effected large savings in machine time and assembly and improvements in product quality.

In this operation, the 1¼" LANDMATIC Head on a turret lathe equipped with Leadscrew is cutting a ⅝-6 Acme thread on a Stabilizer Screw used by a light aircraft manufacturer. The thread was held to the close tolerance of ±.001 between the P.D. of the thread and the O.D. of the screw, for a full thread length of 5⅜" on cold-drawn piston stock, Spec. #AISI, B1112.

Former methods required two passes to produce the finished thread—one roughing and one finishing cut. The thread is now cut in one pass in .192 at a spindle speed of 230 R.P.M. Approximately 3500 pieces are cut between chaser grinds. Hand fitting with the mating nut in assembly, previously necessary, has been eliminated. Total cost savings in all operations are in excess of 75%.

LANDMATIC Heads are stationary threading heads with self-opening action designed primarily for turret lathes. Their unusually-large oversize capacity makes them ideally suited for these machines.

For information and specifications, write for Bulletins F-80 and F-90.

50TH ANNIVERSARY

LANDIS Machine COMPANY
WAYNESBORO, PENNA



THREADING MACHINERY—THREAD CUTTING DIE HEADS—COLLAPSIBLE TAPS

The New Louisiana Purchase

EVERY day America crosses a frontier—the frontier of a new market. It is the market created by an ever growing population. Since Pearl Harbor, our population has increased 23½ millions—more than all the people now living in the region west of the Mississippi once called the Louisiana purchase, that vast billion-acre area which provided us with geographical frontiers for a hundred years.

During 1952, 8,500 babies were born daily, increasing our population by nearly 3,000,000 people. New families and bigger families need more and bigger houses, more food, clothing, cars, roads, hospitals, churches, schools. Their needs call for continuing and increasing production from farms and factories.

There are those among us who say a decline in government spending will bring depression. But where is there room for depression when we add the population of another Minnesota or an Iowa to our nation each year—when the need for goods and services increases steadily? In fact, only by tapering off our vast programs of government spending can industry and business hope to provide sufficient goods to maintain our present standard of living and satisfy the demands of our ever growing population.

Let no one tell you America has crossed its last frontier.

QUALITY YOUNGSTOWN SERVICE

The Youngstown Sheet and Tube Company

General Offices--Youngstown 1, Ohio
Export Offices--500 Fifth Avenue, New York

MANUFACTURERS OF CARBON ALLOY AND YOLOY STEELS

RAILROAD TRACK SPIKES - CONDUIT - HOT AND COLD FINISHED CARBON AND ALLOY BARS - PIPE AND TUBULAR PRODUCTS - WIRE - ELECTROLYTIC TIN PLATE - COKE TIN PLATE - RODS - SHEETS - PLATES.

END-WELDS STUDS TO STEEL IN A SPLIT-SECOND
ELIMINATES DRILLING, TAPPING, HAND WELDING
REDUCES MATERIAL HANDLING—TAKES THE TOOL TO THE WORK
SAVES STEEL—ELIMINATES HEAVY BOSSES AND FLANGES
IMPROVES PRODUCT DESIGN AND QUALITY
TAKE ADVANTAGE OF
NELWELD COST SAVINGS
IN STEEL FABRICATION

TO HANG....TO HANDLE....TO HOLD..

Faster installation of brackets or hangers for piping, tubing or conduit.



Fast installation of handling accessories that can be easily removed.

Split second stud welding lowers fabrication costs, improves product.

THE NELSON FASTENING ENGINEER WILL SHOW YOU

... right in your own plant how your production and your products can be improved with this modern fastening method. Your design and production men can actually participate and test the results on your own products.

For full information on Nelweld as applied to steel fabrication, write the Main Office, Lorain, Ohio.

Fasten it Better... at Less Cost, with NELWELD T. M. REG.

NELSON STUD WELDING

DIVISION OF GREGORY INDUSTRIES, INC., LORAIN, OHIO

LETTERS TO THE EDITORS

Specs Handbook Proves Value

We are in receipt of a copy of your Specifications Handbook which was sent to us as a subscription bonus. We wish to thank you for this handbook, and compliment you on the completeness and the valuable references contained therein . . .

C. H. Proffen
secretary
Charles T. Brandt Inc.
Baltimore

Have received my copy of the Specifications Handbook, which is of untold value to me. I have used it every day since receiving it.

P. T. Reilly
10412 Brighton Rd.
Cleveland

. . . . we think it is one of the finest things which could have been published for steel warehouses.

J. H. Rayfield
Steel & Tube Department
J. M. Tull Metal & Supply Co. Inc.
Atlanta

We sincerely appreciate our copy. It is most complete and we want to express our sincere thanks.

M. G. Henderson
district sales manager
Youngstown Sheet & Tube Co.
Boston

Machine Problem Posed

The sales department of STEEL suggested we contact you relative to a machine problem we are having for the Air Corps on a subcontract basis.

Our problem: Boring a 2¼ inch type 304, stainless steel tube by removing approximately 0.015 to 0.018 per side. The tubes are from 19 to 23 inches long. We have to have 100 to 125 micro finish and can have 0.005 to 0.008 taper. We have used all reputable brands of tool bits. All these break. Any suggestions you have will be greatly appreciated.

E. F. Gi
Unit Manufacturing C
Minneapol

• *At this distance it is difficult to pinpoint the source of your trouble. A long distance guess would be that your operation could offer an acute problem of tool chatter and vibration. An excessive condition of this kind could lead to tool breakage. Perhaps the use of a piloted boring bar with the possible addition of a roll support for steadying the workpiece would eliminate or at lea*

Dave O'Leary, Shop Superintendent, and Joe Koehn, Fitting Shop Foreman, look over a blueprint in the Heyl & Patterson Fitting Shop. Both men are 30-year veterans with Heyl & Patterson.

"Old Pros" with the "FOLLOW THROUGH" that counts!



The "Follow-Through" is one of the many ingredients that contributes to the successful performance records of Heyl & Patterson designed, fabricated and erected equipment.

Here is a picture snapped in the Heyl & Patterson Fitting Department. It's a "natural" showing how our shop men "follow-through" from the original designs of our Engineering Department. Compare the picture of these "Old Pros" with the "Follow-Throughs" you have seen on TV in batting scenes from the World Series in baseball and the important winning forward passes in pro-football games. The Heyl & Patterson "follow-through" is possible because we have our own Engineering Department, our own Fabricating Department, our own Machine Shop, our own Erection Department.

The H & P Engineering Department calls the signals and the other H & P Departments know how to "Follow-Through." This is why Heyl & Patterson can guarantee long-life, low-cost performance of Heavy Bulk Materials Handling Equipment.

Heyl & Patterson, Inc.

"SINCE 1887"

Heavy Bulk Materials Handling Equipment

All The Way from Design to Erection

55 WATER STREET · PITTSBURGH 22, PA.

How to get drier or cooler air or gases . . .



NIAGARA AERO AFTER COOLER cools a compressed gas, or air, below the temperature of the surrounding atmosphere, thus preventing the condensation of moisture in your lines. The gas will contain only half of the moisture left in it by conventional methods. Even drier gas can be produced if you require it.

In working with controlled atmospheres of inert gases to prevent undesired reactions, this dryness of the gas at low cost is a great advantage. The cost of the Niagara method is low because it uses evaporative cooling, saving 95% of the cost of cooling water (and its piping and pumping). This direct saving of cost pays for the Niagara cooler in less than two years.

If you use compressed air to operate tools or pneumatic equipment you save much in water and oil damage to tools and equipment, and in water damage to materials by using the Niagara Aero After Cooler.

Write for a bulletin, or ask nearest Niagara Field Engineer if you have a problem involving the industrial use of air.

NIAGARA BLOWER COMPANY

Over 35 Years' Service in Industrial Air Engineering

Dept. S, 405 Lexington Ave. New York 17, N. Y.

Experienced Field Engineers in Principal Cities of U. S. and Canada

LETTERS

Concluded from preceding page

alleviate the chatter problem. Speed and feed information as well as specifications for the carbide grade could be obtained from the representative of any reliable carbide maker.—ED.

Only Fool's Gold

In your article "Hunt on for Germanium" (Feb. 9, p. 118) you note that this metal is 65 per cent more than the price of gold. Don't you mean of?

I. H. Steinsapir
vice president
Standard Emblem Jewelers
Pittsburgh

• *You're right. Germanium is 65 per cent of the price of gold. Thanks for pointing out this error.—ED.*

How Smooth Is a Surface?

We have noticed with interest your article entitled "How You Can Specify Surface Finishes" (Jan. 19, p. 74). We would appreciate receiving six reprints of that article for use in our engineering department.

L. A. Camerota
chief engineer
Florence Pipe Foundry & Machinery Co.
Florence, N. J.

. . . please send me a reprint.

L. E. Pearson
engineering research department
Crompton & Knowles Loom Works
Worcester, Mass.

. . . we would like ten copies.

E. R. Lawson, assistant manager
Contract Engineering
Lewis Machinery Division
Blaw-Knox Co.
Pittsburgh

• *Sent.—ED.*

Waste Recovery Gets a Boost

We would very much like to receive a reprint of the article "Ion Exchange—New Hope for Waste Recovery (Oct. 20, p. 96) by Dr. Allen G. Gray, Technical Editor of STEEL.

A. Shukla
Gravery Water Conditioning Co.
New York

• *Sent.—ED.*

We read with considerable interest your article "Ion Exchange—New Hope for Waste Recovery." Since you don't mention the materials of construction we are wondering if you can tell us whether or not lead is used in the ion exchange systems used in brass pickling, tin plating and copper-nickel-chromium plating. We do know that lead is used in phosphoric acid pickling operations.

With this information at hand we would like to do another story for our own publication describing these particular applications. Whatever help you can give will be appreciated.

K. H. Rol
Lead Industries Association
New York

• *For more complete information on equipment used in ion exchange processes, write to Permutit Co., 330 West 42nd Street, New York 18, and Illinois Water Treatment Co., Rockford, Ill. —ED.*

Quality threading
AT MINIMUM COST



MODEL TG-615
6 x 15 inch

The 6 x 15 Automatic Thread Grinder is used for high production thread grinding with either single or multi-ribbed wheels on relatively small parts.

ONES & LAMSON
UTOMATIC THREAD GRINDERS:

- Produce threads of better quality and more uniform finish
- Reduce handling cost
- Eliminate costly rethreading after heat treatment
- Eliminate expensive retooling when specifications change
- Reduce cost of gage maintenance

Built-in accuracy and automatic features, make any of these machines a paying investment for toolroom or production line.

- Automatic wheel truing
- Automatic infeed on successive cuts
- Automatic sizing
- Rheostat wheel speed control
- Diamond or crush dressing of wheels
- Multi-ribbed threading
- Right and left hand threading



MODEL TG-636
6 x 36 inch

The 6 x 36 machine is extremely versatile and is used on long or short run jobs on a great variety of precision threaded parts. Single or multi-ribbed wheels can be used.



MODEL TG-1245
12 x 45 inch

The 12 x 45 machine is used for grinding threads on a wide range of work from small to large heavy parts. Single or multi-ribbed wheels can be used.

When measuring the value of a thread grinder remember the extra benefits of J&L top-flight construction. Write Dept. 710 for illustrated catalog.

JONES & LAMSON

Machine Tool Craftsmen Since 1835

JONES & LAMSON MACHINE CO., 517 Clinton St., Dept. 710, Springfield, Vt., U.S.A.

THREAD GRINDER DIVISION

another case where welded steel tubing does the job best . . .



HOW we took the rumble out of grandpa's sedan . . .

● Remember the rumble and roar that began when the old-style drive shaft under the floor started vibrating and whipping at 40 MPH.?

Today's automobiles can travel at twice Grandpa's speed with never a whisper of whip and rumble from the propeller shaft. Many such shafts are Republic ELECTRUNITE Tubing...uniformly round, fully concentric, with uniform wall thickness all around the tube and from end-to-end. There can be no heavy spots or light spots to throw the rotating tube out of balance.

Another advantage . . . Republic ELECTRUNITE Tubing has plenty of strength to withstand the reversal of torque when you release the accelerator and change from engine-driving to engine-braking conditions. The uniform walls of the light-and-strong hollow steel tube can "take" this twist for hundreds of thousands of miles.

This propeller shaft should give you the idea that welded steel tubing made the Republic ELECTRUNITE Way can take a lot of punishment . . . and come back for more. We'd like to tell you *all* the things that Republic ELECTRUNITE Tubing is doing successfully, and at lower cost. Write to:

STEEL AND TUBES DIVISION
REPUBLIC STEEL CORPORATION
253 East 131st Street • Cleveland 8, Ohio



Write for this booklet of design data and ideas on Republic ELECTRUNITE Mechanical Tubing. Ask for "Booklet STMT 100."

Republic
ELECTRUNITE TUBING

automatic performance reduces costs

even on **SHORT RUN** *jobs like this*

A MOTOR MANUFACTURER who made this commutator sleeve, and similar components, in lots of 300 to 800 and in several sizes, said "*on a modern type, hand-operated turret lathe our net output varied from 2½ to 3 pieces per hour, depending upon conditions*".

Present output on his new Acme-Gridley Model M Single Spindle Automatic has more than doubled, as the job facts reveal. Much of this increase is due to Model M design features which avoid those so-called "conditions". Most important among these features is. . .

—fully automatic performance which guarantees a controlled cycle time and uniform precision—piece after piece

In other shops, these newest Acme-Gridley Single Spindle Bar Automatics, on hundreds of small and large lot jobs, are *2 to 10 times faster than the machines they replaced.* Ask for Catalog M-50A—better still, ask us to quote.

Other Model M time and cost reducing advantages are—

- Eight independently operated tool slides and three automatic spindle speed ranges selective to suit each cut, whether for use of carbide or high speed tools.
- Turret indexes in 1 second and its independent tool slides provide for overlapping operations such as several short end cuts while the heavy cuts are continued from the side slides.
- The Model M also features standard cams, interchangeable spindle speed and feed change gears, and wide open tooling zone—all quickly accessible. So the set up time for changing jobs to secure fully automatic performance on similar work does not exceed that of the hand operated lathe.

JOB FACTS:

Part: Commutator Sleeve
Size: 3⅜" dia. 2¾" long
Material: C-1030 Steel
Machine Time: on Acme-Gridley 3½" Model M Single Spindle Automatic—10½ minutes.
Operations: 11, including rough and finish trepan on O.D. of flange for smooth finish, reaming hole for close concentricity and threading with automatic Vers-o-tool to class 3 fit.
Former Time: on current model hand operated turret lathe—20 to 25 minutes.

The NATIONAL ACME COMPANY

170 EAST 131st STREET • CLEVELAND 8, OHIO

Acme-Gridley Bar and Chucking Automatics, 1-4-6 and 8 Spindle—Hydraulic Thread Rolling Machines—Automatic Threading Dies and Taps—Limit, Motor Starter and Control Station Switches—Solenoids—Contract Manufacturing.





economical metal cutting with

VICTOR "Moly"® HIGH SPEED Power BLADES

Whatever your metal cutting problem, VICTOR "Moly"® High Speed Power Blades will cut your initial blade cost 15%, and give you the additional economy of more efficient cutting.

Quality makes VICTOR Blades industry's preference—top-quality, carefully heat-treated steel, fabricated on specially designed equipment, to give you fast, economical cutting and long blade life. Send for the free VICTOR Metal Cutting Booklet which tells you how to pick 'em—Gold "Moly"® High Speed or Silver Unbreakable High Speed.

ECONOMICAL SERVICE *from your* VICTOR DISTRIBUTOR

VICTOR "Moly"® High Speed Power Blades are always sold through the recognized Industrial Distributor because he is closest to your problems. You know and have confidence in him, and he can give you delivery from stock where and when you want it.

1822 VICTOR

SAW WORKS, INC. • MIDDLETOWN, N.Y., U.S.A.

Makers of Hand and Power Hack Saw Blades, Frames and Metal Cutting Band Saw Blades

STEEL

The Weekly Magazine of Metalworking

Editor-in-Chief, EARL L. SHANER *Editor*, IRWIN H. SUCH

Managing Editor, WALTER J. CAMPBELL

Assistant Managing Editors, VANCE BELL, JOHN S. MORGAN

News and Markets

WM. M. ROONEY.....*Market Editor*
FRANK R. BRIGGS.....*Associate Editor*
ARTHER W. ZIMMERMAN..*Assistant Editor*
JOHN KELSEY.....*Assistant Editor*
ROBERT O. JAYNES.....*Assistant Editor*
ROBERT M. LOVE.....*Assistant Editor*
H. VANYORX CALDWELL JR..*Assistant Editor*
MARY T. BORGERHOFF.....*Assistant Editor*

Engineering and Production

EDWIN L. KARPICK.....*Engineering Editor*
ALLEN G. GRAY.....*Technical Editor*
J. D. KNOX.....*Steel Plant Editor*
ROBERT F. HUBER.....*Machine Tool Editor*
WM. R. WOLFE.....*Assistant Editor*
THOMAS F. HRUBY.....*Assistant Editor*
DOLORES K. MAILLE.....*Assistant Editor*
NANCY SHAFFER.....*Editorial Asst.*

Resident Editors

New York 17 ..... 60 East 42nd St.
B. K. PRICE, L. E. BROWNE
SAMUEL W. BAKER
Murray Hill 2-2581

Chicago 11 ..... 520 North Michigan Ave.
E. F. ROSS
Whitehall 4-1234

Pittsburgh 19 ..... 2837 Koppers Bldg.
ROBERT E. HALL
Atlantic 1-3211

Detroit 2 ..... 6560 Cass Ave.
FLOYD G. LAWRENCE
Trinity 5-3024

Washington 4 .. 1123 National Press Bldg.
E. C. KREUTZBERG
Executive 6849

London, 2 Caxton St., Westminster S.W. 1
VINCENT DELPORT
European Editor

Editorial Correspondents

Birmingham ..... R. W. KINCEY
Birmingham 3-1121

Buffalo..... L. G. FELDMANN
Cleveland 5353

St. Louis.....MAC L. HUTCHENS
Republic 7752

Youngstown .....GEORGE R. REISS
7-1471

Los Angeles..... NORMAN LYNN
Hudson 2-4376

San Francisco ..... EDWIN HAVERTY
Yukon 6-5151

Seattle ..... R. C. HILL
Melrose 1895

Dallas ..... C. K. CATES
Riverside 4355

Toronto ..... F. S. TOBIN
Empire 4-9655

Birmingham, Eng. .....J. A. HORTON

Paris, France .....LEON JAUDOIN-PROM

Dusseldorf, Germany...DR. HERBERT GROSS

Liege, Belgium.....M. JACQUES FOULON

BUSINESS STAFF

Business Manager.....J. W. ZUBER
Promotion Manager .....S. F. MARINO
Circulation Manager .....G. R. EBERSOLE
Research Manager.....N. R. LADABOUCHE
Market Statistics .....G. J. AUNER

Advertising Manager .....C. H. BAILEY
Production Manager .....A. V. ANDERSON
Classified Advertising Mgr..DORIS ROBBINS
Mail & List Service.....AMY LOMBARDO
Reprints .....C. B. NILES

Advertising Representatives

New York 17 .....60 East 42nd St.
E. W. KREUTZBERG, K. A. ZOLLNER
Murray Hill 2-2581

Farmington, Conn. ... 12 Farmstead Lane
CALVIN FISHER, JR.
Farmington 7-1756

Pittsburgh 19 .....2837 Koppers Bldg.
S. H. JASPER, J. C. SULLIVAN
Atlantic 1-3211

Cleveland 13 .....Penton Building
D. C. KIEFER, H. G. ROWLAND
Main 1-8260

Cincinnati 30 .....5568 Beechmont Ave.
E. L. FRANKE—Parkway 3640

Detroit 27 .....14583 Longacre Rd.
C. A. TALLINGER JR.—Vermont 8-7207

Chicago 11 ..... 520 North Michigan Ave.
L. C. PELOTT, W. L. POLAND
JOHN W. VAUGHAN
Whitehall 4-1234

Los Angeles 48. 6262 Commodore Sloat Dr.
F. J. FULLER—Webster 1-6865

Griffin, Georgia .....331 South 12th St.
FRED J. ALLEN—Griffin 7854

Circulation Representatives

H. R. DUNNE, C. A. PRICE

CCA NBP MPA

Published Every Monday by

THE PENTON PUBLISHING CO., Penton Bldg., Cleveland 13, Ohio

President and Treasurer.....G. O. HAYS
Chairman .....E. L. SHANER
Vice Pres., Director of Advertising..R. C. JAENKE
Vice Pres. and Secretary .....F. G. STEINEBACH
Asst. Secy. and Asst. Treas. .....J. P. LIPKA

Also Publisher of FOUNDRY, MACHINE DESIGN, NEW EQUIPMENT DIGEST

Member of Controlled Circulation Audit, Inc., Magazine Publishers Association Inc., Society of Business Magazine Editors, and National Business Publications, Inc.

PRODUCTIONEERED

for Efficient Surface Grinding

You get a perfect balance of precision and production with Brown & Sharpe Surface Grinding Machines. Sensitive and precise, yet sturdy and durable, they give you exceptional performance on both toolroom and production work. You'll find them basically designed — "Productioneered" — for rapid set-up, easy operating, maximum output, and long-term accuracy that will repay your investment many times.

Brown & Sharpe

B·S "Productioneered" to cut

Brown & Sharpe No. 5 SURFACE GRINDING MACHINE

Where precision, fine finish, and rapid stock removal on flat surfaces are equally important, this productive hydraulic-type machine quickly pays for itself. Automatic hydraulic table feeds are powerful, smooth, quiet and infinitely variable. Centrally-located controls permit rapid set-up and easy operation. Flange-mounted removable unit-type wheel spindle provides accuracy of alignment — choice of plain-bearing or antifriction-bearing types. You'll find many other features for speed, safety, accuracy and long life that make the No. 5 ideal on both toolroom and production grinding for work up to 24" long, 8" wide and 11" high.

costs on precision work...



Brown & Sharpe Nos. 2L and 2LB SURFACE GRINDING MACHINES

These machines, long famous for their economical production of small to medium-sized precision work, give you the advantages of automatic lubrication and ample guarding to reduce maintenance costs and extend machine life. Removable unit-type precision wheel spindle, plain-bearing or antifriction-bearing — and rigid column construction—provide exceptional grinding finish with quick spark-out. The No. 2LB Machine with Hand Feeds Only is ideal for toolroom and production work where automatic feeds are not used. No. 2L (illustrated) and No. 2LB grind work to 18" long, 6" wide and 9½" high, using a wheel 7" in diameter.

"Productioneered" to aid in uniformly accurate production from your machines



BROWN & SHARPE ELECTRONIC MEASURING EQUIPMENT

Precision gaging and inspection as close as .00001" are simple and fast with this equipment that practically eliminates human error—for external or internal measuring.

BROWN & SHARPE PERMANENT MAGNET CHUCKS

These Permanent Magnet Chucks eliminate clamps, vises, and fixtures on many jobs . . . they're the time-saving way to solve work-holding problems. No operating costs, no electrical connections, no heating. Just turn lever and work is held firmly. Rotary and rectangular models. Wide range of sizes.

For sale only in the United States of America and its Territories.



BROWN & SHARPE No. 616 CYLINDRICAL GRINDING AND INDEXING ATTACHMENT

This versatile attachment makes possible dry grinding of small cylindrical work on surface grinders. Accommodates tapers and work requiring indexing. Grinding is done on dead centers. Indexing spring chuck, with spring collets, holds work not ground between centers. Centers swing 6" diameter—take 8¼" length. Table tilts to 45°.

WE URGE BUYING THROUGH THE DISTRIBUTOR

WRITE FOR COMPLETE INFORMATION ON ANY OF THE BROWN & SHARPE PRODUCTS LISTED AT RIGHT.

PRINTED IN U.S.A.

Brown & Sharpe

Milling Machines • Grinding Machines • Screw Machines • Cutters
Machine Tool Accessories • Machinists' Tools • Johansson Gage Blocks
Electronic Measuring Equipment • Permanent Magnet Chucks • Pumps

Brown & Sharpe Mfg. Co., Providence 1, R. I., U.S.A.

CHAINS and SPROCKETS

Jeffrey Chains and Sprockets are being put through the acid test of actual service on thousands of tough jobs . . . especially where the demand is for high-quality products. They are in universal use for unit machinery, for conveyors and bucket elevators, and for transmitting power. Follow the lead of those engineers who know the importance of "good chains and sprockets." Send for our new Catalog No. A-418 which goes into detail.

We show only a few types here but Jeffrey builds a complete line from which to choose.

THE JEFFREY MANUFACTURING CO.

ESTABLISHED 1877

Columbus 16, Ohio

sales offices and distributors in principal cities

PLANTS IN CANADA, ENGLAND, SOUTH AFRICA

IF IT'S MINED, PROCESSED OR MOVED . . . IT'S A JOB FOR JEFFREY!

It's no accident that

they're known as LIGHT-HEAVYWEIGHT Drill Presses



It was done by design— WALKER-TURNER Design

For jobs where neither the capacity nor expense of a heavy industrial machine is warranted, and where a "hobby drill" would be wholly inadequate, Walker-Turner has engineered a special class of Light-heavyweight Drill Presses.

Professional in design and operation, yet light for production machines, this "in-between" line gives industry the needed capacity for short-run production work, without the necessity of heavy investment. Walker-Turner makes 15″ and 20″ Drill Presses (in Bench, Floor, and Production Models), as well as Radial Drills. For complete information, use margin below to write your name and address.

WALKER-TURNER
• DIVISION •
KEARNEY AND TRECKER CORPORATION
PLAINFIELD, N. J.

DRILL PRESSES • RADIAL DRILLS • TILTING ARBOR SAWS
BELT and DISC SURFACERS • METAL-CUTTING BAND SAWS
LATHES • SPINDLE SHAPERS • JOINTERS

SOLD ONLY THROUGH
TRAINED
INDUSTRIAL DISTRIBUTORS

VERSATILE LIGHT-HEAVYWEIGHT 20″ WALKER-TURNER DRILL PRESS MULTIPLE-SPINDLE MODEL

Designed for industrial users where production rate and initial cost are primary factors in the selection of equipment, Walker-Turner 20″ Drill Presses operate continuously and accurately at any rate of speed from 400 to 2600 r.p.m. Multiple spindle models (2 to any desired number) are particularly effective in increasing production on many jobs where a series of holes are to be drilled, tapped, reamed or counterbored in a single piece.



Use this space

to write for full details and specifications
Walker-Turner Division, Kearney & Trecker Corp.
Dept. S-5, Plainfield, N. J.
(Please write your name and address in margin of page)



Like the grinding of a lens—

STEELMAKING, TOO, REQUIRES EXACT FINISHING

Whatever your requirements for formability, uniformity, or drawing qualities, you'll find J&L Sheet & Strip . . . accurately and faithfully produced to meet your specifications. Complete understanding of the end-use of the sheet or strip you order is a rigid requirement of J&L production. You can depend upon J&L products to fit your production line.

J&L STEEL

JONES & LAUGHLIN STEEL CORPORATION
PITTSBURGH

Treadwell



Courtesy of Aluminum Co. of America



TREADWELL UPCOILERS for the FERROUS and NON-FERROUS STRIP INDUSTRY.

The above Coiler and Coil Handling Equipment is being used on what is probably the largest Aluminum and Aluminum Alloy Strip Mill in operation. The Coiler automatically transfers the Coil to a Turn Table. The Coil is turned 90° and deposited on a Run-out Conveyor to a Downender. The Downender sets the coil on end, depositing it on a Storage Conveyor for distribution.

Our Engineers will be glad to discuss your Hot and Cold Strip and Coil problems with you. We manufacture all types of Rolling Mill Equipment including Blooming Mills, Bar Mills, Rod Mills, Plate Mills, and Strip Mill Machinery, as well as Slab, Billet, and Bar Reheating Furnace Equipment.

BETTER GRADE MACHINERY

Treadwell Engineering Company

EASTON, PA.

SALES AND ENGINEERING OFFICES:

208 S. LA SALLE STREET
CHICAGO 4, ILL.
CEntral 6-9784

140 CEDAR STREET
NEW YORK 6, N. Y.
WOrth 4-3344

1217 FARMERS BANK BLDG.
PITTSBURGH 22, PA.
ATlantic 1-2883



If Your Tubing Problems Involve Corrosion Resistance . . .



THEN HIGH QUALITY, WELDED STAINLESS TUBING WILL IMPROVE YOUR EQUIPMENT, PRODUCTS AND SERVICE

If you are fabricating or using tubing in corrosion resistance applications such as heat exchangers, condensers, evaporators, boilers, then you'll lower maintenance costs, improve your products and increase the service life of your equipment by using Pacific high quality, Welded Stainless Tubing.

PATCO Welded Stainless Tubing is made from bright-finished, high-quality, flat-rolled strip of uniform thickness and hardness. The finish is inspected on both sides. The strip is fusion welded under an inert gas shield (no flux or filler is used) to prevent porosity or contamination of the welded metal.

The tube is then subjected to severe cold work which removes the weld flash and produces clean smooth surfaces. Subsequent annealing to remove all traces of work hardening further refines the weld area. Soundness of the weld is doubly insured by special testing when welding and by the cold finishing operations that are employed.

There is no need for you to take chances with ordinary tubing when you can be sure of results with PATCO high quality, Welded Stainless Tubing. It's available now in sizes from ¼" to 2⅜" O.D. in Types 304, 316, 321 and 347. For complete information write or mail the coupon today. If your need is urgent call UNderhill 0-1331.

West Coast representatives for: Superior Tube Company, manufacturers of fine small tubing in all analyses from .010" to ⅝" O.D. and in certain analyses (.035" max. wall) up to 1⅜" O.D.

Visit our booth at the WESTERN METAL SHOW
March 23-27, Los Angeles, California

Sizes and Analyses

TUBING

SEAMLESS CARBON
MT.—1015, 1020, 1025
Round: ⅜" O.D. to 2¾" O.D.
Square: ¼" to 2" O.D.

SEAMLESS ALLOY
4130—NE 8630
Round: ⅜" O.D. to 3¾" O.D.
Square: ¼" to 2" O.D.

CHROME
4%-6%, 6%-8%, 8%-10%
⅜" to 1⅞" O.D.

STAINLESS STEEL
Seamless and Welded
Types 304, 316, 321, 347
Round: ¼" to 2⅞" O.D.
Square: ¼" to 1⅞" O.D.

WELDED CARBON TUBING
¾" to 3" O.D.

BARS

C-1018, B1113, G1137, FS1117
COLD FINISHED
⅜" to 2½"

For Other Shapes, Contact Mill

YOU CAN'T BEAT **PATCO** FOR TUBING

PACIFIC TUBE COMPANY

First Steel Tube Mill in the West

PACIFIC TUBE COMPANY
5702 Smithway Street
Los Angeles 22, Calif.
Gentlemen:

☐ Please send me information on your welded stainless steel tubing.

☐ Have your representative call.

Name_____

Firm Name_____

Address_____

City_____ Zone_____ State_____

STANDARDS and SPECIALS by the Millions

THE FERRY CAP & SET SCREW CO.

2159 SCRANTON ROAD • • • CLEVELAND 13, OHIO

"SHINYHEADS"

America's Best Looking Cap Screw

Made of high carbon steel — AISI C-1038 — to standards for Full Finished hexagon head cap screws — bright finish. Heads machined top and bottom. Hexagon faces clean cut, smooth and true, mirror finish. Tensile strength 95,000-110,000 p.s.i. Carried in stock.

"HI-CARBS"

Heat Treated Black Satin Finish

Made of high carbon steel — AISI C-1038. Furnished with black satin finish due to double heat treatment. Hexagon heads die made, not machined. Points machine turned; flat and chamfered. Tensile strength 130,000-160,000 p.s.i. Carried in stock.

"LO-CARBS"

Made of AISI C-1018 steel — bright finish. For use where heat treatment is not required and where ordinary hexagon heads are satisfactory. Hexagon heads die made to size — not machined. Points machine turned. Tensile strength 75,000-95,000 p.s.i. Carried in stock.

SET SCREWS

Square head and headless — cup point. Case hardened. Expertly made by the pioneers in producing Cup Point Set Screws by the cold upset process. Cup points machine turned. Carried in stock.

FILLISTER CAP SCREWS

Heads completely machined top and bottom. Milled slots — less burrs. Flat and chamfered machined point. Carried in stock.

FLAT HEAD CAP SCREWS

Heads completely machined top and bottom. Milled slots — less burrs. Flat and chamfered machined point. Carried in stock.

"SHINYLAND" STUDS

All studs made steam-tight on tap end unless otherwise specified, with flat and chamfered machined point. Nut end, oval point. Land between threads shiny, bright, mirror finish. Carried in stock.

ADJUSTING SCREWS

Valve tappet adjusting screws — Hexagon head style — to blue print specifications — hexagon head hard; polished if specified — threads soft to close tolerance — points machine turned; flat and chamfered.

CONNECTING ROD BOLTS

Made of alloy steel — heat treated — threads rolled or cut — finished to extremely close thread and body tolerances — body ground where specified. Expertly made by the pioneers in producing connecting rod bolts by the cold upset process.

SPRING BOLTS

Case hardened to proper depth and ground to close tolerances. Thread end annealed. Supplied in various head shapes, with oil holes and grooves of different kinds, and flats accurately milled.

FERRY PATENTED ACORN NUTS

For ornamental purposes. Steel insert — steel covered. Finish: plain, zinc plated, cadmium plated. Size: 9/16", 3/4", 15/16" across the flats.

Tapped 1/4" to 3/4" inclusive. Cross section of Ferry patented acorn nut, showing how steel hexagon nut fits snugly into shell.

Pioneers and Recognized Specialists, Cold Upset Screw Products since 1907

STANDARDS carried by LEADING DISTRIBUTORS

SPECIALS furnished to BLUE PRINT SPECIFICATIONS

WRITE FOR INFORMATION

SEND FOR SAMPLES



MACHINING FOR GOLD at Homestake

with Gisholt Turret Lathes

Yes, gold mining means machinery. And here at the famous Homestake Mine at Lead, South Dakota, Gisholt Turret Lathes help to machine the machines that dig for gold. It's a big job, too—turning out the variety of rock bits and drill rods that are used up in large numbers.

This Gisholt Ram Type Lathe was first used to turn the plain ends on the one-inch quarter-octagon drill steel for two types of rock bits. Production averaged 30 an hour. Now, the machine is also used to machine and thread three sizes of forged steel drill rods. Besides all this, the Gisholt has the job of facing and chamfering the chuck, or shank ends, of the drill steel so that a perfectly flat face is hit by the drill machine tappet.

Here, again, Gisholt Ram Type Turret Lathes prove their easy change-over and ability to produce profitably, even on small runs—big assets in any machine shop. Ask your nearest Gisholt representative about them. Or write us.

GISHOLT MACHINE COMPANY

Madison 10, Wisconsin

THE GISHOLT ROUND TABLE
represents the collective experience of specialists in machining, surface-finishing and balancing of round and partly round parts. Your problems are welcomed here.

TURRET LATHES • AUTOMATIC LATHES • SUPERFINISHERS • BALANCERS • SPECIAL MACHINES

10 Important Technical Handbooks

To help you...
available without charge...

Put Reynolds Technical Knowledge To Work for You . . . If you are part of a plant management, design or production group, you'll find these interesting, helpful books of real value. Each deals with an important phase of aluminum design and fabrication. Each is fully illustrated and comprehensively discusses all aspects of its subject. These authoritative handbooks by the technical experts on aluminum at Reynolds belong on your desk for ready reference. And, to put added interest in your training programs and technical society meetings, you'll want to use Reynolds 16mm. sound-color-films on aluminum. Please request handbooks or films on your business letterhead.

Also see our condensed catalog $\frac{1a}{Rey}$ in Sweet's Product Design File or write for your personal copy.

Valuable 16MM Color-Sound Films, Too

- **SHAPE OF THINGS TO COME.** Interesting descri- tion of the aluminum extrusion process and the desi opportunities it provides. Running time 30 minutes.
- **TALE OF THE POWDERED PIG.** Developments aluminum powders and pastes including their application protective and decorative coatings. Running tim 22 minutes.
- **PIGS AND PROGRESS.** The complete story of al minum from mine to finished products. Covers all forms aluminum. Running time 26 minutes.

Complete index of Reynolds literature and films on aluminum design and fabrication also available.

Order from REYNOLDS METALS COMPAN
2520 South Third Street, Louisville 1, Kentucky

Instructors in technical schools are also invited to take advantage of these educational aids.

GNING WITH ALUMINUM
RUSIONS—Explains
asic principles for using
ded aluminum shapes
effectively.



ALUMINUM STRUCTURAL DESIGN—Shows how to design original structures with aluminum or convert present designs to aluminum.



FASTENING METHODS FOR ALUMINUM—Offers information on mechanical joining and fastening methods, and the advantages of each



FINISHES FOR ALUMINUM—Supplies basic information on the application and uses for electroplated, mechanical, chemical and organic finishes.

on Aluminum Design and Fabrication

ALUMINUM DATA BOOK—Discusses the physical, chemical and metallurgical factors of aluminum as they affect design and fabrication.



ALUMINUM POWDERS AND PASTES—Describes types of powders and their uses in coatings, pyrotechnics, processing, metallurgy, etc.

AINUM FORMING—De-
es accepted practices for
ing, forming, and draw-
luminum.

MACHINING ALUMINUM ALLOYS—Discusses all phases of aluminum machining including automatic screw machining.



HEAT TREATING ALUMINUM ALLOYS—Explains the methods and results of heat treating suitable aluminum alloys.



WELDING ALUMINUM—Gives complete information on *all* types of welding as applied to aluminum.

ure to see "Mister Peepers" every Sunday night, 7:30 EST, NBC-TV; hear "Fibber McGee and Molly" every Tuesday night, 9:30 EST & PST, NBC radio

EYNOLDS ALUMINUM

DERN DESIGN HAS ALUMINUM IN MIND

NEED A SPECIAL PURPOSE MACHINE?

TURNER BROS. INC. DESIGNS AND BUILDS SPECIAL MACHINES TO HELP YOU *SAVE* ON MANPOWER, INSPECTION TIME AND FLOOR SPACE



Turner Bros. are primarily known for designing and building special indexing, transfer and trunnion type drilling, reaming, tapping and milling machines. They also design and build other types of special purpose machines, such as assembling machines, testing machines, hydraulic presses, impregnating and flushing machines. Some typical examples are shown here.

Flush-Out Machine

Multiple cylinder head flush-out machine for testing and washing sand and chips from semi-machine cylinder heads. Cylinder head is placed in one side of machine, tripping limit switches, and when operator presses buttons, fixture closes, water pressure is automatically applied to fixture and forced into all openings that are not sealed in cylinder head. Water is flushed through all cavities in cylinder head for wash purposes. Pressure of water is equal to a 3" stream forced 90 feet into the air. During the sequence of this operation, operator is unloading and loading other fixture on machine. Note two palm buttons for operator safety.



Automatic Drilling, Assembling and Crimping Machine

Machine designed and built by Turner Bros. for the automatic hopper loading of breather nut, insertion of baffle, crimping of baffle, drilling of nut, and automatic ejection.

50-Ton Hydraulic Precision Assembly Press

Hydraulic Assembly Press for accurately maintaining center distances in assembling inner portions of fluid coupling. The ram on this machine is set with an indicator and the stroke is electrically and hydraulically controlled so that assembly of the three members is accurately maintained and production is increased.

Do you have a production assembly or inspection problem where you can utilize to advantage a special purpose machine? Why not write us today describing your problem. After our engineering department analyzes it, our field engineer will discuss it with you.

TURNER BROS. INC.

2625 HILTON ROAD
FERNDALE 20, MICHIGAN

DESIGNERS and BUILDERS of:

- SPECIAL MACHINES
- JIGS and FIXTURES

tool steel is the cornerstone of our business

Just as the cornerstone is of fundamental importance to a building, tool steel is the base of our business. And ever since we were founded — now over 50 years ago — we have been proud of our reputation as the nation's leading producer of tool steels.

We have always given our customers what they needed — quality and service — regardless of their volume of business or the general supply and demand situation. During last year's steel shortage, for instance, all our customers had their share of our production.

You too, can benefit from our long experience in this field through our freely available metallurgical service . . . and from our reliable delivery service through our fully stocked warehouses, conveniently located all over the country.

SEND TODAY for the unique Crucible Tool Steel Selector — a twist of the dial gives the tool steel for your application.

Rex® High Speed Steels
Peerless Hot Work Steels
Halcomb 218
Chro-Mow®
Sanderson Carbon Tool Steels
Ketos®
AirKool Die Steel
Airdi® 150
Nu-Die V Die Casting Steel
CSM 2 Mold Steel
La Belle® Silicon #2
Atha Pneu

SPECIFY YOUR TOOL STEELS BY THESE BRAND NAMES

Crucible Steel Company of America
Dept. S, Chrysler Building, New York 17, N. Y.

Name_____

Company_____ Title _____

Address _____ City_____ State_____

9" diameter, 3-colors

CRUCIBLE first name in special purpose steels

53 years of Fine steelmaking

TOOL STEELS

CRUCIBLE STEEL COMPANY OF AMERICA • TOOL STEEL SALES • SYRACUSE, N. Y.

Engineered Rebuilding

How Simmons Methods Increase Machine Tool Output and Efficiency

Rebuilt and modernized slotter boosts output, saves time and labor...



Faced with the problem of acquiring a 72″ slotter, the engineers of a large manufacturer decided to buy a used one and have it rebuilt to their needs.

But they wanted Simmons, who provided the slotter, to do more than restore it to peak efficiency. They wanted to *modernize* it ...to incorporate into the machine new labor and time-saving devices.

Simmons worked with them on the problem, came up with a push-button method of indexing which precisely turns the table through given angles of rotation. Error is less than 0.003″ on the circumference.

Further modifications made are: increased vertical capacity; power table locks on anti-friction bearings in the table; automatic electromagnetic clutching of the various table drives; automatic lubrication; complete electrical control of all operations from a single pendant station.

The work went ahead on schedule and the machine is now in use. And, according to one of their firm's chief engineers, the modifications have eliminated manual-layout work, and the need for a helper's assistance, as was formerly required. In short: considerable savings.

Will rebuilding work for you? It's easy to find out: simply send a list of your machines that might be rebuilt for extra capacity, renewed accuracy. We'll quote prices and delivery. Meanwhile, write today for a copy of our quarterly publication, THE SIMMONS WAY.

Simmons Machine Tool Corporation
Main Office and Plant:
1755 N. Broadway, Albany 1, N. Y.
Export Office:
50 East 42nd Street, New York, N. Y.
Philadelphia: Phone Victor 8-3133
Pittsburgh: Phone Penhurst 1-3700

SIMMONS GIVES USED MACHINE TOOLS A NEW LEASE ON LIFE

STEEL PROBLEMS ?

One call gives you ALL the answers!



Delays are costly. When a business is faced with a problem, it is to its advantage to solve it quickly and maintain production rates. Of course—in this age of mass production, specialists, and far-flung operations —that isn't always possible. But Weirton, with a full appreciation of the importance of its customers' problems, has integrated all operations to provide time-saving answers.

At Weirton, key men who may be needed for decisions on prices, quantities, metallurgy, deliveries, or other problems are within quick reach of one another. Sales, laboratory, production, shipping—all departments are "under one roof" to cut delays to a minimum when customers need quick action.

This method of operation was established for your benefit. When you are faced with a steel problem, pick up your phone and get *all* the answers quickly . . . from Weirton.

WEIRTON STEEL COMPANY
WEIRTON, WEST VIRGINIA

NATIONAL STEEL CORPORATION

The Answer to your toughest tank lining problems

TYGON

flexible – plastic

TOPS IN CORROSION-RESISTANCE

PROVEN in hundreds of the toughest possible applications during the past fourteen years, flexible Tygon plastic linings offer more value today than ever before.

Greater toughness — more stability — even longer life. These improved performance characteristics stem from improved manufacturing techniques, resulting in a denser, more homogeneous body. Top quality yesterday, Tygon is an even better material today.

And along with improved quality — application methods have been simplified. Application is no longer a "factory" must. Strategically located Tygon licensed applicators can now install Tygon linings quickly and economically. Coupled with lower applied costs are important savings in freight costs — and vitally important savings in time.

For that next "tough" tank lining problem — ask for, insist on — Tygon.

This new booklet tells the "down-to-earth" facts about Tygon. Where and how to use it. When not to use it. A valuable reference for every engineer faced with corrosion problems. Free on request. Write for your copy today!

Address: Plastics & Synthetics Division, The U. S. Stoneware Co., Akron 9, Ohio.

U. S. STONEWARE

AKRON, OHIO

it doesn't look like a turret lathe, BUT...

- It sets up *fast*—like a turret lathe.
- It uses turret lathe tools.
- It machines turret lathe lots, on an automatic basis, without the usual penalties of automatic operation.
- It will combine certain operations not possible in accepted turret lathe practice, thus reducing machining time.
- It will automatically change speeds and feeds under cut to assure more efficient performance of your cutting tools.
- It requires less skill to operate—and in many cases one man can handle two or more machines.

. . . it is the Warner & Swasey 1-AC Single Spindle Automatic Chucking Machine.

With today's emphasis on greater production, there are undoubtedly certain jobs in your shop that could be machined faster and better on the 1-AC. Call in your nearest Warner & Swasey Field Engineer—he'll show you exactly how it can improve your operation.

WARNER & SWASEY
Cleveland
PRECISION MACHINERY SINCE 1880

)U CAN PRODUCE IT BETTER, FASTER, FOR LESS WITH WARNER & SWASEY MACHINE TOOLS, TEXTILE MACHINERY, CONSTRUCTION MACHINERY

Do You Have a Corrosion Problem as Tough as This?



If you have a tough corrosion problem, there's a good chance you'll find the solution in durable Pitt Chem Tar Base Coatings.

Pickling tank surfaces like these, for example, *really* take a beating from constant exposures to acid spillage, fumes, and condensation. But month in and month out, Pitt Chem Tar Base Coatings can provide economical, long-lasting protection against these and similar extreme corrosive conditions.

Pitt Chem Tar Base Coatings are easy to apply and up to ten times as thick as ordinary paints. No other material does such a complete job of protection at so little cost.

Why not drop us a line, *right now,* outlining your problem? We'll gladly provide you with our recommendations . . . or supply the technical literature or assistance you need.

W&O 4485

PITT CHEM 101
For severest corrosive conditions

PITT CHEM 102
A thin, high gloss maintenance coating

PITT CHEM 103
For metal exposed to vapors, dilute acids and alkalis

PITT CHEM 104
For equipment handling potable water

AND OTHER SPECIALTY COATINGS

PROTECTIVE COATINGS DIVISION

PITTSBURGH
COKE & CHEMICAL CO.

Grant Building · Pittsburgh 19, Pa.

COAL CHEMICALS • AGRICULTURAL CHEMICALS • FINE CHEMICALS • PROTECTIVE COATINGS • PLASTICIZERS • ACTIVATED CARBON • COKE • CEMENT • PIG IRON



No job is too tough for a FLEXLOC. TOMKINS-JOHNSON uses a FLEXLOC on the piston rod of its revolutionary Super-Cushion Air Cylinder. The maker doesn't take the chance of a nut coming loose and damaging the whole cylinder.



What FLEXLOC locknuts do for you

FLEXLOCS eliminate complicated, time-consuming methods of locking threaded fasteners. They offer simpler, faster application and safer, more dependable locking than plain nuts and lockwashers, castellated nuts and cotter pins, or nuts and jam nuts. And they won't work loose.

The reasons for all this are plain. FLEXLOCS are one piece—nothing to assemble, come apart, lose or forget. FLEXLOCS are all metal—have higher tensile than most other locknuts and are not affected by temperatures to 550°F. FLEXLOCS are both stop and locknuts—don't have to seat to lock, and stay put anywhere on a threaded member as soon as their locking threads are fully engaged.

SPS can deliver any quantity of FLEXLOCS in a wide range of sizes. Stocks are carried by industrial distributors everywhere. Write for literature. SPS, Jenkintown 33. Pa.

FLEXLOC

LOCKNUT DIVISION

SPS

JENKINTOWN PENNSYLVANIA

Our Fiftieth Year : A START FOR THE FUTURE

Dramatic radar tower of the S. S. United States. The ship was designed by Gibbs & Cox, Inc., built by Newport News Shipbuilding and Drydock Co., and is operated by U. S. Lines, Inc.

S. S. UNITED STATES MADE WITH BRICK!

Symbol of superiority among the world's merchant marine fleets. The fastest and safest passenger liner afloat. Flagship of American production . . . made with brick.

Refractory brick, that produced the thousands of tons of steel for the mighty S.S. United States. For her gigantic hull and the thousands of components . . . all made from steel, the metal that has established America as the industrial leader of the world.

In every type of furnace used in a steel mill, you will find refractory brick produced by GREFCO. The coke ovens that make the fuel for blast furnaces are built of silica and fireclay brick, while coke chutes and hoppers give trouble-free service when lined with CARBEX silicon carbide. A long-time standard of quality in coking chambers is GREFCO's silica brick. The same eminent position is occupied by GREFCO fireclay brick in other parts of the ovens. Both GREFCO silica and



GENERAL REFRACTORIES

·eclay brick are produced in strategic cations throughout the country.

In blast furnaces it's OLIVE HILL l the way. Hard fired, dense OLIVE ILL, a special high duty fireclay brick r which GREFCO is famous, provide ıe best of service in hearth, bosh and ack. Other GREFCO high duty fireclay ick are used in lining piping and her auxiliaries.

Most hot blast stoves are lined with ense, high duty fireclay brick but, r extra severe service, the combustion ne inner lining, the dome, and the p checkers, are built with HIAC SUPERAC, super duty fireclay brick.

GREFCO's exclusive unburned RITEX basic brick and STEELKLAD, a basic brick permanently jacketed in a patented steel shell, give unmatched service in the open hearth.

In every other phase of steel production, GREFCO products will be found. There would be no S.S. United States without steel . . . and there would be no steel without refractory brick. If, in your production, you demand quality refractories backed by the most modern of research facilities . . . available in whatever quantity you may require . . . call on GREFCO for a truly *complete refractories service.*

GENERAL REFRACTORIES COMPANY

PHILADELPHIA



ALLOY STEEL FORGINGS
FOR THE AIRCRAFT INDUSTRY

From its early days National Forge has produced alloy forgings, heat treated and machined to the exacting requirements of the Aircraft Industry.

We are proud that our facilities—the special electric steels, heat treating and skilled machining—have made it possible for us to assist the aircraft industry in pioneering the development of many mechanical components.

Pictured here are shafts for turbo-jet engines and rotor shafts for helicopters; both requiring the maximum in strength and resistance to fatigue, wear and shock. Their production, here at National Forge, started with the steel itself, and through successive steps of heat treatment and machining were brought through our plant under the closest metallurgical and physical control.

National Forge has complete facilities and assumes the whole responsibility of producing your forgings from the steel through finish machining. This service is yours for aircraft or for commercial forgings.



THE SOLVENT DESIGNED FOR MODERN VAPOR DEGREASING



CONVEYORIZED. "Triclene" D cleans refrigerator motor parts speedily and economically on a production line basis.

MANUALLY OPERATED. Castings will emerge clean, warm and dry from this small basket degreaser—instantly ready for assembly or further fabrication.

DU PONT "TRICLENE" D

(TRICHLORETHYLENE)

peeds conveyor and manual operations

You can't buy a better solvent for modern vapor degreasing than "Triclene" D. Whatever your present degreasing requirements are, rugged "Triclene" D assures you perfect solvent performance. That's because "Triclene" D has been carefully developed over the past twenty years—ever since Du Pont pioneered synthetic solvents for vapor degreasing—and is specifically designed to meet today's varied cleaning tasks.

Stable and pure "Triclene" D gives excellent results in high-speed degreasing operations—even those involving removal of the newer, chemically active lubricants. Its narrow boiling range permits easy solvent recovery from sludge for efficient re-use. And to help keep your *entire* metal cleaning operation at peak efficiency, Du Pont field men will gladly give you the benefit of their technical experience.

THIS VALUABLE INFORMATION IS YOURS—FREE

You'll find complete information on the operation and maintenance of vapor degreasing equipment in these booklets. And interesting, up-to-date case histories about degreasing units in operation throughout the metal field are presented in our publication, "MODERN METAL FINISHING." You can receive this wealth of information by checking the appropriate boxes in the coupon below and returning it to us.



E. I. du Pont de Nemours & Co. (Inc.)
Electrochemicals Dept., Wilmington 98, Del.

Please send me more information on vapor degreasing and "Triclene" D. I am interested in receiving the literature checked below.

- ☐ **Free booklets on vapor degreasing**
- ☐ **Free publication "MODERN METAL FINISHING"**
  (Please add my name to the mailing list)

*Name*_____ *Position*_____

*Firm*_____

*Address*_____

*City*_____ *State*_____

DU PONT
first in solvents for
VAPOR DEGREASING

DU PONT REG. U.S. PAT. OFF.

BETTER THINGS FOR BETTER LIVING
. . . THROUGH CHEMISTRY



You know he'll never lose you . . .

YOUR GUIDE . . . you *know* he'll take you where you want to go, by the quickest, easiest route. That's exactly what Bristol Brass aims to do . . . to get your order to you the same way. And that takes experience and *character* . . . both in the company and in its product.

Matter of fact, that's why so many people keep standing orders with Bristol Brass . . . because they know those orders will never get lost. They'll be where they're supposed to be, right on time, and *right* according to specifications . . . be it sheet, rod or wire.

. . .

The BRISTOL BRASS CORPORATION, makers of Brass since 1850 in Bristol, Conn. Offices or warehouses in Boston, Chicago, Cleveland, Dayton, Detroit, Los Angeles, Milwaukee, New York, Philadelphia, Pittsburgh, Providence, Rochester.

"Bristol-Fashion" means **Brass at its Best**

Only DRAVO *Counterflo* Space Heaters offer you these 5 exclusive features:

Ideal for heating large open spaces in industrial, commercial and educational buildings, standard Dravo *Counterflo* Space Heaters have five exclusive advantages over other warm-air space heaters.

1. The Dravo *Counterflo* combustion method takes place in a stainless steel combustion chamber. The exhaust gases from combustion are "whirl-cooled" through two sets of economizer tubes. This four-pass heat transfer results in a minimum heating efficiency of 80%.

2. One rotor shaft operates all heater fans, thus co-ordinating exhaust, air-intake and heat-discharge systems.

3. Air for combustion is provided by main supply fan; volume and velocity are controlled by an adjustable damper.

4. Approved by American Gas Association and listed by Underwriters' Laboratories, Inc.; Dravo Safety Control Circuit is accepted by Factory Mutual Engineering Division.

5. Burners are designed by Dravo Engineers for top efficiency. Heaters burn gas or oil; burners are interchangeable to take advantage of fuel savings by using the most economical source of supply or in times of shortage the most available fuel.



Dravo *Counterflo* Space Heaters in addition to comfort heating are easily adapted to heat curing and process drying, tempering of replacement air and summertime ventilation. Dravo Heaters can also be tied in with air conditioning systems by making use of the same ductwork.

Mail this coupon NOW for more information

Dravo Corporation, Heating Department
Dravo Building, Fifth and Liberty Avenues
Pittsburgh 22, Pennsylvania

Send me information about heating for the subjects I've checked, and Dravo Heater Catalog MN 52 -9102.

- ☐ Space heating warehouse, garages, hangars.
- ☐ Stores, schools and auditoriums.
- ☐ Process drying and heat curing.
- ☐ Tempering make-up air.
- ☐ Temporary heating.
- ☐ For use in conjunction with air conditioning.
- ☐ Please have a representative call at no obligation to me.

Name_____ Title _____

Company_____ Address_____

City_____ Zone_____ State_____

DRAVO

CORPORATION

PITTSBURGH • ATLANTA • BOSTON • CHICAGO • CINCINNATI
CLEVELAND • DETROIT • NEW YORK • ST. LOUIS
PHILADELPHIA • WASHINGTON

Sales Representatives in Principal Cities

Manufactured and sold in Canada by Marine Industries, Ltd., Sorel, Quebec. Export Associates: Lynch, Wilde & Co., Washington 9, D.C.

BLENDING IN A WELDED CORNER is a job you can do faster and better with a Norton BFR semi-flexible wheel.

Here's your "TOUCH OF GOLD" team for more economical portable grinding

CLEANING OUT FINS of a compressor casting is a hard job made easy — when you use a Norton BD rigid wheel.

There's gold in hub-wheel grinding — the real cost-cutting, value-adding "Touch of Gold" that you can bring to job after job with these faster, safer Norton Reinforced Hub Wheels!

They're the long popular Norton BD rigid wheel and the newer Norton BFR semi-flexible wheel. Beyond any doubt they're the most useful pair ever built for portable grinding. They're lighter and easier to handle than cup wheels, longer lasting than coated abrasive discs, and more versatile than either.

Built-in speed and safety

Made of aluminum oxide and silicon carbide abrasives, resinoid bonded, both the BFR and BD wheels cut fast and cool, without spalling or loading. And for tops in safety, they're reinforced with nylon webbing. Even if breakage occurs this strong web keeps pieces from flying off in all directions, until the machine can be stopped.

Covering a wide job range

Where finish is most important — especially for blending corners and contours — you'll like the way the semi-flexible BFR wheel hugs the work. Where stock removal is the main factor, you'll prefer the heavier duty, rigid BD wheel. And with both these wheels working for you, you have a grinding team that will help you turn out better products faster and easier — adding the profit-boosting "Touch of Gold" to countless every-day jobs.

NEW! . . . The Norton BF Wheel For Light Finishing

Meet the latest Norton development for your lighter finishing jobs. Basically, the new BF wheel is built like the BFR wheel but is designed especially for periphery grinding. You'll find its flexibility in the softer grades (G and I) ideal for blending and smoothing curved surfaces and corners. The hardest grade (K) is more rigid — best for light welds and sharp edge applications. In all grades it tends to finish as it cuts.

Like the BFR and BD wheels, the new BF wheel cuts fast and free and has a high safety factor. Like them, too, it features versatility, covering a range of usefulness that includes finishing stainless steel welds, deburring metal parts such as stampings and removing gates and fins from molded plastics. Let the new BF wheel add "The Touch of Gold" to many of your own light-duty grinding jobs.

GET YOUR NORTON DISTRIBUTOR TO DEMONSTRATE

these versatile Norton wheels in your shop. He'll be glad to help you on any grinding problem and, if necessary, he'll call in a Norton Abrasive Engineer. Or write to NORTON COMPANY, Worcester 6, Mass. for descriptive folder #225. Distributors in all principal cities. *Export:* Norton Behr-Manning Overseas Incorporated, Worcester 6, Mass.

W-1470

NORTON
ABRASIVES
Making better products to make other products better

Put the value-adding "TOUCH OF GOLD" into jobs like these



Cutting down a heavy weld — rigid BD



Blending a welded radius — semi-flexible BFR



Smoothing a flame-cut edge — rigid BD

Grinding welds in a fabricated cone — semi-flexible BFR

Smoothing a weld seam — semi-flexible BFR



Notching risers on gray iron castings — either type

There's only ONE TAPER-LOCK



TAPER-LOCK sheaves run true! The patented Taper-Lock bushing grips the shaft for the full length of the bushing—holds with the firmness of a shrunk-on fit!

Every belt pulls its full share of the load. Grooves, machined on precision equipment, have identical pitch diameters, assuring equal belt tension.

Easy on—Easy off. Slip it on the shaft, line it up and tighten while sighting. In ease and speed of mounting and demounting you'll appreciate there is only ONE Taper-Lock.

No flange, no collar, no protruding parts. Flush hub means safety.

Taper-Lock sheaves are available from distributors' stocks in complete range of sizes in A, B, C and D grooves.

DODGE MANUFACTURING CORPORATION
4400 UNION STREET, MISHAWAKA, INDIANA

1878 DODGE 75th ANNIVERSARY

DODGE
of Mishawaka, Ind.

CALL THE TRANSMISSIONEER, your local Dodge Distributor. Factory-trained by Dodge, he can give you valuable assistance on new, cost-saving methods. Look for his name under "Power Transmission Machinery" in your classified telephone book.

DODGE-TIMKEN PILLOW BLOCKS

TORQUE-ARM SPEED REDUCERS

ROLLING GRIP AND DIAMOND D FRICTION CLUTCHES

NAME PLATES

FOR YOUR NAME PLATE REQUIREMENTS, WRITE OUR SUBSIDIARY, CHICAGO THRIFT-ETCHING CORPORATION, 1555 N. SHEFFIELD AVENUE, CHICAGO 22, ILLINOIS



IT'S JUST THAT SIMPLE. There's only one reason in the world why 2 out of 3 wire rope users in the industrial field prefer Roebling wire rope... *it costs a lot less on the job than any other.*

For maximum wire rope efficiency and economy, call your nearest Roebling office for a Field Man. He'll recommend the best ropes for your operations.

J.A.R. ROEBLING

ROEBLING CF&I

A subsidiary of The Colorado Fuel and Iron Corporation

JOHN A. ROEBLING'S SONS CORPORATION, TRENTON 2, N. J. BRANCHES: ATLANTA, 934 AVON AVE. • BOSTON, 51 SLEEPER ST. • CHICAGO, 5525 W. ROOSEVELT RD. • CINCINNATI, 3253 FREDONIA AVE. • CLEVELAND, 13225 LAKEWOOD HEIGHTS BLVD. • DENVER, 4801 JACKSON ST. • DETROIT, 915 FISHER BLDG. • HOUSTON, 6216 NAVIGATION BLVD. • LOS ANGELES, 5340 E. HARBOR ST. • NEW YORK, 19 RECTOR ST. • ODESSA, TEXAS, 1920 E. 2ND ST. • PHILADELPHIA, 230 VINE ST. • SAN FRANCISCO, 1740 17TH ST. • SEATTLE, 900 1ST AVE. S. • TULSA, 321 N. CHEYENNE ST. • EXPORT SALES OFFICE, TRENTON 2, N. J.

you save money





you save time and labor



you get greater flow and capacity

when you specify light wall schedule 5 pipe

WHAT SCHEDULE 5 PIPE IS—
A light wall pipe, Carpenter Schedule 5 gives you more feet of pipe for every pound of scarce stainless steel. So you can quickly see how Schedule 5 reduces your cost per foot. Plus the fact that the larger I.D. means increased flow area.

HOW SCHEDULE 5 REDUCES COSTS
First saving is 40% to 50% on the cost of your pipe.

Since Schedule 5 is considerably lighter, this means quicker and easier installation.

And, because the increased capacity of Schedule 5 lets you use the next smaller pipe size, you can reduce substantially your costs of valves, fittings, etc.

FITTINGS ARE AVAILABLE
This pipe is easily adapted to use with existing lines of tubing or Schedule 40 and 10 pipe, using simple connectors. Fittings as well as stocks of Schedule 5 pipe are carried by conveniently located Carpenter distributors.

ADDITIONAL ADVANTAGES

Tubing sizes can now be replaced with light wall *pipe* . . . for ready hook-up with standard valves, pumps and other equipment which is normally manufactured in pipe sizes.

Data Sheets give you complete information about Carpenter Schedule 5 Stainless Pipe. Write for your personal copy. THE CARPENTER STEEL COMPANY, Alloy Tube Division, Union, N. J.
Export Dept.: The Carpenter Steel Co., Port Washington, N.Y. "CARSTEELCO"

Carpenter

STAINLESS TUBING & PIPE

- guaranteed on every shipment

for time-saving, money-saving

POWER DISTRIBUTION

SQUARE D FEED-IN DUCT

is the most efficient way to transmit large amounts of power. It provides the lowest known voltage drop—only 1.8 volts per 1000 amperes per 100 feet.

Exclusive design requires no ventilation—permits a totally enclosed, compact, dust-excluding enclosure. Rigid construction provides high resistance to heavy electrical stresses.

SQUARE D PLUG-IN DUCT

provides flexible power distribution for branch circuits. Machinery can be rearranged quickly at minimum cost. Plug-in units can be attached at frequent intervals along the length of the duct, providing power where it's needed, when it's needed.

BUSWAY FEATURES PROVE DESIGN LEADERSHIP



NEW JOINT DESIGN. Feed-in Duct joint design saves installation time and reduces maintenance cost. Duct ends are identical—unnecessary to select mating ends before positioning or hanging duct sections. Outward-facing, pre-installed bolts permit rapid assembly and easy maintenance.

ROUND BUS BARS for Plug-in Duct provide greater mechanical strength and resistance to short-circuit stresses. Circuit breaker or fusible type plug-in units are easily installed at 2-foot intervals along both sides of the duct. Plug-in stabs grip the round bus bars with exceptionally high pressure.

FLEXIBLE CONNECTORS of laminated copper join bus bars between sections—permit proper alignment, insure tight joints and provide for expansion and contraction at Plug-in duct joints. All bolt heads face outward for greater accessibility.

ASK YOUR ELECTRICAL DISTRIBUTOR FOR SQUARE D PRODUCTS

SQUARE D COMPANY

1903 • 50 YEARS OF DESIGN LEADERSHIP • 1953

SIZE IDENTIFIED ASSEMBLY SIMPLIFIED

The Only

SIZE-MARKED GEAR GRIP SOCKET HEAD CAP SCREW

The size is clearly incised on the head, can be seen at a glance. It prevents errors by "green" workers, helps veterans also to speed assembly. It saves time and wasted screws when sizes get mixed up.

It's a sales feature for your product. Your customers' maintenance men will like the Size-mark . . . it aids them in reassembling after servicing. Gear Grip prevents slips, speeds work, even when fingers are oily.

Since there is no better Socket Head Cap Screw made, why not get these important extra features offered only by P-K? Ask for samples. Parker-Kalon Corp., 200 Varick St., New York 14, N.Y.

FOR ANY TYPE SOCKET SCREW—
REMEMBER

IF IT'S P-K IT'S O.K.
TRADE MARK
REG. U.S. PAT. OFF.

PARKER-KALON®

Sold through Industrial Distributors, the Supply Specialists that serve you

Cold-forged **SOCKET SCREWS**





"With Udylite equipment we get tough, durable metal finishes that are *always* uniform. That means fewer rejects—lower costs." That's the experience of Michigan Chrome & Chemical Co. with Udylite Equipment. They do a wide variety of plating . . . and they know Udylite equipment speeds production—allows them to shift quickly and economically from one job to another—as well as keeping rejects to a minimum. Udylite equipment and machines can do the same for you in your metal finishing operations. Call your Udylite technical man today. Let him show you Udylite methods of better plating. Learn how you can up production—cut costs—increase profits!

EQUIPMENT
SUPPLIES
RESEARCH

THE Udylite CORPORATION
DETROIT 11, MICHIGAN

PIONEER OF A BETTER WAY IN PLATING

true and accurate as B&L ground and polished shafting



Many economy-minded firms are meeting today's top specifications at new low costs by taking advantage of the precision-plus qualities of B&L Ground and Polished Shafting. This prime material insures easier manufacturing all along your production line. It provides a smooth, mirror finish which saves machining time where the bar surface is retained in the completed work. Its consistent close tolerances in size, straightness and roundness save time in assembly and assure accurate and uniform finished products for cut-from-the-bar parts or precision shafts. Keep down your costs by using B&L Ground Bars that come to you properly cold worked and accurately sized and finished for your products.

Also COLD DRAWN SHAFTING; DRAWN, GROUND AND POLISHED; TURNED, GROUND & POLISHED. Standard or special Analysis. Plain or Furnace-Treated including Strain-Tempered.

BLISS & LAUGHLIN, INC.

GENERAL OFFICES: HARVEY, ILLINOIS

SALES OFFICES IN ALL PRINCIPAL CITIES

FOUR PLANTS: HARVEY, ILL. • DETROIT, MICH. • BUFFALO, N. Y. • MANSFIELD, MASS.

SINCE 1891



For rugged steel mill service

Steel mill service demands rugged performance in a crane — three gruelling shifts a day, 365 days a year — with no time down for maintenance. This calls for a truly extra heavy duty crane such as this 50-ton, 75-foot span crane servicing an electric furnace in a large Western steel mill. It is one of many cranes EDERER has "job-engineered" to the specific requirements of the steel industry.

EDERER — one of the largest crane manufacturers in the West — can "job-engineer" a crane to your requirements. Delivery can be made to meet your schedule for plant expansion or new construction.

Write for Crane Bulletin CR-500

223C53

EDERER

CRANES

ERER ENGINEERING COMPANY • 2931 First Ave. So. • Seattle 4, Wash.

Export Division: 301 Clay St., San Francisco 11, Calif.

ER 50 YEARS "JOB-ENGINEERING" CRANES FOR INDUSTRY

ANNOUNCING A NEW

Gerrard Tying Machine...

FULLY AUTOMATIC B.S.M. TWINE SEALING MACHINE

• Here's a new, completely automatic tying machine that m fill a need in your plant . . . the Gerrard B.S.M. Twine Sealin Machine. Just place the bundle in the tying area, step on t pedal, and in three seconds, the twine is wrapped around t bundle, drawn to a pre-set tension, securely fastened with *metal seal,* and cut. The bundle is firmly gripped and the will remain neat, strong and tight until the twine is cut. Seve ties can be put around a bundle as quickly as it can be mov into position.

Look around your mailing or shipping department. The may be several spots where a Gerrard B.S.M. Twine Sealin Machine can save you time and money, and do a better tyin job at the same time.

SEND FOR FOLDER DESCRIBING THE GERRARD TWINE SEALING MACHINE. IT'S FRE

THE GERRARD B.S.M. TWINE SEALER IS completely automatic, make a 1-cycle wrap, and secures the twine with a metal seal so firmly that twine will break before the seal will slip. Bundles are limited to a width and a 9" height.

On heavy tying jobs... be safe... save money... use Gerrard Steel Strapping

• Gerrard Round Steel Strapping, in 8 to 18½ gauge, was designed for safe, dependable, easy strapping of small packages, larger cartons and crates, heavy cases, pallets, and for reinforcement of carload lots of steel pipe, plates, sheets and machinery. With Gerrard's hand-operated machines, or the semi-automatic Model Q, you can make firm, tight closures or secure reinforcements that will keep your shipments safe from plant to destination. And Gerrard Round Steel Strapping costs about 40% less than any other metal reinforcement.



BRAKE DRUMS are palletized for inter-plant shipm a good example of what can be done with small, o shaped units. 10 gauge Gerrard Round Steel Str ping holds the pallets securely.

ASK US FOR FULL INFORMATION

Phone, write or wire for further information about the Gerrard Method of Steel Strapping or of Twine Sealing. A Gerrard engineer will gladly call, without obligation, to discuss your packaging and bundling requirements. Also ask for a free copy of the Blue Book of Packaging.

GERRARD STEEL STRAPPING DIVISION, UNITED STATES STEEL CORPORATION
4745 South Richmond St., Chicago 32, Ill.

U·S·S GERRARD STEEL STRAPPIN

USS

UNITED STATES STEEL

MORE AIR Per Horse Power

- IT'S TWO-STAGE
- IT'S AIR COOLED
- SELF OILING



The New Curtis

MODEL 98 AIR COMPRESSOR

TWO-STAGE AIR COOLED 15 AND 20 HORSEPOWER

TWO-STAGE — More air per kilowatt hour, assuring savings in power bill.

AIR-COOLED — No expensive water bills; eliminates plumbing installation costs.

INTERCOOLER — Four section, finned, providing unusually effective cooling between stages; cooled by cyclone of air from fan flywheel.

SELF OILING — Simple, positive centro ring method; provides pressure lubrication of connecting rod and pistion pin bearings.

TWO TIMKEN MAIN BEARINGS — Tapered rollers; provide easy adjustment made externally without dismantling compressor.

VALVES — Readily removable as assembled units without removing cylinder head or breaking pipe connections or gasket joint.

CRANKSHAFT — Counterbalanced, drop forged — two main bearings — no overhung bearing.

PRECISION WORKMANSHIP — Assures long life and minimum maintenance.

EXPERIENCE — Backed by 99 years of manufacturing — assures you dependable, troublefree service.

Available as a simple compressor or base mounted — motor driven.

LET ONE MAN DO THE WORK with this Curtis air-operated equipment.



AIR CYLINDERS — for almost any pushing, pulling or hoisting operation.

AIR HOISTS — for low-cost lifting or lowering of materials or machines.

-726

CURTIS PNEUMATIC MACHINERY DIVISION
of Curtis Manufacturing Co.
1996 Kienlen Avenue, St. Louis 20, Mo.

I am interested in items checked below:

☐ THE NEW MODEL 98 ☐ AIR HOISTS ☐ AIR CYLINDERS
☐ AIR COMPRESSOR

Name.....

Firm.....

Street.....

City.....Zone....State.....

CURTIS PNEUMATIC MACHINERY DIVISION of Curtis Manufacturing Company

1996 KIENLEN AVENUE ST. LOUIS 20, MO.

STEEL WOOL bursts into flame under a jet of fluorine gas in an experiment at The Whitemarsh Research Laboratory of The Pennsylvania Salt Manufacturing Company.

When Metal Bursts into Flame

Imagine, if you can, an element so fierce it burns up steel. One that claws its way through fire-brick . . . makes water burn like alcohol . . . destroys almost everything it touches.

That's fluorine for you!

And for over two hundred years chemists racked their brains to find some material that would hold fluorine. Hold it for even a few minutes' study.

Numerous materials — all considered dependably resistant to corrosion — were tried. Most went up in a flash.

Some few seemed to work, momentarily. But let temperature rise a trifle, or pressure build up . . . or a trace of moisture seep in . . . then dig out the wreckage and start over.

Finally Nickel and its alloys were tried. They work. They last for months where other materials failed in days or weeks.

Today, you find Nickel and Inco Nickel Alloys in equipment that produces fluorine . . . in pumps and piping and valves where fluorine is compressed, stored, and processed. Nickel and Inco Nickel Alloys hold fluorine, even under heat and pressure. By the way, if you would like to know more about fluorine, ask us for a copy of "Fluorine Makes Its Debut."

When <u>you</u> have a metal problem

If it's corrosion, it can't be any tougher than that caused by fluorine . . . and the solution may be found in Inco Nickel or one of the Inco Nickel Alloys.

Inco corrosion engineers are ready to help you. They've prepared a Corrosion Data Work Sheet to make it easy for you to outline your problem to them. Write for it, without obligation, of course.

• • •

Or perhaps your metal problem concerns temperatures—high or low . . . stresses or fatigue resistance. Whatever it may be, Inco engineers will gladly help you find the answer. The International Nickel Company, Inc., 67 Wall St., New York 5, N. Y.

Inco Nickel Alloys

Monel® • "R"® Monel • "K"® Monel "KR"® Monel • "S"® Monel • Nickel Low Carbon Nickel • Duranickel® • Inconel® Inconel "X"® • Incoloy® • Nimonics®

March 9, 1953

Big and Early

Iron ore shippers are looking forward to what may be their biggest season and earliest opening in history. Freighters will start plying the upper lakes by Mar. 15. The goal for 1953 is 103 million tons of ore. Previous record was about 92 million tons in 1942. Last year, with two months lost due to the steel strike, shipments were 75 million. Ice conditions on the upper lakes are much better than usual and many freighters already are being manned in readiness for early sailings.

No Slackening

A. F. Franz, Colorado Fuel & Iron president, adds his voice to those steelmakers who predict capacity operations through 1953. Mr. Franz is confident that operations in the West will be maintained at full capacity. The picture in the East may be a little softer, with some easing in wire demand later in the year.

Pop in Cans

Major can producers are casting covetous eyes at the soft beverage market. Cans now are being made for large-scale consumer testing this summer. The unknown quantity is the reaction of pop drinkers. Pepsi-Cola is supporting a consumer research program. If the idea of pop tin cans takes hold, it may open an important new market for tin plate.

Labor "Korea" in Detroit

Labor observers in the automotive capital believe major auto builders may try to stall the United Auto Workers-CIO at the bargaining table while production is pushed hard this spring. By May or June they could have a fair backlog of cars and be in a stronger position to resist heavy union demands.

Price of Being Basic

Prolonged subjection to government price controls is the price the steel industry is paying for being so basic to our economy. While price controls have been lifted from various other materials and products, they still remain on steel. An exception is the charge for conversion of steels. It was decontrolled last week. A general increase in steel prices is not in the cards, but you can look for some adjustments, most of them upward, needed to correct imbalances that have arisen in a price structure made rigid by government controls. Growing competition will help keep any increases moderate. Already a few sellers have shaded prices.

We'll Still Have Controls

Government controls on distribution of steel, copper and aluminum will not disappear entirely on June 30 when the present Defense Production Act expires. Enough controls will be retained to assure

roduction-Engineering News—p. 93 The Market Outlook—p. 175

materials for military and atomic energy requirements. Under consideration in Washington are three systems for giving priority to defense requirements after June 30: 1. A simple DO (defense order) rating band. 2. A "little CMP." 3. A programming set-up in which task forces from the steel, copper and aluminum industries would confer with the armed services, AEC and other qualified claimants to ascertain requirements and parcel them out on the basis of capacity relationships of the various producers. In effect CMP will be open-ended for all civilian uses of steel, copper and aluminum. Now it's open-ended only for any portions of these materials produced in excess of military needs and CMP allotments to civilian users.

Advisory Groups To Stay

National Production Authority will be continued after June 30, although it will be cut down substantially from its present size. This means that the 554 industry advisory committees with more than 7000 industrial members will be maintained. The industry committees at present are the most important means of government-industry cooperation.

FTC Leans Republican

Republicans will gain a three-to-two majority in the Federal Trade Commission next September when a successor to Stephen J. Spingarn is appointed. Last week President Eisenhower nominated Republican Edward F. Howrey, Washington attorney, to a seven-year term. Mr. Howrey is a specialist on antitrust and corporation law.

Straws in the Wind

You may list as income tax deductions retroactive payments of wage and salary increases agreed on during the control period but not put into effect until after decontrol . . . Detroit area soon will get more locally-produced cold-finished bars: Bliss & Laughlin will open a new plant there next month . . . The Air Force, which halted all disposal of its excess equipment at the outbreak of the Korean war, will resume sales of such equipment.

What Industry Is Doing

Steel warehousemen are looking forward to a year of satisfactory operations (p. 65) . . . Expansion projects by Bethlehem Steel and Youngstown Sheet & Tube will boost the nation's iron and steelmaking capacity (p. 66) . . . Warehouses and automotive companies in 1952 took 36 per cent of the steel shipped from mills (p. 68) . . . A new organic coating—hard enough for home appliances, yet flexible enough for application before the metal is formed—has been developed by Glidden Co. (p. 68) . . . Hazards lurk for defense producers in the Air Force's ruling on contract terminations (p. 70) . . . Machine tool builders expect improved backlogs now that they may work on unrated orders for Appendix D tools as NPA amends its Order M-41 (p. 71).

High strength for light structurals with Armco Welded Tubing

Armco Welded Steel Tubing provides a tailored-to-order steel for light structural applications that gives you an excellent combination of high strength per pound and attractive appearance.

Within practical limits, the larger the tube or special section and the lighter the wall thickness, the greater is its structural efficiency.

For example, a welded steel tube and a standard steel pipe serve as a basis of comparison. The tube tested here is 2¼-inch outside diameter with 18 gage (0.049-inch) wall thickness; the standard steel pipe has an outside diameter of 1.05 inches, a wall thickness of 0.113-inch. Both tube and pipe are about the same weight.

WHEN LOADED AS A BEAM



The 1.05-inch diameter pipe on 4-foot centers will deflect 0.211-inch under a 100-pound load.



But the 2¼-inch diameter tube on the same centers will deflect only 0.038-inch under the same load.

LESS THAN ONE FIFTH THE DEFLECTION WITH THE SAME AMOUNT OF STEEL!

(Besides having lower deflection the welded tubing has about two and one-half times the safe load-carrying capacity of the pipe.)

WHEN LOADED AS A COLUMN

The 1.05-inch diameter standard pipe has a safe load-carrying capacity of only 533 pounds.

While the 2¼-inch diameter welded tube can carry a load of 2920 pounds with safety.

MORE THAN FIVE TIMES THE LOAD-CARRYING CAPACITY WITH THE SAME AMOUNT OF STEEL!

If you are not familiar with the many applications for Armco Welded Steel Tubing, or the methods of assembling it, write for these booklets: "Armco Welded Steel Tubing" and "How to Fabricate Armco Tubing."

ARMCO STEEL CORPORATION

2233 Curtis Street, Middletown, Ohio

Export: The Armco International Corporation

1
LOW INITIAL COST
2
SIMPLE CONSTRUCTION
...easy to maintain
Good Reasons for Specifying
EC&M Control for Skip-Hoists
In addition to low initial cost and simple, easily maintained construction, EC&M Control gives highly desired flexibility and top-notch efficiency on the straight part of the skip-incline. It also provides utmost accuracy in stopping.
When building new furnaces or modernizing existing installations, consult with EC&M, without obligation, of course.
THE ELECTRIC CONTROLLER & MFG. CO.
2698 EAST 79th STREET • CLEVELAND 4, OHIO
E&M

Signal for a Change

What happens as a result of the incapacitation of Premier Joseph Stalin can be of the utmost importance to the United States. Ever since the Bolshevist revolution, democratic nations have found it increasingly difficult to deal with the Soviet rulers. Each change of premiers has precipitated new problems in world relationships and there is every reason to expect that the shift of power from Stalin to his successor will be accompanied by similar, if not more troublesome, repercussions.

In considering future relations of the United States with Russia it is well to remember the difficulties of the past. Through the thirties and the first half of the forties, the leading democratic nations were compelled to deal with an unprecedented number of powerful dictators. In the period when Hitler, Mussolini, Hirohito and Stalin were in the ascendancy, their technique of direct, personal action in handling foreign relations put a terrific strain upon the state departments or foreign offices of free nations.

As a natural result of this, it became more and more the practice of the leaders of western powers to deal personally with the dictators. Fateful examples were the attempts of Prime Minister Churchill and Presidents Roosevelt and Truman to negotiate with Premier Stalin by means of personal conferences at Yalta and Potsdam. Today there is widespread opinion that serious mistakes were made by our representatives at these conferences.

In light of these mistakes and of other instances where our relations with Russia have been unfortunate, it would seem that the departure of Premier Stalin from office should be the signal for a complete change in our methods of dealing with the ruler or rulers of the Kremlin.

We would like to think that no American President again will go into a huddle with a Red dictator with the cocksure feeling that by personal charm he can "get along with" him or outwit him.

Henceforth, let all of our dealings with the Kremlin be out in the open, so that the Congress and the people can know what is going on and so that no "secret" understandings can be reached.

E. L. Shaner

EDITOR-IN-CHIEF

AMERICAN INSTITUTION: During the past half-century, trade associations have grown in number and in influence to the point that today they are recognized as one of the most important institutions in the American industrial system. From 250 in 1910 (p. 76), trade associations have grown in number to 1600 in 1953, of which 425 are serving the metalworking industry.

The secret of the success of a trade associa-

tion is simple. Assume that there are 100 companies manufacturing a certain product. Somebody suggests that they form an association. About 65 of the 100 join as charter members. If the association is well managed, it soon becomes apparent that there are many things which members can do co-operatively which none of them could afford to do individually. Membership grows until only a negligible minority of eligible companies remains outside.

A good trade association helps members solve many internal problems but in most cases it also does a good job of making the government and the public cognizant of the importance of the group it represents.

* * *

TRADE PLAN DUE SOON: In 1952, U. S. exports totaled $15.2 billion, a new all-time high. In the same year imports climbed to $10.7 billion. Of the $4.5 billion excess of exports over imports (p. 75), about $2 billion represented shipments of military equipment to friendly nations to help them to meet the threat of Communism.

How to increase imports is one of the most pressing problems of the Eisenhower administration. Its foreign trade policy should be pretty well formulated before the Reciprocal Trade Agreements Act expires on June 12. The administration seems to favor the principle of low tariffs but with the hedge that provision must be made to limit the adverse effects upon domestic production in certain industries.

Perhaps the picture is distorted by an excess of publicity on such items as briar pipes, watches and cheese. Possibly more serious attention to imports of certain strategic materials of which there is no domestic source of supply might help to outline the problem in clearer perspective.

* * *

TREND AGAIN IS RISING: Sharp-eyed observers will have noticed that industrial activity has taken a new lease on life. About three weeks ago production in the metalworking industry was in a sidewise movement. Since then it seems to have managed to get off dead center and has been moving ahead rapidly.

U. S. output of passenger cars and trucks in the last week of February was at the highest level in 21 months. Electricity output (p. 83) is running about 10 per cent ahead of comparable weeks a year ago. Steel ingot output has risen above the 100 per cent of capacity mark and is within range of new records almost any week. Revenue freight car loadings remain the only weak sister of the four basic indicators. They lag about 4 per cent behind those of a year ago.

* * *

INCOME SPREAD WIDELY: At the 13th Freedom Forum held recently at Harding College at Searcy, Ark., simplified figures were presented as to the distribution of national income. The breakdown showed that 65 per cent goes to employees, 9 per cent to professional men and unincorporated business, 7 per cent to farmers, 4 per cent to landlords, 4 per cent to stockholders, 4 per cent to bond holders and other lenders, 2 per cent back into the business for expansion and 5 per cent to taxes.

Another interesting fact, derived from research conducted by the University of Notre Dame, is that 73 cents out of every dollar of interest, dividends and rent payments to individuals go to people with less than $100-a-week incomes. Figures of this kind reflect a widespread distribution of income, which is one of the nation's greatest assets.

* * *

THEY SEE THE LIGHT: Norman Thomas—perennial candidate of the Socialist party for President of the United States—sometimes impresses radio listeners by the restraint with which he advocates his beliefs. Recently he issued a pamphlet entitled "Democratic Socialism—A New Appraisal," which is significant from several angles.

For one thing, he confesses that many of his ideas have been proved false. "The working class is not the Messiah which some of us thought." Capitalism is not necessarily the cause of war, nor is Socialism "a panacea against war." State ownership should not be carried too far, because big government under any auspices becomes oppressive.

Here is an honest confession of disillusionment. It does not mean that he renounces his basic tenets in entirety. It means he adjusts them in conformity with reality. Conscientious advocates of this or that "ism" should follow his example.

VALLEY MOULD AND IRON CORP.

General Offices: HUBBARD, OHIO

Western Office: Chicago, Ill. • Northern Office: Cleveland, O.

For Special Operations in Steel Mills...



STAMCO 80" Side Trimming Unit



STAMCO Coil Box, coil opener and feeding unit

Call or write

Stamco

for the equipment you need

For mill or warehouse use on ferrous or non-ferrous material, STAMCO has a model or size to fit your needs—or can make it for you If you use trimming units, plate shears, slitting units, coil openers or any other special steel mill equipment, it will pay you to write us. No obligation.



STAMCO 1¼" x 180" plate shear



STAMCO 48" Slitting & Coiling Line 15000# coil capacity



STAMCO 72" Heavy Gauge Side Trimming and Slitting Unit equipped with a double set of feed and delivery pinch rolls.

STAMCO, Inc., New Bremen, Ohio

STEEL WAREHOUSES: Business Still Good



Ryerson

Steel Warehouse Inventories*



* American Steel Warehouse Association survey of 112 companies with 197 warehouses.
† Considered normal by most members of the industry.

TEEL WAREHOUSEMEN in eneral are looking forward to an- her year of satisfactory oper- ions. Demand is substantial— t least on a par with six months go—and inventories are averaging 5 per cent of normal, which is early back up to the level of ept. 1, 1950.

However, not everywhere is the ıture so bright. Imbalance con- nues to plague almost everybody, nd some areas are still starved or many items.

Demand Holding Up—Although here are exceptions, most ware- ouse operators report that de- ıand is comparable to September, 952. There is some easing in cer- ain areas, part of which is sea- onal, but the general level of usiness is still high. In other reas, such as Detroit and the outh, demand is considered higher. n the former, the heavy demands f the auto industry keep the warehouses hopping, but in the South, a traditional lack of facilities accounts for much of it.

The table above, which represents about 60 per cent of the nation's steel warehouse business, indicates that inventory tonnages are climbing back to a more normal level. But again, individual inventory positions depend on location and other factors. For instance, southern firms must compete with northern houses for most of their products which are produced in northern mills. Consequently, they have only a 30 per cent normal stock, and that is badly imbalanced.

Same Old Story—Imbalance continues the main characteristic of practically every warehouse, even those with good tonnage inventory. Some of the "critical" materials are reported taking up far too much storage space, mainly because they are so closely controlled that few persons can buy them. Nickel-chrome stainless is one example. Alloy steels are reported in good supply, but there is not enough equipment available to heat treat them.

Choosy—A sign of better things to come is the fact that many dealers are getting choosy about what they accept from the mills. After the steel strike, they took anything the mills shipped them, but not so now. On the other hand, they still find most items are hard to come by. Still in tight supply are the heavy articles: Plates; structurals — especially wide-flanged beams; large bars, rounds and flats. Both cold-rolled and hot-rolled sheets and some seamless tubing are critical.

Detroit seems to hold the answer to the sheet problem. If automakers succeed in selling all the cars they can make, sheets will continue to be tight. If not, an

easing should show up by midyear. Midyear could see also a break in heavy plate and structurals.

Who Wants Galvanized?—About the only item in good supply practically everywhere is galvanized sheet. Rumors of price weaknesses on that have shown up in some areas.

As the warehouse position returns more to normal and competition becomes keener, a problem vexing the dealer is what to do about the mill buyers who turned to the warehouse as an emergency measure. At present, there is little loss of those customers, because the mills still cannot handle them well enough. However, their pounds per order are falling off.

A Matter of Service—Many warehousemen feel that they will retain at least a portion of that business. They take pride in the services warehouses can offer which mills cannot. They point to the high cost of storage which quantity buying from the mill involves. But others, perhaps more realistically, realize that some manufacturers cannot afford the extra costs.

The job of retaining as many of those accounts as possible and getting new ones as competition returns will fall to the sales staffs. Most dealers are stepping up their sales efforts, although few will admit that they were ever curtailed even when there was nothing to sell. Not many new men will be added, but the old timers will have to dig deeper. Few of them ever sold in a truly competitive market, so they will have to be re-educated in some cases.

Stimulus—The return to competitive markets, nearly everyone feels, could be hastened greatly by the quick and complete end of CMP. Especially older and bigger warehouses which have stronger historical ties with mills feel that they should be allowed to stock as much of an item as they need and can get through regular business channels. However, the newer and smaller dealers hesitate to condemn CMP for fear they will lose out in the shuffle. John Doxsey, assistant to the president of the American Steel Warehouse Association, says there is some sentiment in and out of the industry for a "Little CMP" to replace the present plan.

Youngstown Sheet & Tube lights new furnace as . . .

Two Companies Conduct Expansion Programs

EXPANSION projects at two steel companies will boost the nation's iron and steelmaking capacity.

Bethlehem Steel Corp.'s annual capacity will rise from a current 17.6 million tons to at least 19 million tons when present expansion and modernization is completed. Meanwhile, Youngstown Sheet & Tube Co. lighted its No. 3 blast furnace at the Indiana Harbor Works, East Chicago, Ind.

At Indiana Harbor — Youngstown's new furnace is the third major unit to go into production since the company launched its building program at Indiana Harbor in 1950. The furnace is 105 feet high and has a 28-foot diameter with a rated capacity of 1500 tons a day. It is equipped with three stoves for preheating air.

An open hearth department of eight 250-ton furnaces went into production last May at Indiana Harbor and a 75-oven coke battery began production last fall. A blooming mill and a cold rolling unit are under construction.

Bethlehem Improvements — Expansion at Bethlehem plants includes two blast furnaces at Bethlehem, Pa., and one at Sparrows Point, Md., as well as additional coke oven capacity at four manufacturing plants and miscellaneous additions to finishing facilities.

Spokesmen of Bethlehem Steel Corp. say that increased facilities cannot indefinitely offset mounting costs of recent years. Despite the reported expansion, they point out that costs lowered the net income per dollar of sales from 8.5 cents in 1950 to 5.9 cents in 1951 and 5.3 cents last year.

CF&I To Improve Facilities

Colorado Fuel & Iron Corp., ninth largest steel producer in the U. S., is planning to spend $20 million on production facilities in the next few years. Most of this outlay will be used to improve currently-owned facilities, rather than to purchase new companies, says C. F. Franz, president.

The corporation in a recent expansion program spent $30 million on new production facilities. Much effort went toward product diversification. C F & I in 1930 devoted 70 per cent of its finished steel production to rails and fastenings; this figure is now 15 per cent, due to development of other products. Rails and fasteners are still the largest items, however.

Soon to contribute to the diversification effort will be a seamless tube mill at Pueblo, Colo., the only such mill west of the Mississippi. This mill is scheduled to start operating in September of this year.

lot Squeeze Put on Tough Alloys

National Tube uses the Ugine-Sejournet process to produce seamless tubing and special shapes from high-alloy steel. Monthly production is expected to reach 2000 tons

IGH-ALLOY stainless steel tub-g and shapes are being "hot ex-uded" by the Ugine-Sejournet rocess at U. S. Steel Corp.'s Na-onal Tube Division plant in Gary, id.

"Using this operation, the Gary lant can now produce seamless ibing from nonpierceable grades stainless steel and extrude un-sual shapes that defied all roll-g methods because of their un-alanced design," says J. E. Goble, resident of National Tube Divi-on. Production is expected to be bout 2000 tons of tubing and hapes a month, he adds.

Plastic Steel — The process queezes steel slugs heated to bout 2250° F to make them plas-c with the pressure coming from 2500-ton hydraulic press that rces the steel through a forming ie. Pressures and working tem-eratures are so high that glass is sed as a lubricant (see STEEL, une 2, 1952, p. 92).

Steel billets, supplied by other J. S. Steel mills, are cut by four ircular saws, weighed, and in ome cases the leading ends of the slugs are chamfered. For production of small stainless steel tubing, the slugs also must be drilled on one end to help the steel flow in the press. To handle the slugs by overhead conveyor, a specially headed flux-filled stud is welded to the end of each slug by the stud welding process (see p. 110).

Before the Squeeze—Slugs pass through a 3-zone, gas-heated furnace, producing maximum temperature of 2400° F, and through a barium chloride bath, where temperatures up to 2300° F can be maintained. From the salt bath, slugs are conveyed to a charging buggy and the welded stud is cut off with an air-driven chisel. A sheet of glass fiber wraps around the slug as it rolls into position before the press.

Before extruding pressure is applied, the slug case is packed with sandwiches of woven, pane, spun or other forms of glass, depending on the type of extrusion and composition of the steel. In addition, a knitted fiber-glass "stocking" is fitted to the mandrel which pierces and shapes the inside of the tube as it travels through the die. Heat and pressure reduce the glass to a viscous liquid which serves as a lubricant.

No Hot Fingers—The extruded product leaves the die by means of an outlet conveyor and can be dropped into a water-quench tank or onto an air-cooling rack. Both the press and its auxiliary equipment are fully instrumented and all controls are automatic.

At present the press is capable of producing seamless tubing 1½-inches to 5⅛-inches in outside diameter, though, with additional tooling, sizes up to 6¼-inches are possible.



PREPARING TO EXTRUDE HIGH-ALLOY STEEL
. . . "glass stockings" on the mandrel help the flow

McKee To Build Blast Furnace

Arthur G. McKee & Co., Cleveland, has contracted to build for the American Steel & Wire Division of United States Steel Corp. what is expected to be the world's largest merchant iron blast furnace. The new unit, with an estimated capacity of 1350 tons per day, will be constructed at AS & W's Central Furnace & Docks Plant in the Cuyahoga valley.

Name Steep Rock Manager

A. J. Cayia, manager of Inland Steel Co.'s iron mines and quarries, will direct development of the company's $50-million iron ore project in Steep Rock lake, northwestern Ontario. Inland has leased the property from Steep Rock Iron Mines Ltd. (STEEL, Mar. 2, p. 61).

Write-Off Certificates Issued

Office of Defense Mobilization in the two weeks ended Feb. 25 issued certificates of necessity for rapid tax write-offs on 233 new or expanded defense facilities, valued at $334.6 million. Among the largest certificates were those to Kaiser Aluminum & Chemical Corp. and United States Steel Corp. Kaiser received an amortization certificate to build at Mentor, Ky., an aluminum plate and sheet mill valued at $66,052,000, with 50 per cent allowed. U. S. Steel Corp. was issued a certificate for expansion at Two Harbors, Minn., of iron ore sintering facilities, valued at $60 million, with fast write-off on 65 per cent.

Who Got the Steel

Warehouses and automakers accounted for over one-third of last year's shipments

THE TWO biggest takers of steel from this country's mills continued in 1952 to be warehouses and the automotive industry.

A compilation by the American Iron & Steel Institute shows warehouses received 19.8 per cent of mill shipments of 68,003,612 net tons of finished steel in 1952. The automotive industry got 16.2 per cent. These percentages gave warehouses 13,327,799 tons of finished steel, the automotive industry 10,852,075 tons.

In 1951, warehouses received 18.5 per cent of mill shipments and the automotive industry, 16.7 per cent.

More for War—Continuation of the Korean war is reflected in shipments for ordnance and other military. This classification's share in 1952 was 3.1 per cent, compared with 1.5 per cent in 1951.

The portion going into export rose from 3.6 per cent in 1951 to 4.9 per cent in 1952.

Total mill shipments of 68,003,612 net tons in 1952 were off, because of strikes, nearly 11 million tons from the record year of 1951. While the loss of production time was 16.7 per cent of the year, shipments were off only 14 per cent from 1951, reflecting the rapid post-strike recovery.

Reflection of Controls—Analysis of the 1952 shipments by products reveals the effect of the defense program and government controls on steel distribution. Bars and semifinished steel made up a greater proportion of total shipments in 1952 than in 1951 as a result of the emphasis on ordnance. Pressure tubing, essential for industrial power plant expansion and various military items, showed an increase in tonnage over 1951.

Casualty—Light flat-rolled products in general were reduced in their proportion of total shipments, corresponding to the reductions to the automotive and other consumer goods markets. Furthermore, the facilities for rolling light flat products were used to a large extent in production of plates for defense needs.

Details on distribution of finished steel in 1952 to market groups are shown in the table.

WHERE THE STEEL WENT IN 1952

Mill Shipments of All Grades of Finished Steel

MARKET CLASSIFICATION	NET TONS	% TOTAL
Steel for converting & processing	3,040,819	4.5
Forgings (other than automotive)	1,437,436	2.1
Bolts, nuts, rivets & screws	1,300,862	1.9
Warehouses	13,327,799	19.8
Construction, incl. maintenance	7,800,753	11.6
Contractors' products	2,609,809	3.9
Automotive	10,852,075	16.2
Rail transportation	3,987,118	5.9
Shipbuilding & marine equipment	1,027,064	1.5
Aircraft	137,275	0.2
Oil & gas drilling	770,255	1.2
Mining, quarrying & lumbering	311,703	0.5
Agricultural	1,347,835	2.0
Machinery, indust. equip. & tools	3,791,528	5.7
Electrical machinery & equip.	1,605,448	2.4
Appliances, utensils & cutlery	1,362,886	2.0
Other domestic & comm'l. equip.	1,562,856	2.3
Containers	5,546,781	8.3
Ordnance & other military	2,096,711	3.1
Total domestic	63,917,013	95.1
Export	3,269,624	4.9
Total	67,186,637	100.0
Shipments of nonreporting companies	816,975	
Total shipments	68,003,612	

Source: American Iron & Steel Institute.

Porcelain paint in twist test shows . . .

Super Organic Finish

COMBINATION of durable qualities reach an all time-high for an organic coating in Glidden Co.'s new silicone resin base finish.

Known as Nubelon S, the finish is harder, tougher and yet more flexible than existing ones. Manufacturers of metal products have long sought a coating that combines surface hardness for abrasion resistance with flexibility. Tendency in the past was to lose hardness with an increase in flexibility.

Glidden chemists overcame the problem with an unusual modification of silicone resins. Results: A baking enamel hard enough for use on home appliances yet flexible enough to permit application before the metal is formed.

Figures Speak—Extent to which the new coating maintains its color under severe conditions and its extreme hardness and adhesion make it especially valuable as a white appliance finish. Taber Abraser wear tests give only 30 milligrams loss per 1000 revolutions. Tests of high quality alkyd-amine baking enamels show 66 to 100 per cent greater loss.

The new finish shows no appreciable corrosion after fog tests in 20 per cent salt spray for 400 hours at 95° F. Actual figures: 0.03-inch creepage in 400 hours. Exposure in a standard humidity cabinet gives no change in 400 hours. Basis of the tests are on

coat of the new finish compared with a high quality two-coat alkyd-amine system.

The coating resists staining of dyes, including mustard—one of the most annoying stains with which home appliance manufacturers must deal—and lipstick, coffee, fruit acids, hot soap and hot grease. Another point of interest—heat resisting properties look good.

Where to Look—Characteristics of the finish recommend it for applications such as kitchen and laundry appliances, metal furniture, prefabricated farm buildings, silos, screening, hospital equipment and concrete forms. Fence wire coated with Nubelon S can be fabricated into fencing without chipping the surface.

The new finish is available in various shades of whites, grays, and yellows as well as blue, tan, green and red. It is more expensive than current standard enamels and requires baking at 425°F.

May Drop Advance Allotments

Look for cancellation of advance allotments of controlled materials placed in second quarter for third-quarter delivery when the Defense Production Act expires June 30. Washington agencies concerned with controls have reached virtual agreement on this. However, they think some provision should be made for military and Atomic Energy Commission requirements.

Three plans are in the discussion stage. They are: Simple DO rating system; Little CMP; and a board composed of task forces from the steel, copper and aluminum industries to parcel out materials to qualified claimants.

Regardless of which system is adopted, there is general agreement that the warehouse order M-9A will have to be continued in some form after June 30. That would take care of AEC and defense orders and provide for warehouse set-asides.

Do not look for much relief in nickel, though. The agencies think that full nickel control must be kept up after June 30. At present, however, NPA is preparing to raise advance allotments of nickel-bearing stainless for third-quarter delivery from 80 per cent to 100 per cent of the second-quarter consumption.

Bright Outlook Ahead for Window Makers

Prospects of an uncontrolled economy are encouraging manufacturers of metal windows, sash and storm doors

WITH MUCH to gain from lifting of controls, and little to fear from declines of defense orders, metal window producers generally have a clear view of prosperity in 1953.

The predominately civilian industry making storm doors and windows and metal sash is currently in a lull between the fall and spring heavy production periods. When the year's building construction begins in earnest, manufacturers of metal windows forecast sales gains of 5 to 15 per cent over 1952.

Contributing Factors — Among the reasons for industry optimism is the possibility of increased civilian building and the trend toward larger houses with more windows. Manufacturers of basement windows point out that hastily-built houses in the immediate postwar period used fewer cellar windows than are installed now.

In addition to housing sales, demand from schools and hospitals is heavy this year, and sales to constructors of commercial structures are increasing. Aluminum is gaining rapidly in usage, not at the expense of steel, but to the detriment of wood, which remains the leading material in window casements. In window sash, aluminum's lightness and corrosion resistance causes that metal to rival steel in use. A major handicap to aluminum is its higher price.

Combinations—Aluminum frame windows with removable screen and glass sections are increasingly popular. These "storm and screen" combinations, manufactured by companies such as Weather-Proof Co., Cleveland, Stetson Window Corp., Belmont, Mass., and Champion Windows Inc., Boston, permit quick changes from summer to winter positions. A new development at Weather-Proof Co. is an aluminum door with glass and screen sections which can be stored in a panel inside the door when not in use.

The feeling among industry members is that aluminum will grow into still greater favor in metal windows, now that the metal is in freer supply. Prospects for market expansion caused officials of Season-All Co., Pittsburgh, to remark that the storm window industry is still in its infancy. Others believe aluminum has gained in public acceptance over the past five years, promising a bright future.

Defense Contracts—Metal windows are intended almost completely for civilian production, but several companies round out slack periods with defense work. General Bronze Corp., Garden City, Long Island, N. Y., anticipated an acute aluminum shortage following outbreak of the Korean war, and took on stainless steel fabrication for aircraft. To do this, General Bronze installed special equipment, but did not change its regular production. A Cleveland manufacturer makes small aluminum parts for Air Force jet aircraft.

Among problems faced by metal window producers is the annual slack period, paralleling that experienced by construction. The slump occurs in February and early March, during which time companies renovate their plants and as many employees as possible take their annual vacations.

Spring Building—With the government loosening its reins on metals, sash and casement manufacturers think they can raise their capacity considerably this year. The spring building rush is close at hand and most producers think it will be a prosperous season.

Disk Whirls Into Production

Turbine disk for a J-47 jet aircraft engine whirls into production on a vertical turret mill at the Chrysler jet engine plant, Utica, Mich. Designed to spin at speeds up to 7000 rpm, the disk will be fitted with blades to form the heart of the J-47's air compressor. Navy-owned and operated by Chrysler Corp., the engine plant was built from scratch and producing within 15 months

Hazards Hide in New Contract Terminations

ARE DEFENSE contractors aware of their hazards under the new termination procedure?

That's the question some Washington lawyers are asking about the termination article finalized by the Air Force. The hazard is that the comptroller general and his General Accounting Office can challenge agreements reached by contracting officers with terminated contractors. Such interference could result in long delays, and in disallowance of important costs.

In Air Force Manual—Title of the Air Force article is "Termination of Contracts." It has been incorporated as Section VIII in Air Force Manual No. 70-6J covering "Air Force Procurement Procedures." Like Army and Navy articles, still in the review stage, it is based on Section VIII of the Munitions Board's Armed Services Procurement Regulation.

Washington corporation lawyers say a principal defect of Section VIII is a lack of statutory authority to the contractor to carry out his contract agreement to act as the government's agency in disposing of surplus property.

This is an important factor, for once the defense contract has been terminated, the contractor must prepare his plant speedily for normal peacetime employment. Under Section VIII there is no protection to the contractor from GAO questioning his right to clear the plant for peacetime retooling.

Property Disposal—Lawyers do not like the failure to spell out authority for disposing of property in subcontractors' plants. Section VIII gives contractors authority to settle on their own responsibility only such subcontractors' claims as come to less than $1000.

Among other provisions objected to is lack of interest on delayed payments to terminated contractors. In World War II, 2 per cent was allowed. Section VIII does not allow as costs the interest a contractor pays on borrowed funds, or the contributions he has to make for various reasons; such costs were allowed in World War II. Too, many fixed-price contracts are subject to redetermination. If the comptroller general were so minded, he could have a field day in this area.

What is needed, say the lawyers, is a peacetime Contract Settlement Act and a Surplus Property Act which will give both the armed services and contractors the protection they need in making termination settlements. Such proposals have been put forward in Congress, but they are not being pushed. In the meantime, lawyers fear, the contractor has a noose around his neck which could be drawn tight at the time for termination settlements.

Anaconda Starts School

Anaconda Wire & Cable Co. announces a program to combat the engineer shortage by means of a 13-week industrial engineer training course at Anaconda's Hastings-on-Hudson, N. Y., plant.

Anaconda's project has three objectives: To develop technically trained men with knowledge of industrial engineering theory; to equip these men with ability to impart the training to foremen, and to improve production.

Some 15 trainees took the course and have been assigned to various Anaconda mills to pass around benefits of the training.

SELECTED DEFENSE CONTRACTS IN EXCESS OF $100,000

PRODUCT	CONTRACTOR
Lathes	Robert R. Stephens Machinery Co., St. Louis
Link Loading Machines	Marnat Engineering & Machinery Works, San Francisco
Automotive Parts	International Harvester Co., Peoria, Ill.
Parts for Cranes	Baldwin-Lima-Hamilton Corp., Eddystone, Pa.
Parts for Rock Crushers	Pioneer Engineering Works, Minneapolis
Valves, Thermostat Control	Leonard Valve Co., Cranston, R. I.
Valves, Various Sizes	Ludlow Valve Mfg. Co., Inc., Troy, N. Y.
Radio Receivers	Motorola Inc., Chicago
Transmitters	Mackay Radio & Telegraph Co. Inc., New York
Sound Reproducing Units	Webster-Chicago Corp., Chicago
Bombs, 100 lb.	Allen Mfg. Co., Nashville, Tenn.
Fuzes, Grenade	Bayshore Industries Inc., Elkton, Md.
Fuzes	Stewart Warner Corp., Alemite Div., Chicago
Adapter Grenades	Wald Industries Inc., Huntingdon, Pa.
Metal Parts for Boosters	Grand Rapids Hardware Co., Grand Rapids, Mich.
Parts for Electric Motors	General Electric Co., Schenectady, N. Y.

NPA Relaxes Order M-41

Toolmakers look for improved backlogs as they take unrated orders for Appendix D tools

MACHINE TOOL builders got a hot in the arm when National Production Authority amended Order M-41 to allow purchase of tools listed in Appendix D without rated orders. In the face of seriously declining backlogs of rated orders, the new amendment means that some manufacturers will not have to cut schedules as they had thought they might, but will continue to produce at normal rates.

Donald M. Pattison, director of NPA's Metalworking Equipment Division, says the relaxation of the order comes about as the result of prompt deliveries of such tools to the military and all others qualified for them. Also, NPA feels that the industry will be able to produce more tools more efficiently if it is allowed to accept and fill unrated orders.

Just in Time—Many producers feel the action was just in time to avert at least a partial shutdown in the industry. Since January, 1951, shipments of all machine tools have risen from 114.3 per cent to an estimated 361.9 per cent of the base period of 1945-1947. At the same time new orders have declined from 475.4 per cent to about 254.9 per cent, according to the latest figures released by the National Machine Tool Builders Association.

Since July, 1952, the industry has reduced its service-rated backlog by two weeks per month until it now stands at an average of 6 months. That represents less than 30,000 tools.

Equals Lead Time — Combine those two sets of facts, and you get many situations where the manufacturer's rated backlog is equivalent to or less than his lead time. On the other hand, the backlogs of unrated orders for less critical tools have built up from about $110 million in August, 1952, to about $225 million in February, 1953.

The business is to be had, and the effect of the new amendment is to let toolmakers have it. The effect will be immediate, Mr. Pattison believes, although it will probably take at least 90 days for the effects to show up on the records.

Appendix D of M-41 includes boring machines, die-sinking machines, drilling machines, grinding machines, lathes, milling machines, planers and shapers.

Stator Shipped to India

Off the ship at Calcutta harbor comes a stator for a General Electric 62,500 kilowatt steam turbine-generator. The stator is destined for the ultra-modern Bokaro steam plant located 200 miles northwest of Calcutta on the Damodar river in India's mining country

Air Force To Sell 228 Tools

The Air Force Air Materiel Command is going to sell to the highest bidders 228 tools stored at Marietta, Ga., on Mar. 31. The units are the remainder of 40,000 tools stored shortly after World War II, most of which have been leased to Air Force contractors or to other branches of the services.

The tools are damaged, have missing parts or are obsolete for armed forces purposes. But they are repairable and may fit into some civilian production use. Highest bidders will obtain outright title to them.

Bids must be postmarked before midnight, Mar. 27, and sent to U. S. Air Force, Plant Clearance Office, c/o The Tumpane Co. Inc., Government Aircraft Plant No. 6, Marietta, Ga. Forms may be obtained from that address. Prospective bidders may inspect the tools at Marietta.

CHECKLIST ON CONTROLS

Materials Orders

SELENIUM—NPA Order M-91 was revoked, effective Feb. 25, 1953, removing allocation control over selenium.

MACHINE TOOLS — Amendment of Feb. 27, 1953, of NPA Order M-41 no longer requires rated orders to obtain machine tools in Appendix D of the order. It was effective Mar. 1.

ALUMINUM SCRAP—NPA Order M-22 was revoked, effective Mar. 2, 1953, removing controls over aluminum scrap.

PLATINUM—Amendment of Mar. 3, 1953, of NPA Order M-54 permits a refiner to deliver to a processor platinum recovered from completed jewelry or parts of jewelry, or from scrap or sweepings, received from jewelry manufacturers, wholesalers and retail jewelers to be used by the processor in manufacturing any item included in List A of the order. The amendment was effective Mar. 3.

SILICON — Amendments of Mar. 4, 1953, of NPA Order M-80 and its Schedule 1 permit consumers of silicon to use or have in inventory up to 50 gross tons per month without reporting such usage to the NPA Iron & Steel Division. Previous limit was 15 gross tons per month. The amendments also exclude from inventory control boron, calcium and ferrosilicon. NPA Regulation 1 is amended accordingly. All amendments were effective Mar. 4.

NPA Regulations

SELENIUM—Amendment 2 of NPA Regulation 1, issued and effective Feb. 25, 1953, restricts users' inventories of selenium, selenium alloys and selenium dioxide to a 30-day supply.

SELENIUM—Amendment of Feb. 25, 1953, of Direction 3 to NPA Regulation 2 adds selenium and selenium alloys to the list of items for which defense (DO) ratings may not be applied or extended to obtain delivery.

Price Regulation

COPPER, ALUMINUM — Amendment 42 of General Overriding Regulation 9, issued and effective Feb. 25, 1953, exempts from price controls primary copper and aluminum; aluminum mill products; brass mill products; copper wire mill products; copper powder; copper and aluminum screen cloth; mechanical precision springs, metal stampings and screw machine products; bolts, nuts, screws and rivets; copper and aluminum ores and concentrates.

Appointments in Washington

Clifford L. Newton, superintendent of supplies and motor vehicles for the Southern Bell Telephone & Telegraph Co., Atlanta, was named director of the Communications Equipment Division, National Production Authority.

Robert C. Watson, formerly a senior member of the patent law firm of Watson, Cole, Grindle & Watson, was administered the oath of office as Commissioner of Patents.

Windows of Washington

By E. C. KREUTZBERG *Washington Editor*

PREPARATION TOMORROW MAY BE TOO LATE
. . . a little planning might save a lot of trouble

Government and industry study means of diminishing damage of a possible bombing attack. Spokesmen stress importance of adequate preparation

IN THE INTEREST of industry is the new governmental study to minimize production interruptions from bomb attacks in event of war. It is titled the "Post-Attack Production Planning Program." W. J. Hoff, assistant to the director, Office of Defense Mobilization, heads the study.

Co-ordinator in the National Production Authority of efforts to interest industry in the program is James Hynes. So far two industries —rubber and chemical manufacturing—have taken hold, and others have become interested.

Manufacturers are accustomed to protecting themselves against risks—such as fire, lightning, tornados, floods—and there should be little difficulty in getting them to treat realistically the new risk of bomb attack. Adequate preparation is the important thing. In some cases dispersion can minimize the damage. By advance planning, reconstruction necessary to get bombed plants back into production can be expedited. In some of these activities, the manufacturer can meet the expense out of his own pocket.

That summarizes the program in a general way; specific measures will vary for different industries and for different plants in an industry. The approach is outlined in a pamphlet entitled "Suggested Post-Attack Production Measures." Manufacturers can get copies by writing to the Office of Defense Mobilization, Washington 25.

Commerce Face-Lifting? . . .

If Sinclair Weeks intends to make the Commerce department the advocate of private business in the federal government, he has a long way to go.

In this department are a group of agencies rendering informational and other services to industry. Another group, set up for defense programming, or assigned temporarily to carry out defense functions, include such agencies as the National Production Authority and National Bureau of Standards.

Commerce can advise but has no authority on vital problems facing industry. Functions important to business are vested with the Justice department and the Federal Trade Commission. Labor-management matters are the concern of the Labor department, National Labor Relations Board and the Federal Mediation and Conciliation Service.

If Mr. Weeks is to build up the Commerce department to be the effective voice and friend of business in the government, he will have to obtain powers now residing elsewhere.

Fortunately Mr. Weeks, in addition to being a forceful and successful businessman in his own right, is a member of an administration definitely pledged to the promotion of private business.

Maintains Watchdog . . .

The Senate Armed Services committee voted to continue "watchdog" operations of its Preparedness subcommittee. Chairman Leverett Saltonstall (Rep., Mass.) committee chairman, will head the subcommittee which will function in "task groups." The first task group, composed of Senators Styles Bridges (Rep., N. H.), Ralph Flanders (Rep., Vt.) and Harry Byrd (Dem., Va.) is investigating aircraft procurement.

Tax Reports in Offing . . .

Treasury department spokesmen told a news conference that the administration won't be able to submit its tax recommendations to Congress for two or three months. They refrain from guessing whether extension of the excess profits tax will be recommended.

Consider Seaway Project . . .

Sen. Alexander Wiley (Rep., Wis.) appointed a special Senate Foreign Relations subcommittee headed by himself to hold hearings on legislation to authorize American participation in the St. Lawrence seaway and power project.

Other members are Senators Robert Taft (Rep., O.), William Knowland (Rep., Calif.), John Sparkman (Dem., Ala.), Theodore Green (Dem., R. I.) and Walter George (Dem., Ga.). Hearings are tentatively scheduled to start about the middle of this month.

CHARGING BUGGY?

no, this is a "Charging Buggy"

This Morgan buggy places billets or slabs in the furnace singly or in multiples so that both ends are equidistant from the furnace walls. The fitting of a telescopic ram to the buggy makes possible the charging of billets and slabs of different lengths. The quick and precise operation of this charging mechanism makes possible an uninterrupted flow of billets or slabs through the heating furnace with resultant uniform temperatures throughout the entire length of the billets or slabs.

Your problem may be different. If it relates to equipment we build, why not talk it over with our engineers?

MORGAN CONSTRUCTION CO.

WORCESTER, MASSACHUSETTS

English Rep., International Construction Co., 56 Kingsway, London W. C. 2, England

ROLLING MILLS • MORGOIL BEARINGS • WIRE DRAWING MACHINES
REGENERATIVE FURNACE CONTROLS • EJECTORS • GAS PRODUCERS

RM-49



Like the right size hat CMP THINSTEEL is made to fit your need

Are you one of those who constantly find it necessary to adjust and make changes in your fabricating operations to compensate for a lack of the optimum characteristics in the strip steel you require for your manufacturing needs? If you are "making do" with slit-sheet products or mill-run strip because you don't know that The Cold Metal Products Company is equipped to develop specifications and produce the exact size, tolerance, structure, finish, or temper most adaptable for your particular need alone, then this message is intended to bring us together. The "unusual" specification is our business and what's more we are prepared to study your problems and make recommendations for specifications which you may not know are available but which well may be commonplace with us.

Our message is simply this—If you are having fabricating problems with cold rolled strip steel, if the labor cost represented in your rejects is a cause for concern, or if your assembly costs are high because of quality variations in your strip steel components, give us an opportunity to show you what CMP strip steel products can do for you.

PRECISION COLD ROLLED C M P STRIP STEEL

the Cold Metal Products co.

YOUNGSTOWN 1, OHIO

New York • Chicago • Indianapolis • Detroit • St. Louis • Los Angeles • Cleveland

LOW CARBON, HIGH CARBON (Annealed or Tempered) ***STAINLESS AND ALLOY GRADES, ELECTRO ZINC COATED ARE AVAILABLE FROM:***

THE COLD METAL PRODUCTS CO. of CALIFORNIA, 6600 McKinley Avenue, Los Angeles
Phone: PLeasant 3-1291
THE KENILWORTH STEEL CO., 750 Boulevard, Kenilworth, New Jersey
Phones: N. Y., COurtlandt 7-2427; N. J., UNionville 2-6900
PRECISION STEEL WAREHOUSE, INC., 4425 W. Kinzie, Chicago • Phone: COlumbus 1-2700

British Problem Linked to Productivity

Latest statement on the British economic problem is the result of more than a year's study. Faster increase in productivity is seen as the key

ROTECTIVE AMERICAN tariffs nd Buy American legislation ere rapped again last week. his time it was in the findings of ie Research & Policy Committee f the Committee for Economic Delopment.

Recommendations for American ction in the CED report, "Brit-in's Economic Problem and Its feaning for America," resemble ose of Henry Ford II (STEEL, Feb. 3, p. 61): Reduce tariffs, simplify ustoms procedures, progressively emove agricultural import quotas nd repeal the "Buy American ct."

First Served — "Increasing the utput of the British economy, tol and per capita, at a greater rate han in the inter-war period or han at present," was called the ey to the British economic prob-m in the long run by the report. cting on that problem, Great Brit-in became the first Mutual Secur-y Program country to reach greement on a $9 million alloca-ion from MSP to be spent for the ncouragement of productivity and timulation of competition. Among ther things, the MSP allocation ill set up a revolving fund to pro-ide short term reorganization and odernization loans to British anufacturers.

In the meantime, record iron and teel production in England, to-ether with unsolved export prob-ms, have brought about these un-sual circumstances. Iron found-ies are short of work, not through ack of pig iron but because of a ack of orders. The "ring fence," et up to keep out a strong flow f defense work, was removed from round Coventry, home of the Brit-sh auto trade. The automobile in-ustry has worked through its acklog in the last six months and ritish buyers can now get a new ar right from the showroom.

New Marks—Steel production in Britain in January was at a weekly verage of 346,300 tons, compared vith the previous record of 345,200 ons in a week in November, 1952. Pig iron output was at a weekly rate of 213,900 tons, against the previous best rate of 208,000 tons a week in September, 1952.

The whole question of how far the U. S. should go to open its doors to foreign-made products and foreign trade is one of the first questions the Eisenhower administration will have to answer on a policy level. President Eisenhower, in his refusal to boost duties on imported briar pipes, promised action at "an early date." That would certainly be before the Reciprocal Trade Agreements Act expires on June 12, 1953. While generally considered in favor of low tariffs, the President has said any extension of the trade agreements legislation should include peril point and escape clause provisions.

U.S. Exports Hit New High

Final foreign trade figures for 1952 show U. S. exports hit $15.2 billion and imports rose to $10.7 billion. The export total is an all-time high and the import figure, while above the previous two years, is less than any other post-war year.

Ironically, military aid shipments, which were undertaken to help friendly nations survive the cleft with Communism, accounted for about $2 billion of the $4.5 billion excess in U. S. exports over U. S. imports. That unfavorable balance of dollar trade with the U. S. is weakening many foreign nation's position in the family of free western countries.

Instrument Market Ripe

"Most large producers of metals in Europe are anxious to modernize their plants and they have adequate funds to purchase new equipment," says Dr. M. F. Hasler, president of Applied Research Laboratories, Glendale, Calif. "That's in direct contrast to many U. S. and Canadian firms whose working capital has been stretched to the limit because of tremendous plant expansion and high taxes."

During his four month stay in Europe, Dr. Hasler completed arrangements for a new permanent ARL branch at Lausanne, Switzerland, to assemble and sell the company's scientific instruments.

Wisconsin Firm Assists Belgian Mill

Transmission of this diesel locomotive working in a Belgian steel mill is equipped with a 17.5 in. hydraulic coupling and CL-211 clutch manufactured by the Twin Disc Clutch Co., Racine, Wis. The clutch is actuated by a hand wheel instead of a lever. The locomotive is built by Moteurs MOES of Waremme, Belgium

TRADE ASSOCIATIONS

	All National Associations	Metalworking Associations*	Business Population
1910	250	50	2 million
1930	900	180	3 million
1953	1600	425	4 million

*Estimated by STEEL. Source for other figures: Department of Commerce

How To Grow With Them

STEEL FOUNDRYMEN wanted to find if there's a practical way to desulphurize their melt. The problem looked like it needed an expensive research job, one that no individual company in the industry could easily afford.

But the research job—now being handled by Battelle Memorial Institute, Columbus, O., for $100,000—is well within the financial resources of the industry acting cooperatively through its trade association, Steel Founders' Society of America. F. Kermit Donaldson, executive vice president of the group, points out that results of the research, too costly for many members, will now be available to all through co-operation.

Keystone—A trade association helped make that possible. Trade associations are bringing countless benefits to industry yearly. They could do you still more service if you only used them better.

"All too frequently," says Orrin B. Werntz, executive secretary of National Screw Machine Products Association, "association members have only a partial idea of what their organization can do or is doing for them." Reuel W. Elton, the general manager of American Trade Association Executives, a trade association of executives in the association field, puts it this way: "Trade association men have a constant battle to get their members to use their services."

Definition—Trade associations are nonprofit organizations of business competitors in any single industry, formed to render mutual-aid services. As the accompanying chart illustrates, some 1600 such national groups are now in existence, an estimated 425 in metalworking alone which has more trade associations than any other industry in the U.S. Membership now approaches 1 million for national outfits of all types, 30,000 for metalworking groups. In a few of the larger groups, members have access to as many as 78 different kinds of services. In virtually all organizations, members can be helped by at least 15 basic services. And all that's available at a cost in dues which averages only 0.1 per cent of a company's annual sales.

The 15 major services probably offered by your association are listed in the accompanying table. C. J. Judkins, chief of the Commerce department's Trade Association Division, believes that the major benefit derived from trade associations is the pooling of know-how, as in the case of steel founders. Because of trade associations, manufacturers more readily today than a few decades ago reveal their operational secrets.

How It Works—"Manufacturers have learned that by helping each other they help themselves," says one association member. "For example, years ago a varnish manufacturer revealed through his trade association that he maintained a then-unusual degree of uniformity in his product by spitting into each batch and observing the action of the spittle. That led to investigation by the industry of a more scientific approach to the problem which eventually resulted in new laboratory methods of maintaining uniformity of quality—methods that were made available to the whole industry."

Co-operative research is still a comparatively rare function among associations, but its use is growing and promises to be one of the most important functions in a few years. Besides Steel Founders' Society, American Petroleum Institute and American Gas Association are among the groups already active in that area.

Government Help—Co-operation through trade associations also pays off on government relations. Big companies may be able to hire Washington representatives to interpret the latest federal directives, but many small and medium sized firms can't afford that. But they can afford trade associations, and a major job for most of those groups since the start of World War II has been to render such service and fight in Washington for better treatment of their industries.

Are you taking full advantage of your opportunities in trade associations? The accompanying check list can help you do a better job. The advice all boils down to this: To get full benefits, use your trade association, support it with your time, your money, your talents.

Tell Your Story—Especially important is to take your problems to your association. Your difficulty may not be as unusual as you think and the secretary may

What They Offer . . .

1. Information on business facts and problems.
2. Conventions and conferences where you can exchange know-how and meet competitors.
3. Help on government relations and legislative research.
4. Studies of trade practices, unfair competition and business ethics.
5. Public relations activities and building up of consumer good will.
6. Sales promotion of the industry's products.
7. Labor relations in general (but few regular trade associations go so far in employer-employee services as to be the industry's collective bargaining agency for employers).
8. Statistics and economic planning.
9. Commercial research to find wider and more profitable markets.
10. Industrial research to find new or improved products or manufacturing techniques.
11. Uniform cost accounting and industry surveys of costs of production and distribution.
12. Standardization, simplification, inspection, grading and certification.
13. Studies of the industry's financing, credit, collection, cash discount and related practices.
14. Commercial arbitration between members or between members and customers.
15. Furnishing advice on broad industry problems of a legal nature (but not acting as general legal adviser for industrial members).

What To Do . . .

1. Learn its functions.
2. Attend its national and regional meetings.
3. Get junior members of your company to participate in its special and regional meetings.
4. Read and study its many publications; assign one man the responsibility of knowing where and what the publications are.
5. Assign one man the responsibility of keeping up your company-association relations.
6. See that your company is well represented on your association's committees.
7. Be generous in your financial support. An association rarely has enough money.
8. If you aren't getting what you think you should from your association, let your association officials know it. They may be falling down on the job.

have already helped work out the solution for another company. For example, a metal fabricator was allowed only 6 per cent annually by the Bureau of Internal Revenue as a tax depreciation allowance. The company told its association about it; the association already had wrestled with that tax situation and had statistics showing that the industry's average depreciation allowance was 9 per cent, not 6. The fabricator won a 9 per cent allowance.

Or your association may have services you never knew it had. A basic metal producer was about to embark on a market research program to learn how to sell more efficiently to a big industry composed mostly of small companies. As a preliminary step, it joined the industry's association as an associate member and sent a man to attend the group's convention. There, the representative discovered that the association had complete industry statistics which fitted perfectly into the primary producer's market research plan. Instead of going to the expense of gathering the figures itself, it had access to statistics through the nominal expenditure of dues and the cost of sending a man to a convention.

Help for All—Or you may suggest a problem to your association that results in a new service for all. For example, diesel engine producers complained to their Diesel Engine Manufacturers Association about the shortage of good engineers and the lack of training of those college graduates they were getting. The result: The association outlined a program to educators whereby it would spend time and money to help get better engineers. There's still a shortage of engineers, but diesel manufacturers think they're on the road toward a solution. The same type of query on cost accounting led Malleable Founders' Society to publish a manual of principles and procedures for cost accounting which was one of the first of its kind.

George Eaton, executive secretary of National Tool & Die Manufacturers Association, believes many associations don't publicize their activities adequately. Few have the money to do the job. Money is a problem with practically all associations. They can't do what they know they should be doing. Some associations have staffs numbering more than 100, but the majority have only three of four full-time employees, not enough to do a good job.

Tragedy?—Such skimping could prove tragic, for as former President Hoover says: "Trade associations are the safeguards of small business and thus prevent the extinction of competition."

Trade associations got their start because of government encouragement. During World War I, Bernard Baruch as head of the War Industries Board urged companies to form mutual associations so he could better deal with them. Herbert Hoover, the co-father of the movement, developed the idea still further, when he was secretary of commerce in the 1920s, as the only practical way for government to deal with the then more than 3 million independent businesses in the U. S. That argument holds even greater weight today since more than 4 million separate businesses now function.



UNMATCHED TESTING FACILITIES...

one of many reasons for Hyatt leadership!

In testing laboratory or manufacturing plant, Hyatt's facilities are second to none. Continuing research in methods and materials, and exacting inspection with the finest in modern equipment, has made the Hyatt name a synonym for "highest quality." That's why Hyatt Roller Bearings are so widely used in tables, cars, cranes and other steel mill equipment. Design engineers know that Hyatt bearings ease shock loads, extend equipment life and reduce operating costs. Hyatt Bearings Division, General Motors Corporation, Harrison, New Jersey.

HYATT ROLLER BEARINGS

By FLOYD G. LAWRENCE *Detroit Editor*

Mirrors of Motordom

Corrosion continues No. 1 problem for automobile body engineers. Corners of bright work rust first because plating is thinnest there. One correction: Flatter trim and more wax

DETROIT

EVER NOTICE HOW rust starts first in the corners of your chrome car garnish? The explanation, if you didn't know, is because that's where the plating is thinnest. The vertex of an acute surface angle can get less than one-ninth of the one-thousandth inch nickel plate currently permitted car manufacturers, says D. M. Bigge, Chrysler Corp.

The moral noted by those attending the S.A.E. National Passenger Car, Body and Materials Meeting in Detroit last week is this: For designers—keep plated trim surfaces as nearly flat as possible; for car owners—keep those areas heavily waxed.

Splash, Rust—F. L. LaQue of International Nickel, noted that splashing water increases body corrosion two to four times over normal atmospheric corrosion. Surprisingly, salt treatment of roads accelerates corrosion only moderately. Mr. LaQue points out that more quickly disposing of snow through the use of salt may actually minimize corrosion when the greater natural melting time and consequent longer water splash is taken into consideration. "Wash your car frequently to get rid of the salt, however," says Mr. LaQue in conclusion.

A total copper and nickel plating thickness of .002 inches is necessary to provide adequate protection against corrosion for zinc, aluminum and magnesium base die castings, say M. R. Caldwell and C. Pack of Doehler-Jarvis Division of National Lead Co. They also point out that consideration of die life and intricacy of detail in the finished part desired should enter into the decision on material for die castings.

Headache for Engineers — Air conditioners are giving auto engineers their share of headaches. P. J. Kent of Chrysler predicts one out of every ten cars will be so equipped in the next decade. Whether they should be installed on the final assembly line or by dealers is a moot problem. H. V. Joyce of Ford points out that they are extremely complex to install and variations in drive ratio of the compressor to insure proper minimum and maximum operating speeds with variations in engine and rear end ratios of different models pose dealer installation barriers.

When installed, the system must be bled, filled with refrigerant and checked for leaks. The dealer removing radiator, radiator support, front end springs and shocks, tires, fan, crankshaft pulley, horns and other affected parts may not be eager to tackle this additional chore. In the last analysis, final assembly line installation looms more feasible, but automakers hate to loose the accessory nature of the cooler.

Bubble Trouble—Air bubbles and dirt accumulation in oil are the chief causes of hydraulic tappet trouble, says Carl Voorhies, Chicago Screw Co. They're troubles the engineers will have to lick because the modern overhead valve engine with high peak rpm accentuates the need for uniform valve timing over a greater range which hydraulic tappets afford.

Higher engine speeds also require design of valve gear components having a high stiffness to mass ratio, reports Ralph P. Horan, Eaton Mfg. Co. Overhead valve gear is much more sensitive to speed than L-head engines due to the greater weight and flexibility of parts.

Also advocated in valve design by John A. Newton and M. J. Tauschek of Thompson Products Inc., is the positive valve rotator to minimize the effects of valve seat distortion. The unit is reported to prevent occurrence of hot spots at any one point on the valve, prolonging valve life two to five times.

Auto, Truck Output

U. S. and Canada

	1953	1952
January	612,830*	409,406
February		467,691
March		517,207
April		576,505
May		546,673
June		560,947
July		246,461
August		293,722
September		592,253
October		645,862
November		556,366
December		569,696
Total		5,989,121

Week Ended	1953	1952
Jan. 31	150,289	102,402
Feb. 7	146,809	102,406
Feb. 14	147,103	111,821
Feb. 21	161,860	110,542
Feb. 28	164,903	118,397
Mar. 7	162,000*	115,126

Sources: Automotive Manufacturers Association, Ward's Automotive Reports. *Preliminary

Nash's Calculated Rambling

The only thing "rambling" about the new Nash Rambler is its name. These continentalized cuties are definitely aiming at an increased cut of the low-priced field through design away from the stigmatizing "small car" look.

Pinin Farina, Nash's favorite Italian dish, is served on the same 100-inch wheelbase. But fender lines have been lengthened and the hood has been lowered giving the body the look of being nine inches longer—which it is. Add the continental spare tire mount which is standard on all models but the station wagon, and you have a car which will not look undernourished at anybody's drive-in.

This happy circumstance is precisely what the Nash people intended. With standard appointments including air conditioning system, radio, electric clock, courtesy lights, directional signals, foam cushions, custom upholstery and trim, continental rear tire mount and other deluxe features with no extras to buy, Nash figures it's offering a mightly competitive bit of merchandise to the Ford,

(Material in this department is protected by copyright and its use in any form without permission is prohibited)



A Look at the 1953 Nash Rambler

Newly designed 1953 Nash Rambler series includes a custom convertible (upper left) and a station wagon (upper right). Continental rear tire mount (lower left) is standard equipment on Rambler convertible models, while the front end (lower right) shows a re-styled appearance with a lowered hood line and new air scoop

Chevrolet and Plymouth classes.

NXI To Become Reality — There's more to the Nash strategy than just the new Rambler, however. Remember the NXI that people who hang out in hotel lobbies were invited to opine on a few years ago? It's a small double-seater definitely in the economy car class, and it's going to be built. Austin will make the engine, Fisher-Ludlow will make the body and the whole deal will be assembled in England based on Nash specifications. Nash for its part will take a prearranged quantity of the demi-autos for stateside distribution.

The NXI in effect will become the Rambler in the future Nash line, with first shipments scheduled to arrive early in the fall. Meanwhile, the largerish Rambler will be rambling, Nash hopes, through the sales of the low-priced field.

Cleaning the Desk

Chevrolet has started production on the new R3350-85 turbo compound engines of 3500 horsepower at its Buffalo plant. Each engine contains 19,632 pieces exclusive of the carburetor which contains more than 600 alone. In all, 360 manufacturing plants in 20 states contribute to the Chevrolet aviation program.

Willys-Overland Motors Inc. expects to license Standard Motor Co. Ltd. of Coventry, England, to make the Willys jeep for sale in the sterling area. Cited in the move is penetration of the sterling area barrier which has existed since the end of the war for American manufacturers.

A merger in the "no comment" stages is pending between Willys-Overland and Kaiser-Frazer. Before this column sees print the merger may be concluded. Kaiser production thus far this year is 7000 compared with 9300 for the first two months of 1952. Willys production ran about 10,000 during the first two months of 1953 compared with about 5000 during the like period in 1952. A co-operation of the manufacturers in which Willys supplies the Henry J chassis and engine has been in effect since the Henry J was created. In further union, the reasoning may go, lies strength.

Reconstruction Finance Corp., eyeing the multi-million dollar Kaiser-Frazer bag it could possibly be holding undoubtedly agrees.

Reo Motors Inc., reports that: More than 12,000 gallons of gasoline are consumed each month in its dynamometer department in testing truck engines; sales of used trucks at Reo branches throughout the country have increased 21 per cent over last year; a "combination" muffler has been developed as part of an independent program aimed at reducing truck noise.

Chrysler Corp. reveals that 68,000 DeSoto and Chrysler cars have been ordered with power steering during the past six months, almost as many as in the entire preceding year.

Jaguar Goes Automatic

If you've been troubled by pesky gear shifting on your Jaguar sedan, here's good news: Jaguars will have a Borg-Warner automatic transmission as optional equipment henceforth.

Manufactured by Detroit Gear Division of Borg-Warner Corp., the units will be shipped to England for assembly into cars. The cars, in turn, will probably be shipped right back to the United States.

Involved in the unit are a hydraulic torque converter and two sets of planetary gears constantly in mesh in series. The planetary gears provide two forward driving ratios and a reverse ratio, all sans clutch. Results are claimed to be equivalent of the four-speed transmission now standard on Jaguar cars permitting the use of high ratios in the rear axle. In direct drive, the converter is locked out preventing heat loss, with downshifting through accelerator depression at speeds up to 66 miles an hour.

Two years of rigorous testing in the Swiss Alps lend substantial evidence to the belief that the transmission is ready for the market. Besides, it's starkly similar to the transmission Borg-Warner has been making for Studebaker.

Jaguar expects the transmission to double sales of its Mark VII sedans in the United States, but the unit will not be immediately available for the XK-120, most popular of the Jaguar line in this country. About 8000 Jags are currently in American garages.

Cost of the unit, if you're wondering, will be about $280; car somewhat additional.

● The "third degree" is but a superficial scanning compared to the trials a ball bearing must withstand in New Departure's Research Laboratory. Here, under conditions which pack years of normal use into a short time, engineers determine how to make the best ball bearings even better.

Production bearings and experimental designs, alike, take this "torture treatment." They are subjected to overspeeds and overloads, intense heat and cold, day and night operation for protracted periods.

Search and Research

Three decades of this search and research have produced the sealed rear wheel-bearing for motor cars, the self-sealed bearing for farm implement use, the tiny, jewel-like bearing for delicate instruments . . . and many other types to fit a host of applications.

You can specify New Departures and *know* that they are right for the job. Keep your eye on the BALL to be sure of your BEARINGS!

Vibration analyzer eliminates human error in scientific search for causes of noise in bearings.

New Departure ball bearings are readily available at your equipment dealer or bearing distributor —supplied from the industry's largest network of warehouse stocks.

W DEPARTURE • DIVISION OF GENERAL MOTORS • BRISTOL, CONNECTICUT

Also Makers of the Famous New Departure Coaster Brake



ORDER wear-resistant 52100 tubing today. We ship it tomorrow from our mill stock of one hundred and one sizes!

A high-carbon chrome steel, 52100 manufactured by the Timken Company, is through-hardening in moderate sections and can often be used in place of more expensive steels.

It can be heat treated to file hardness and tempered back to any desired point. And it's available in sizes from 1″ to 10½″ O.D., to fill many of your hollow parts needs: aircraft parts, ball bearing races, pump parts and plungers, collets, bushings, spindles, grinding machine parts and precision instrument parts.

As America's first producer of 52100 tubing, the Timken Company has unequalled experience that results in uniform high quality from tube to tube and order to order. Rigid quality control checks every step of production.

For immediate delivery of your less-than-mill quantity orders, write, wire or call The Timken Roller Bearing Company, Steel and Tube Division, Canton 6, Ohio. Cable address: "TIMROSCO".

YEARS AHEAD—THROUGH EXPERIENCE AND RESEARCH



TIMKEN
TRADE-MARK REG. U. S. PAT. OFF.
Fine Alloy
STEEL

SPECIALISTS IN FINE ALLOY STEELS, GRAPHITIC TOOL STEELS AND SEAMLESS TUBIN



*Week ended Feb. 28

Based upon and weighted as follows: Steelworks Operations 35%; Electric Power Output 23%; Freight Car Loadings 22%; and Automotive Assemblies (Wards' Reports) 20%.

Production is staging another upswing as soaring automotive operations supply the largest boost. Industrial activity index nears the record level attained last fall

USINESS activity is staging another upswing and may set new ecords in the weeks to come.

Production in mid-February alted its sidewise movement and tarted to climb rapidly. In the vo weeks ended Feb. 28, STEEL's ndustrial activity index rose 8 perntage points to 234 per cent of he 1936-1939 average. This index eading is only 1 point below the ecord of 235 per cent set in the nal week in October, 1952.

Most prime indicators of the naon's output are advancing rapidy, indicating that the hoped-for pring upturn in industrial activy is probably under way.

High Demand—Automotive companies—receiving a shot-in-the-arm y the lifting of production quotas -boosted the U. S. output of passenger cars and trucks in the final eek in February to the highest evel in 21 months. This new level ay be maintained in the weeks head as the industry tries to each its production goals for passenger vehicles and trucks.

Electricity production, a good arometer of industrial activity, is lso climbing. Generation in midanuary remained about 7 per cent ver the comparable weeks in 1952. At present, utilities are producing nearly 10 per cent more electricity than a year ago.

Steady Progress—Steel production is also making steady, though less spectacular, progress. Mills in the first six weeks of 1953 were operating at around 99 per cent of the Jan. 1, 1953, rated capacity. In the two weeks ended Feb. 28, steel operations rose to 100.5 per cent of capacity.

Freight car loadings, on the other hand, are continuing to lag about 4 per cent under shipments in the comparable weeks of 1952. Most of this decline, however, is due to the drop-off in shipments of agricultural products and livestock.

Steel Output Nears Record . . .

Steel mills, with demand coming from all consuming directions, are doing practically everything to maintain production as high as possible. The American Iron & Steel Institute estimates that production in the week ended Mar. 7 totaled 2,224,000 net tons of steel for ingots and castings. This output is within 4000 tons of the record 2,248,000 net tons poured in the week ended Feb. 9, this year.

Forging Shops Busy . . .

Makers of forgings are pounding out high production, which, in turn, is lowering the industry's unfilled orders. The Census bureau says that shipments of steel forgings in December rose 16 per cent over November to 181,000 net tons. Drop and upset forgings accounted for 134,000 tons of the December total, while press and open hammer forgings accounted for the balance of 47,000 net tons.

Unfilled orders for commercial steel forgings on Jan. 1 approximated 1.2 million net tons, or 190,000 tons below the level of the previous three months.

Autos Rolling Fast . . .

The passenger auto industry, hoping to complete 3.2 million units in the first half of 1953, is pulling the throttle out on production. U. S. assembly lines in the week ended Feb. 28 yielded a bumper crop of 126,671 passenger vehicles, or 47 per cent over the comparable week in 1952, says *Ward's Automotive Reports*. These end-of-the-month completions brought the February total to around 483,000 units, up 17,000 units from January.

Truck production, however, is making a disappointing showing



Metalworking Wages
(cents)
Production Workers—Five Major Groups

	Prim. Mtls.	Fab. Prod.	Mach. inery	Elec. Mchy.	Trans. Equip.
1951					
Dec.	183.6	170.0	181.7	167.0	190.3
1952					
Jan.	184.7	170.3	182.0	166.9	191.4
Feb.	183.1	170.5	183.0	166.8	190.3
Mar.	184.8	171.5	184.1	169.5	193.4
Apr.	183.0	170.9	183.6	169.5	193.0
May	184.0	171.9	184.0	169.5	192.4
June	183.0	171.5	184.7	170.4	194.0
July	181.3	170.0	184.4	169.5	194.0
Aug.	193.7	172.4	184.5	171.6	194.8
Sept.	199.1	176.3	187.1	173.6	200.5
Oct.	199.0	178.9	188.5	173.0	203.7
Nov.	200.0	179.4	190.1	173.2	204.3
Dec.	202.4	181.0	191.6	173.9	206.0

U. S. Bureau of Labor Statistics



Durable Goods Orders, Sales
In Millions of Dollars

	New Orders*		Sales	
	1952	1951	1952	1951
Jan.	11,115	15,050	10,459	10,430
Feb.	11,392	13,474	10,694	10,390
Mar.	11,841	15,452	11,270	10,851
Apr.	12,761	12,987	11,237	10,739
May	11,492	15,542	11,056	10,851
June	12,423	13,257	10,284	10,383
July	11,393	12,235	8,844	9,666
Aug.	9,938	11,032	10,579	10,028
Sept.	12,198	10,344	11,905	9,508
Oct.	11,772	11,956	12,787	10,660
Nov.	11,390	11,820	11,529	10,542
Dec.	.....	10,937	.....	9,963

*Seasonally adjusted. U.S. Office of Business Economics



Gear Sales Index
(1935-1939=100)

	1952	1951	1950
Jan.	670.6	764.6	280.2
Feb.	539.5	809.1	272.9
Mar.	517.1	830.7	358.4
Apr.	478.7	742.5	328.6
May	425.9	667.1	363.1
June	452.3	800.9	401.0
July	453.9	589.1	410.7
Aug.	413.9	564.2	617.4
Sept.	485.0	630.1	654.5
Oct.	533.1	703.4	564.8
Nov.	516.0	530.0	554.9
Dec.	456.8	716.5	680.4

American Gear Mfrs. Assn.



Standard Size Ironers
Factory Sales—Units

	1952	1951	1950
Jan.	15,636	24,600	20,300
Feb.	17,630	32,400	27,600
Mar.	13,913	34,700	37,800
Apr.	8,938	23,700	31,600
May	12,652	24,200	27,400
June	17,654	24,500	27,100
July	15,025	11,100	25,100
Aug.	16,477	17,200	42,700
Sept.	22,492	18,300	41,400
Oct.	25,204	29,800	47,500
Nov.	19,724	20,500	41,900
Dec.	16,798	16,900	38,800
Total	202,143	277,700	409,200

American Home Laundry Mfrs. Assn.

Charts Copyright 1953 STEEL

Issue Dates on other FACTS and FIGURES Published by STEEL

Construction .....Feb. 23	Indus. Production..Feb. 16	Ranges, Gas .....Feb. 23
Employ.,Metalwkg. Jan. 18	Machine Tools ....Feb. 9	Refrigerators .....Feb. 2
Employ., Steel ....Dec. 15	Malleable Castings.Mar. 2	Steel Castings .....Mar. 2
Fab. Struc. Steel ..Feb. 9	Prices, Consumer ..Jan. 26	Steel Forgings ....Mar. 2
Foundry Equip. ..Feb. 16	Prices, Wholesale..Jan. 26	Steel Shipments ...Nov. 3
Freight Cars .....Feb. 16	Pumps .....Feb. 16	Vacuum Cleaners..Feb. 9
Furnaces, Indus. ..Feb. 2	Radio, TV .....Feb. 2	Washers .....Feb. 23
Gray Iron Castings.Mar. 2	Ranges, Elec. ....Feb. 2	Water Heaters ....Feb. 23

when compared to passenger autos. In the week ended Feb. 28, manufacturers in the U. S. rolled out 28,024 trucks. During 1952, the fourth quarter netted several 30,000-unit output weeks, while in March, 1951, operations soared as high as 35,000 trucks per week. Yet truck output is expected to rise in the next few weeks, since virtually all change-overs to new models have been completed.

Combined U. S. and Canadian auto-truck output in the week ended Feb. 28 totaled 164,903 units, up more than 3000 units from the previous week and far over the 118,397 passenger cars and trucks produced in the comparable week in 1952.

Business Outlook Good . . .

Business will probably remain at today's high levels at least through June. That's the consensus of industrial buyers polled by the Business Survey Committee of the National Association of Purchasing Agents.

Production in February rose above the current demand and started to eat into order backlogs. New orders in February continued to flow in, though slightly under the January rate. Much of the new business was in orders for early delivery.

Employment in February remained about the same as in the previous month, although a few companies reported longer workweeks. Skilled labor remained in short supply. Wage decontrol didn't cause much labor unrest during February, but many labor-management discussions were in process.

Laundry Equipment Jumps . . .

While practically all appliance makers are saying that demand is good, the laundry is gaining precedence over the kitchen in the up trend. A report of the Gas Appliance Manufacturers Association says that shipments of domestic gas ranges in January rose to 166,900 units, only 0.5 per cent over January, 1952. But the market is far less saturated in laundry equipment. The American Home Laundry Association reports that factory sales of standard-size household washers in January totaled

BAROMETERS OF BUSINESS

	LATEST PERIOD*	PRIOR WEEK	YEAR AGO
INDUSTRY			
Steel Ingot Output (per cent of capacity)[2]	100.5	100.5	101.0
Electric Power Distributed (million kwhr)	8,190[1]	8,196	7,416
Bituminous Coal Output (daily av.—1000 tons)	1,421	1,392	1,702
Petroleum Production (daily av.—1000 bbl)	6,540[1]	6,543	6,367
Construction Volume (ENR—millions)	$322.7	$144.1	$165.7
Automobile, Truck Output (Ward's—units)	164,903	161,860	118,397
TRADE			
Freight Car Loadings (unit—1000 cars)	700[1]	690	756
Business Failures (Dun & Bradstreet, number)	178	176	163
Currency in Circulation (millions)[3]	$29,735	$29,654	$28,390
Dept. Store Sales (changes from year ago)[3]	+2%	+3%	+13%
FINANCE			
Bank Clearings (Dun & Bradstreet, millions)	$14,264	$17,520	$14,767
Federal Gross Debt (billions)	$267.5	$267.4	$260.3
Bond Volume, NYSE (millions)	$14.5	$16.6	$11.0
Stocks Sales, NYSE (thousands of shares)	8,968	6,630	6,158
Loans and Investments (billions)[4]	$77.1	$76.9	$73.5
United States Gov't. Obligations Held (billions)[4]	$31.1	$31.3	$32.0
PRICES			
STEEL's Weighted Finished Steel Price Index[5]	181.31	181.31	171.92
STEEL's Nonferrous Metal Price Index[6]	210.9	210.7	243.6
All Commodities[7]	109.7	109.6	113.0
All Commodities Other Than Farm and Foods[7]	113.1	112.8	114.3

*Dates on request. [1]Preliminary. [2]Weekly capacities, net tons: 1953, 2,254,459; 1952, 2,077,040. [3]Federal Reserve Board. [4]Member banks, Federal Reserve System. [5]1935-1939=100. [6]1936-1939=100. [7]Bureau of Labor Statistics Index, 1947-1949=100.

277,309 units, a gain of 29.6 per cent from a year earlier. Sales of automatic tumbler dryers in January reached 38 per cent over January, 1951, to 62,260 units. Ironer sales took the biggest over-the-year jump (45 per cent) in January by aggregating 24,395 units.

Structurals Tower Skyward . . .

As the construction boom rolls on, new orders for structural steel are also gaining momentum. The American Institute of Steel Construction says that January bookings for fabricated structural steel amounted to 268,163 tons, an increase of 14 per cent over December and 26 per cent over January, 1952. Shipments of structurals in January totaled 234,234 tons, or some 33,929 tons under the incoming orders of that month.

Total industry backlog on Feb. 1 amounted to 2,179,777 tons, of which 49 per cent is scheduled to be produced before May 31.

Retail Sales Improve . . .

Sales of retail stores are up considerably from a year ago, when the bottom had fallen out of the post-Korea spending spree. The Commerce department's Office of Business Economics says that sales of retail stores in January totaled $13 billion, about 10 per cent over January, 1952. Sales of durables rose 11 per cent over the year to $4.3 billion.

Consumer Prices Edge Down . . .

The cost of living in January declined for the third consecutive month. So says the Bureau of Labor Statistics, as it introduced its controversial index of consumer prices. Retail prices of goods and services bought in January by moderate-income urban families average 0.2 per cent lower than those of December and 0.4 per cent under those of November. The bureau's index in January was 113.9 per cent of the 1947-1949 average, compared with 113.1 in January, 1952.

Trends Fore and Aft . . .

The Federal Reserve Board's index of industrial production in January rose 2 points to 237 per cent of the 1935-1939 average. . . Shipments of plumbing fixtures in the fourth quarter of 1952 rose 9 per cent over the same period in 1951. . . Business failures in 1953 are averaging 8 per cent over the same period, a year ago. . . Contract awards for heavy construction in 1953 are about 46 per cent over the same weeks in 1952.

Clear your floor area

. . . of scrap strip

Quickly. . .

with an Allied Scrap Baler

. . . simple, inexpensive, electrically operated. Forms densely packed bundles 19" x 19", about 400 lbs. Wound up in a few minutes. Needs only one man.

Sell Bundles of Steel

Profitably. . .

. . . saves time, clears floor areas. A profitable means for quick salvaging right at shearing operations. Produces compact, saleable bundles ready for shipment.



ALLIED STEEL & CONVEYORS, INC.

17311 Healy • Detroit 12, Mich.

Complete Material Handling Systems

Designed • Fabricated • Erected

STEPPED-UP QUALITY

Use Ohio Rolls to step up your mill production.
Choose from 11 types of Ohio Iron and Steel Rolls:

- Carbon Steel Rolls
- Ohioloy Rolls
- Ohioloy "K" Rolls
- Holl-O-Cast Rolls
- Chilled Iron Rolls
- Denso Iron Rolls
- Nickel Grain Rolls
- Special Iron Rolls
- Nioloy Rolls
- Flintuff Rolls
- Ohio Double – Pour Rolls



Ohio Rolls

SHAPING METAL FOR ALL INDUSTRY



THE OHIO STEEL FOUNDRY CO.

LIMA, OHIO • PLANTS AT LIMA AND SPRINGFIELD, OHIO

Men of Industry

ROBERT C. TRUNDLE
. . . president of Trundle Engineering

F. J. KOEGLER
. . . new duties at National Lead

HARVEY R. HILLER
. . . Laclede-Christy gen. sales mgr.

Robert C. Trundle was elected president, **Trundle Engineering Co.**, Cleveland, to succeed **George T. Trundle Jr.**, elected chairman of the board, continuing in active charge of major policies. Added to the board of directors are **C. P. Hawkins** and **Lyman B. King**, both vice presidents.

Richard A. Williams was appointed director of engineering, **Comfort Products Corp.**, Dallas. He will be in charge of both design and research. Mr. Williams was for many years chief engineer with Yates-American Machine Co.

Responsibilities of **L. A. Dixon**, **Rockwell Mfg. Co.** executive vice president, have been expanded to include jurisdiction over the company's power tool operation, which includes the Delta Power Tool Division, Rockwell Tools Inc. and De-Luxe Saw & Tool Co. He is located at Pittsburgh.

Standard Horse Nail Corp., New Brighton, Pa., appointed **R. S. Merrick** vice president; **W. C. Sheers** manager, production and quality control; **H. K. Anderson** supervisor of customer service.

Thermal Transfer Corp., Pittsburgh, appointed **Joseph V. Schleisner** chief engineer and **Robert J. Sahr** sales engineer.

National Lead Co., New York, elected **F. J. Koegler** a vice president of the company and general manager of its newly formed Doehler-Jarvis Division. He started with Doehler-Jarvis Corp. in 1913, became a vice president in 1933, executive vice president in 1948 and president in January of last year. He makes his headquarters in Toledo, O.

Lloyd R. Wallis, secretary-treasurer, **Youngstown Foundry & Machine Co.**, Youngstown, was elected vice president and treasurer. **L. R. Massman** was named secretary and **B. S. Parker** was elected vice president and general manager. **J. Harry Reed** becomes manager of sales.

Pipe Machinery Co., Cleveland, appointed **Russel L. Gergen** sales manager, gage division. He has served the company in various capacities for 12 years.

Henry F. Arndt of the **Detroit Electric Furnace Division**, Kuhlman Electric Co., Bay City, Mich., was named chief engineer of the division to replace **Charles V. Kilburn**, who resigned to join Essex Wire Corp.

John R. German was appointed purchasing agent of **Shelley Steel Corp.**, Chicago. He had been with Inland Steel Co. for 25 years.

Harvey R. Hiller replaces **John L. Cummings**, resigned, as general sales manager, **Laclede-Christy Co.**, St Louis. Mr Hiller joined the company 30 years ago as a sales engineer, was subsequently named district sales manager, regional sales manager and assistant vice president of sales.

Kilbourne Knox Jr., for the last five years senior designer on hydraulic equipment with McDonnell Aircraft Corp., joined **Parker Appliance Co.**, Cleveland, as staff engineer in charge of engineering aircraft hydraulic equipment. **Edward W. Hollis** is manager of the new Cleveland sales office, while **Donald T. Boody** will head the new Los Angeles office in the plant of Parker Aircraft Co. **George A. Fort** was promoted from manager of quality control to general manager, rubber division, succeeding Mr. Hollis.

William F. Langefeld, director of purchases, Material Service Corp., joins **Maytag Co.**, Newton, Iowa, in a similar position. He succeeds **C. W. Clauser**, appointed personal assistant to the vice president of manufacturing.

Lincoln Engineering Co., St. Louis, appointed **T. V. Picraux** production manager for both its plants. **Albert J. Gruenewald** was made sales manager, industrial division, to re-

J. H. WERNER

J. L. KOZMA



VERNON L. MILLER

R. L. CORBETT

. . . newly appointed district managers at Lee Wilson Engineering

place Mr. Picraux, and **Robert E. Redenbaugh** manager of its original equipment division.

New district managers for **Lee Wilson Engineering Co. Inc.**, Cleveland, are **J. H. Werner**, southern and midwestern territory, operating out of Chicago; **J. L. Kozma**, centrally located in his territory at Pittsburgh; and **R. L. Corbett** who continues coverage of Ohio from the Cleveland office. **Vernon L. Miller**, formerly chief engineer, was made district manager for the eastern territory with headquarters in the New Haven, Conn., area.

Lee Johnson was made assistant manager of service, **Chicago Vitreous Enamel Products Co.**, Cicero, Ill. He succeeds **John McLaughlin** who now devotes full time to special projects.

District sales offices created by **Jones & Laughlin Steel Corp.** are managed by **E. W. Hoster Jr.** at Columbus, O., and **F. A. Haynes** at Louisville.

Firth Sterling Inc. appointed **John P. Sweeney** Detroit district manager and **Munro J. Mann** as assistant district manager. Mr. Sweeney succeeds **Gunther A. Jacobs.**

Sales representatives named to serve **Electro Refractories & Abrasives Corp.** include **John E. Courtney** at Detroit; **Charles W. Anthony**, central Ohio; **Sterling Muck**, Pittsburgh; **Peter Antonez**, New England; and **Robert C. Hebard**, Buffalo. Other changes include transfer of **Frank L. Doerr Jr.** from Detroit to Cleveland as grinding wheel sales engineer, and **William J. Eames** to Chicago.

Victory Steel Supply Co., Milwaukee, elected **H. A. Zartner** vice president in charge of estimating and engineering, and **David Becker** second vice president and general works superintendent.

Dr. Allen S. Russell replaces **Cyril S. Taylor**, retired, as chief, physical chemistry division, Aluminum Research Laboratories, New Kensington, Pa., **Aluminum Co. of America.**

Walter A. Madej was promoted to the newly created position of superintendent of the Utica, N. Y., plant, **Chicago Pneumatic Tool Co.**

A. L. Danielson succeeds **G. M. Wallace** as branch manager, Denver office, **Bailey Meter Co.** Mr. Wallace was recently appointed an assistant sales manager at Cleveland.

Curtis L. Bates joined **Ryan Aeronautical Co.**, San Diego, Calif., as assistant director of engineering. For the last ten years he has been with Northrop Aircraft Inc.

Lloyd W. Wendell was named executive vice president, **Federal Steel Warehouse Corp.**, Dayton, O.

Clarence C. Walters was appointed assistant chief engineer, **Republic Steel Corp.**, Cleveland.

Joseph E. Berman was elected president and chairman of **Industrial Metal Protectives Inc.**, Dayton, O., succeeding **H. A. Toulmin Jr.**, who sold his interest in the firm.

Geco Inc., Cleveland, an affiliate of General Engineering Co., appointed **M. E. Hackstedde** manager of its production heat division. He was sales engineer for the Tocco Division, Ohio Crankshaft Co.

Donald R. Moffat is district manager of the recently opened Cincinnati office, **Virginia Metal Products Corp.**

Flexible Co., Loudonville, O., ap-

Any time you fly in a Martin 4-0-4, Superior tubing is probably working for your safety.

Once you're airborne, watch the 840-pound main landing gear assemblies flip forward and up with amazing speed, even though they may be working against a 180 m.p.h. drag. Fast landing gear retraction gives you an extra margin of take-off safety because "clean" aircraft have better flight characteristics.

Chances are your Martin 4-0-4 contains many feet of Superior ½" stainless steel tubing. In the hydraulic system, this tubing operates at a pressure of 3000 p.s.i., normally. On Martin's torture racks, it has demonstrated remarkable endurance under violent pressure surges at 1000 cycles *per second*, even around minimum bends.

Performance like this may well have a bearing on your production problems as well as on your personal safety. Superior's long experience in fine tubing, backed by highly-developed production equipment and extensive research and testing facilities assures you of top-quality small tubing for doing tough jobs well. Outline your own production problems in a letter to us, right now—we'll send you complete information and the appropriate Data Memo by return mail. Address: Superior Tube Company, 2005 Germantown Ave., Norristown, Pennsylvania.

Round and Shaped Tubing available in Carbon, Alloy, and Stainless Steels, Nickel Alloys and Beryllium Copper.



Superior

THE BIG NAME IN SMALL TUBING

West Coast: Pacific Tube Company, 5710 Smithway St., Los Angeles 22, Calif. UNderhill 0-1331

All analyses .010" to ⅝" O.D.
Certain analyses (.035" Max. wall) up to 1⅜" O.D.

CHESTER A. SIVER
. . . joins Black, Sivalls & Bryson

E. O. BURGHAM
. . . gen. supt. at Weirton Steel

JOHN D. SMALL
. . . V. P., Pressed Steel Car Co.

pointed **J. F. Gettrust** western sales manager, and **Harold E. Hilty** eastern sales manager.

Black, Sivalls & Bryson Inc., Kansas City, Mo., appointed **Chester A. Siver** as general manager of engineering. Before joining the company he was manager of engineering, Liquid Carbonic Corp., durable goods division, and previously was associated with American Machine & Foundry Co. and Linde Air Products Co.

John L. Cummings joins **Davis Fire Brick Co.**, Oak Hill, O., as vice president and sales director. He formerly was general sales manager of Laclede-Christy Co.

G. A. Tamblyn was made sales manager of **Frank G. Hough Co.**, Libertyville, Ill. With the company 11 years, he has been assistant sales manager since 1948.

Following resignation of **J. Stewart Williamson** as vice president in charge of operations of **Weirton Steel Co.**, Wierton, W. Va., **E. O. Burgham** was promoted from general superintendent to vice president. Other promotions include **J. H. Strassburger** to assistant vice president assigned to the engineering department in charge of research and development; **Alfred E. Kadell** from manager, tin mill, to general superintendent; **Glenn Gould** as tin mill manager and **Arch Miller** as assistant manager. Mr. Williams, who finishes 35 years of service with the company, continues in a consulting capacity.

Promotions at **Benjamin Wolff & Co.**, Chicago metal distributor, include **Duane S. Seavey** as Chicago district sales manager and **Herbert F. Peterson** as manager of aluminum product sales.

John D. Small was elected vice president, **Pressed Steel Car Co. Inc.**, New York. From November, 1950, until last year he served as chairman of the Munitions Board, U. S. Department of Defense. Previous to that he was an executive with Emerson Radio & Phonograph Co.

Carleton P. Adams was appointed advertising manager and **Newcombe C. Baker Jr.** as manager, special sales promotion of Yale Materials Handling Division, **Yale & Towne Mfg. Co.**, Philadelphia. Mr. Adams was formerly with Quaker Rubber Corp. as director of advertising and sales promotion.

Merritt S. Stevenson was made manager of transportation sales for **Baker-Raulang Co.**, Cleveland.

Wallace A. Gray has become a

Please turn to Page 140

OBITUARIES . . .

E. P. Langworthy, 65, president, **Bearium Metals Corp.**, Rochester, N. Y., died recently in Florida.

Benjamin H. Howell, 77, president and founder of **Garfield Mfg. Co.**, Garfield, N. J., died Mar. 1.

Anton P. Rabas, 65, president, **Niagara Metal Works Inc.**, Buffalo, died Feb. 16.

Rudolph J. Thurner, 74, founder and president, **Thurner Heat Treating Co.**, Milwaukee, died Feb. 22.

Irving R. Smith, 69, president, **Sterling Wheelbarrow Co.**, West Allis, Wis., Lawran Foundry Co. and affiliated firm, Sterling Foundries Specialties Ltd., died Feb. 26. He was also a director of Safway Steel Scaffolding Co. and Smith Engineering Works, both in Milwaukee.

Harry A. Ball, retired steel drum manufacturer, who established **H. A. Ball & Sons**, died Feb. 22.

James I. Minteer, 51, secretary, **Stewart - Warner Corp.**, Chicago, died Feb. 24 of a heart attack.

Harold F. Ziegler, 52, president, **Tanktainer Welded Products Inc.**, Gary, Ind., died Feb. 22.

Theodore B. Drescher, 58, a vice president, **Bausch & Lomb Optical Co.**, Rochester, N. Y., died Feb. 22.

W. Raymond Steele, secretary, **E. D. Clapp Mfg. Co.**, Auburn, N. Y., died Feb. 16.

John M. Lepo, 46, Chicago sales manager for **McLouth Steel Corp.** died Feb. 25.

There's No Guesswork in the Making of WICKWIRE WIRE

Guessing games can be lots of fun. But not to our engineers and metallurgists. They take a dim view of guesswork of any kind—particularly when it comes to making wire.

Steel for Wickwire Wire comes from our own blast furnaces and open hearths, is made exclusively for wire and wire products; precision drawn and processed in our own modern wire mills.

That way, our engineers and metallurgists maintain constant and careful control over the quality of Wickwire Wire. That way, through precision testing and inspection, they *know for sure* that the Wickwire Wire you buy is always of unvarying uniformity in size, surface, tensile strength and degree of stiffness and ductility.

Whatever your needs in specialty steel wire—high or low carbon steel; round or shaped; in all sizes, tempers, finishes and grades—it will pay you to remember: FOR THE WIRE YOU REQUIRE...CHECK FIRST WITH WICKWIRE.

THE COLORADO FUEL AND IRON CORPORATION—Denver, Colorado
THE CALIFORNIA WIRE CLOTH CORPORATION—Oakland, California
WICKWIRE SPENCER STEEL DIVISION—Atlanta • Boston • Buffalo
Chicago • Detroit • New York • Philadelphia

WICKWIRE WIRE

PRODUCT OF WICKWIRE SPENCER STEEL DIVISION
THE COLORADO FUEL AND IRON CORPORATION

CF&I

4176



GO "AMERICAN" FOR CIRCULAR WELDED PRODUCTS

when product designers need help on products they specify and buy, American Welding offers 34 years' experience, complete designing, engineering and metallurgical service, where fusion or resistance welding of either ferrous or non-ferrous metals is required.

drop a line to our product development division

A company you'll like to deal with

AW

THE AMERICAN WELDING & MANUFACTURING CO. · WARREN, OHIO

Send for your copy of our 20 page illustrated catalog

LET US SEND YOU MORE FACTS OR BETTER YET SEND US YOUR SPECIFICATIONS FOR PROMPT QUOTATIONS

Production and Engineering
NEWS AT A GLANCE

SURFACE CHECKS—Smaller shops can determine surface finishes to meet drawing specifications at relatively low cost with "surface sticks." They consist of various surface specimens individually finished to definite microinch readings and grouped together in finish-comparison bars. The operator holds the bar opposite his work in the machine to make a fast accurate visual comparison check of surface roughness, waviness and lay. Acme Industrial Co., Chicago, makes them up in either round plug or rectangular form in boxes accommodating 3, 5 or 8 assorted surface finishes.

DIVIDENDS OF PATRIOTISM—A patriotic alternate to regular nickel-chromium stainless steel is now paying off at the Budd Co. A severe nickel shortage came up at the start of the Korean War. The shortage caused the government to limit steel for most civilian uses to 1 per cent nickel maximum. The order sent Budd looking for a satisfactory alternate to furnish the life blood of its railway car production line. They went to Allegheny Ludlum to find out if it was possible to create a stainless steel that retains all the characteristics of 18-8 type material and do it with only 1 per cent nickel. Working together the two companies came up with TRC, so called because of its first commercial application as a trailer-rail car steel. Budd now has used some 600 tons of the new steel in rail cars and highway trailers. One big item—they made no tooling changes of any sort. p. 94

LEAK SPOTTER—Freon-12, best known as a refrigerant, is finding a big new field as a leak detector. Under pressure it's a colorless, virtually nontoxic and odorless liquid. When released from pressure at room temperature it changes into a gas with an ability to seek out and escape through the finest openings in almost any material. Exact location of leaks can be found quickly with an electronic device or a gas-burning torch whose flame changes color in contact with the nonflammable Freon. The electronic unit, made by GE, is so sensitive it can uncover a leak so small that it would take 100 years for an ounce of Freon to escape.

TOP HANDLERS — Originally many companies hired women as industrial truck and crane operators during the war years as an emergency measure and were surprised to find that the ladies performed with distinction. Carrier Corp., Syracuse, N. Y., went a little further and made a complete study of the efficiency, load spotting ability, etc., of feminine materials handlers as compared to the men. The ladies won in a walk. They maneuver their vehicles as well or better, don't have an after lunch slump like the men do and can place overhead crane loads more precisely, making them safer to work with and less likely to damage loads. Male truck and crane operators are outnumbered about 4 to 1 by women in Carrier plants.

CLIPPED-WING PRODUCTION—The aircraft industry which has just about everything flying along in high gear is usually faced with relatively slow production methods. There's a good reason for it though—most all airframe producers operate on a short lot basis. At Douglas' El Segundo plant, the engineers have altered some standard production machines to fit their short-run system. Slotted dies for the drop forge hammers permit a fork lift truck to lift from the sides rather than from the bottom of the die. This cuts handling time usually associated with die changes. Adjustable feeds on all punch presses is another example of higher production methods through ingenuity. p. 98

LOOKING GOOD—Rapid progress is being made on welding and working techniques for molybdenum, the promising metal for high temperature use. The Ugine-Sejournet method looks good for extrusions. Two major problems that are being studied now are coatings to protect against oxidation and a so-called brittle phenomenon. Researchers working on brittleness find that high purity molybdenum with less than 0.001-per cent oxygen shows remarkable ductility characteristics. Concerning coatings, people in the know are predicting success within the year.

POCKET-SIZED POWER—Makers of the diminutive engines that power chain saws and the like use mass-production methods to lower cost, increase production—and they have come up with interchangeable parts. An example is the crankshaft line at McCulloch Motors Corp. where shafts enter the line as rough forgings and leave as finished units at a rate of about one per minute. Machine tools in this line include five automatic lathes, grinders and induction heater for hardening. p. 102

INTRICATE BROACHING—A standard machine broaches intricate internal contours of aircraft engine parts in a setup devised by Colonial Broach Co., Detroit. The six identical contours between the internal lobes on the part are broached in two passes, three alternate contours in the first pass and the three remaining in the second. A two station fixture facilitates locating from offset holes in the part. A built up type broach is used incorporating inserted broach sections. Twelve dowels in the fixture, above and below the part, engage six holes in six lobes in the part, providing complete support of the lobes during broaching and holding the thin walled projections so as to effectively prevent distortion during the broaching operation.



Stainless is drawn through these rollers at Budd Co. to form corrugated strips for roof of railway cars



Fabricating the roof section of all stainless steel passenger cars. Strips are welded together here

New Stainless Stretches Nickel

A significant development of the Korean war is chromium-manganese austenitic stainless containing only 1 per cent nickel. It has strength and fabricating properties of type 301

By DR. ALLEN G. GRAY
Technical Editor

DEVELOPED as an alternate to regular nickel-chromium stainless steel, a new type manganese-chromium stainless with 1 per cent nickel is doing a good job at the Budd Co.

Designated as TRC because of its first commercial application by Budd as a trailer-rail car steel, this new grade of stainless has the composition: 15.0 per cent chromium minimum; 16.50 per cent manganese nominal; 0.10 per cent carbon maximum; 1.0 per cent nickel maximum, and 0.15 per cent nitrogen nominal.

For a long time Budd engineers have been convinced that high tensile austenitic stainless steel is the best structural material for railway passenger cars and truck trailers. It has advantages aside from obvious one of corrosion resistance. Its use, however, did involve a new philosophy of design. The problem was one of thinness and how to make it effective in compression or in panels.

Type 301 containing 17 per cent chromium and 7 per cent nickel did the job.

Really Needed—The Korean war started a search. A severe nickel shortage caused the government to limit steel for most civilian uses to 1 per cent nickel maximum. This order sent Budd looking for a satisfactory alternate to furnish the life blood of its railway car production line.

They asked Allegheny Ludlum if it was possible to create a stainless steel that retains all the characteristics of 18-8 type material and do it with only 1 per cent nickel.

Working together, Allegheny Ludlum did laboratory and mill research and Budd made on the job tests. Result: TRC. Budd has now used some 600 tons of the new steel in rail cars and highway trailers. By now a number of producers have supplied the steel.

Does It Work?—Budd states they made no tooling changes of any sort. A sheet of TRC can follow one of regular 301 through any of the fabrication processes and the operators do not realize any substitution has been made.

Looking at yield and tensile strengths, TRC is essentially equivalent to type 301 (see table). Type 430, a straight chromium stainless containing no nickel was unsatisfactory for Budd's requirements because the high physical strength of 301 could not be obtained. Some type 430 is used, however, for interior trim and applications other than structural.

Fabrication of stainless at Budd is typical of many sheet working plants except that stamping and deep drawing operations are on the lean side. Side and roof panels are corrugated by pulling strips of stainless through form rolls on a

TRC—STAINLESS

Chemical Composition

Chromium	15.00% Min.
Carbon*	0.10% Max.
Nickel	1.00% Max.
Manganese	16.5% Nominal
Nitrogen	0.15% Nominal

*For gages 0.050-in. thick and below 0.12 max. carbon is allowed.

This all stainless steel rail diesel car that Budd builds contains about 27,000 pounds of TRC. This is part of an order that will bring total to 40

draw bench. Structural sections are formed on a power brake.

Typical of Stainless — Shearing or punching stainless steel requires more power than for ordinary carbon steel — because stainless is stronger and as a result its strength in shear is greater. The best shear blade is very hard at the edge, yet tough enough to resist the high impact loads produced.

Stainless may be readily handled in forming, drawing and spinning operations. As the tensile strength of the stainless is increased by cold rolling prior to the forming operations, its ability to be formed by these processes is decreased, for they all depend upon the ductility of the metal.

Fairly difficult stampings have been made of stainless with a tensile strength of 135,000 psi. In complex or very severe forming it may be necessary to anneal the piece between stages of the forming operation.

Drilling—Tools of high-speed are used when drilling stainless. The tool is ground somewhat more flat than standard, an included angle of about 140 degrees is generally used. Drilling is at a slower speed than for ordinary steels. The tool point should never be allowed to ride over the material without cutting.

With the possible exception of an indicated slightly greater drill wear, although this is not based on actual measurements, no change has been apparent in either tool or die life in going from type 301 to TRC.

Avoids Corrosion — Wherever possible fabrication is done by the Budd developed Shotweld system. This system is a resistance spot welding process which accurately controls and regulates the welding variables, principally time of current flow, to produce welds of adequate strength and freedom from harmful carbide precipitation.

Stainless is normally a solid solution obtained by heating to some 2000° F and cooling rapidly. Subsequent cold rolling does not substantially change this condition. Reheating to the range between 900 and 1400° F, however, may cause carbide precipitation. This metallurgical change in the structure of the steel lowers its corrosion resistance. The degree to which this change takes place is dependent on the temperature and also on the time of dwell within the harmful temperature zone.

The Shotweld method consists in greatly reducing the time of current flow in welding so that the very steep temperature gradient from the weld metal to the surrounding zones allows no time for deleterious carbide precipitation to take place.

Par or Better — Tests in single Shotweld lap joints show TRC to have somewhat better fatigue strength than 301 in the same section and condition. In single Shotweld U-form tension specimens, fatigue strength of the two are about equal.

Some arc welding of stainless is done at Budd. Arc butt-welded specimens of TRC show 10 per cent higher joint efficiency in tension than 301. The same samples tested under fatigue stressing do not show a significant difference in fatigue strength. However, 301 has a higher ultimate tensile strength. Maximum of 0.10 per cent carbon specified for the steel minimizes possibility of intergranular corrosion resulting from carbide precipitation.

Resists the Elements — Budd is working hard to establish definite corrosion resistance data for TRC compared with 301. Emphasis is being placed on long-term exposure to various atmospheric conditions.

These tests have been under way for about one year in several locations, including industrial areas of Pittsburgh, New York, Philadelphia and Niagara Falls, rural areas, and at the International Nickel Co. testing station at Kure Beach. With exception of Kure Beach and Niagara specimens, which have not been evaluated, test panels show no evidence of corrosion.

On the basis of these and labora-



Shotweld process makes possible the use of stainless steel for entire car structure. Results obtained with TRC are fully equivalent to type 301

tory tests, Budd metallurgists' rate TRC the equivalent of 301 for its railway car and highway trailer applications. If a percentage scale is used and type 301 is considered the standard, TRC rates 100 per cent on general atmospheric corrosion.

In 100-hour, 20 per cent salt spray test, TRC specimens showed slight attack, a shade less than type 430 test panels, while type 301 showed no attack. Budd scientists feel that salt spray tests mean very little in terms of performance of steel on railway cars.

No Difference—One of the points checked in the corrosion tests by Budd was the effect on corrosion resistance of lowering the chromium content of TRC about 1 per cent. In going from chromium content in the 16 per cent range down to the 15 per cent range no significant effect on corrosion resistance was noted.

Producers have less trouble rolling the 15 per cent chromium type than they had when they tried to handle a 16 per cent chromium version which was in the picture early in the game.

Not Easy—Most producers feel that there are still mill troubles in working with the chrome-manganese steels. Difficulties are sometimes encountered in breaking down ingots into slabs. Heats may develop edge cracks in the blooming mill. Yields have been low at times.

Beyond the slab stage rolling difficulties tend to smooth out. Production is still principally strip; sheet is scarce.

Although progress is being made on mill problems, producers feel that there will be some mill troubles as long as they have to work with ingots containing 1 per cent maximum nickel. Relaxation of government restrictions even to the extent of allowing 2-3 per cent nickel would likely eliminate many of the mill's present problems with this steel.

Some producers still feel same as they did early in the game that the chrome-manganese stainless is being produced on an emergency basis for manufacturers who have been cut off from the 18-8 type because of government restrictions on nickel, and who cannot use the straight chromium type, such as 430, because of engineering reasons.

In spite of these mill problems, however, Budd reports that they are receiving TRC at a rate adequate to meet their production schedules. They feel that their success with the steel gives promise of its remaining on the scene even when present nickel restrictions are lifted.

Some metallurgists in chrome-manganese steels from the start feel that a permanent stainless useful for some applications might take the form of a TRC with chrome boosted up to 17-18 per cent and nickel raised to 2-3 per cent.

Old Idea Dusted Off—The fact that manganese, like nickel, will produce an austenitic structure in steel is not new. In the early twenties, metallurgists at Union Carbide's Electrometallurgical Division investigated and patented a whole series of chromium-manganese stainless steels. In 1940, when nickel became short those steels which indicated greatest promise for combined corrosion resistance and strength to compete with chromium-nickel steels were subjected to an extensive series of tests.

They found that the cold rolled

Nearly complete all stainless passenger car progresses down assembly line

REVISED TENTATIVE INFORMATION FOR SUPPLIERS OF STAINLESS STEEL TYPE TRC TO BUDD CO.

Temper	Finish	Yield Strength Min.	Tensile Strength Min.	Tensile Strength Max.	% Elong. min.	Bend Radius Axis Par. To Gr. & Angle	Desired Max. Rock B
LT	2D	40,000	80,000	115,000	50	Zero Rad. 180°	95
	2B	45,000	80,000	120,000	40	½T-180°	105
ST							
0.020 & Under	2B	60,000	110,000	135,000	35	½T-180°	
Over 0.020	2B	60,000	110,000	135,000	35	1T-135°	
MT							
0.020 & Under	2B	75,000	120,000	150,000	25	½T-180°	
Over 0.020	2B	75,000	120,000	150,000	25	1T-135°	
HT							
0.020 & Under	2B	110,000	140,000	165,000	18	½T-180°	
0.020 to 0.156	2B	110,000	140,000	165,000	18	2T-135°	
Over 0.156	2B	100,000	125,000	165,000	18	2T-135°	
VHT							
0.125 & Under	2B	135,000	.....	185,000	10	3T-135°	...

The minimum yield strength and bend properties must be met. All other mechanical properties are desired values—values that are not rejection limits but aims.

manganese and manganese-chromium steels could be readily formed, drilled and machined and they were easy to weld. Physical tests showed these steels to have strengths equal to the best of stainless steels with no practical loss in ductility.

At that time a 16 per cent manganese 12 per cent chromium composition containing about 0.3 nickel, 0.2 silicon, and 0.14 carbon was singled out for further study. This steel could be cold-rolled to high strength with retention of ductility.

Welding operation on small section of all stainless steel railway car

Another property noted: High resistance to atmospheric corrosion.

In the Picture Too—Where does manganese fit into the TRC picture? Both low carbon, low phosphorus ferromanganese and electrolytic manganese are being used for the chrome-manganese stainless. Electrometallurgical Division of Union Carbide & Carbon Corp. produce a grade of ferromanganese with maximum 0.07 per cent carbon and maximum 0.06 per cent phosphorus for the purpose.

The fact that high purity manganese can substitute for critically short nickel in producing an austenitic stainless has lent impetus to expansion in electrolytic manganese.

A relatively new product it contains 99.9 per cent manganese and is almost entirely free of carbon, phosphorus, silicon and other impurities. Supplied as a chip, it is the end product of an electrowinning process. Producers feel that it is competitive at about 30 cents a pound with the low carbon ferromanganese.

More Electrolytic—Expansion is on two fronts. With the help of a $2,250,000 government loan, the Electromanganese Corp., Knoxville, Tenn., is expanding its facilities to double its production of the metal which is now at a level of 7.2 million pounds a year. By midyear production at this company is expected to be at the rate of 15 million pounds yearly.

Electrometallurgical Co., long a producer of ferromanganese, has obtained a certificate of necessity of the order of some $13 million to construct an electromanganese plant in the Marietta, O. development area. When this plant comes in, total production may be at potential rate of twenty to thirty million pounds a year.

As to if this will be enough is anybody's guess. Whether or not the 16 per cent manganese-15 per cent chromium version sticks is elementary. It will probably lead to some chromium-manganese steels which will be modifications and which will be found very useful when increasing amounts of elements are available or better known, that will give a more completely austenitic steel than is possible with the present combination of nickel and nitrogen.

Perhaps the 1 per cent nickel variety of this new stainless won't stick. But there is good evidence that steel producers are giving plenty of thought to the substitution of some manganese for nickel to keep the properties of the 18-8 type. The end result may be a compromise but chances are good that some form of the manganese-chromium stainless, perhaps now in the experimental stage, is here to stay.



This tube bender was modified to facilitate short-run production of small radius bends. Controls for each phase of the bending were added to the original design

Truck with hydraulically adjustable forks deposits drop hammer die on the bed. No overhead cranes are required in either the storage yard or drop hammer department

Modifications Speed Short-Run Operations

Standard production machines at Douglas' El Segundo plant are altered to fit peculiarities of aircraft manufacture. Plant engineering department gets the job and the credit

By D. G. McCONNELL
R. C. BEAVER
Machine Design Engineers
Douglas Aircraft Co.
El Segundo, Calif.

WHILE most types of standard production machines are employed in some facet of the aircraft industry, many of these machines require certain modifications in design or principle to make them efficient in aircraft work. Generally speaking, the most outstanding feature of these machines—that of high-speed repetitive production of the same part—is the one feature that cannot be used efficiently in the airplane shops.

The value of this high-speed repetitive production feature is greatly nullified by the relatively short production runs encountered in most aircraft work. Machine setup time is of little consequence when the setup will be employed over a six-months' period to turn out a hundred thousand parts. But setup time becomes extremely important when only a hundred parts will be produced, and several setups each day are required. Many more production runs in the aircraft industry will vary downward to 50, 25, or even a dozen parts.

Modified Standards—In general, most production machines are a fairly standard item and are purchased as such by the aircraft industry. The modifications to simplify setup, reduce die costs, and minimize service and personnel requirements, are made after the machine is installed. At the El Segundo division of Douglas Aircraft Co., these modifications are studied, engineered and installed by the plant engineering department. A group of specialists ar constantly at work, trying to mod ify standard production machine to secure more efficient short-ru production.

While the details involved i these modifications are limited t specific machines, the idea behin each modification is generally ap plicable. We will therefore confin our discussion in this article t cases where the idea is paramoun and where detail may be worke out according to existing cond tions.

Consider Drop Hammers — Dro hammers are a widely used stan ard production tool. In some in dustries, a drop hammer may b used for days, or even months, repetitive production of the sam

art. When and if the hammer es are changed, the actual time quired and the inconveniences ncountered are of little conse- ience.

In the aircraft industry, this sit- ation is reversed. In most cases, e drop hammer dies have to be anged several times each day, d setup time requirements are of aramount importance. At Doug- s, we tackled this drop hammer e changing problem as the one cet in the process where major novations could be made to im- ove short-run production.

Slotted Dies — The same 3600 op hammer dies in use were re- signed with cast-in slots along posite sides of the die. Purpose these slots is to permit use of fork lift truck, lifting from the des rather than from the bottom the die. Concurrent with die re- sign, two fork lift trucks, one 10,000-pound capacity and the her of 30,000 capacity, were uipped with hydraulically ad- stable lift forks.

With this equipment, the lift uck operator can approach a die, just the width of his lift forks fit in the slots along each side the die, lift it, transport it to e drop hammer department, then sert it over the bed of the drop ammer. At this point, the lateral ift arrangement is used to posi- on the die exactly over the ham- er bed before it is lowered into sition. No pinch bars are used r final positioning; no overhead anes are required throughout the e changing process.

Two-Way Radios—To further ex- edite frequent die changes, each the lift trucks is equipped with low-power industrial radio trans- itter and receiving unit, tuned to similar unit in the dispatcher's fice. When the drop hammer op- ator is ready for a die change, he lephones the dispatcher the nec- sary information. The dispatch- then contacts both lift truck op- ators and passes this information ong.

One truck operator then goes to e drop hammer, removes the old e from the hammer and trans- orts it to the storage area. Mean- hile the second truck secures the quired new die, brings it to the op hammer department, and sets it on the hammer bed. The entire die changing operation requires but a few minutes.

Easy Storage—Several other advantages have accrued from our new drop hammer die handling system. Hammer dies can be stored in any area not equipped with an overhead crane. No pallets are required in stacking the dies (because they are lifted from the sides), thus giving a firmer and safer pile. Dies can be stored in any unused outside area, and stacked in piles about 5-feet high.

It is easy for the truck operator to lift aside dies he does not want to secure one deeper in the pile. Despite the huge size of our drop hammer department, only three men are required to handle all the die changing work—one operator on the smaller lift truck, and an operator with a helper on the big unit.

Tube Bending Machines — While modifications to improve drop hammer production were confined entirely to machine setup and servicing, modifications in the machine itself were necessary in our tube bending department. We started this operation with a No. 2 Pines aircraft tube bender, ideally tooled for high production repetitive bending of long radius bends. The machine was fully automatic, with only a start-and-stop button and a control for operating the tube clamp.

We soon discovered, however, that automatic sequence operation of the tube bender was not compatible with the high precision, small radius tube bending necessary in advanced aircraft work. Many of the bends we had to make were prototypes, and production runs on others were small. More control of the bending operation was needed to produce the types of bends required.

Console Control—To provide this control, a console-type control cabinet was designed and installed so that each phase of the tube bending operation could be individually controlled by the operator. Today, separate controls are employed for the rotating head, the mandrel, the tube clamps, and for starting and stopping. The clamping block is operated separately from the follower block, and the rotation sequence is separate from either clamping operation. By separating the clamping operations, a tube with more than one bend may be rotated and checked before the follower clamp is moved into position.

Other tube bender modifications included bringing all the tube bender operating surfaces into a common plane. This was accomplished by designing an auxiliary bolster plate with T slots as a positive

Hydraulically controlled spinning tool designed for spinning heavy gage material. Spinning pressure is controlled by valve under the operator's thumb



Dial indicator on this hydraulic straightener measures deflection during straightening. Over-straightening is calculated to just offset springback

clamping surface for the wiper die. The original back-up stock for the clamp block was redesigned using 4130 chrome moly steel. The side block, originally of hard brass, was redesigned using 4130 chrome moly steel with hard brass inserts in the slide area.

Using this modified tube bender, our tube bending department is constantly precision-bending tubing material that is normally classed as "unbendable," and have produced many "impossible" one-diameter bends in stainless steel, aluminum, and alloy steel tubes.

Press Control Unified—Not long ago, a new Bliss 800-ton hydraulic press was installed at the Douglas El Segundo plant. While this press, in its original form, was ideal for high-speed repetitive metal forming work, die changing was complicated by the location of controls at four different places around the press. Necessity of changing the press dies several times each day, and also the fact that normally only two men were employed on the press at a time were burdensome complications.

After some study, the Douglas plant engineering department came up with a single cubical control panel that could be operated from one position. All controls, including ram pressure, downstroke and final pressure, stroke limitation, and draw ring cylinder pressure, were led into this single control station. This consolidation of controls has resulted in considerable time-saving insofar as die changing is concerned.

Built Router Motor—While routers are suited to short-run production work, most of them are designed for cutting relatively thin gage material. As air speeds increased and airframes became stronger, we began routing parts from heavier materials. Conventional router motors would not take the beating incurred by this heavier routing work. Now we are using a Douglas designed router motor. All parts for this motor, except the bearings, are made in the Douglas shops.

This motor delivers from 5 to 7½ hp at 20,000 rpm. It is cooled by a mist of lard oil-kerosene mixture blown through spiral grooves around the motor case enroute to its final objective to lubricate the single-flute cutter. A secondary cooling system is incorporated which blows a special bearing oil lubrication mist directly through the motor and then out the nose.

Spinning Problems — On deep draw work in heavy gages it became impossible for a single man to manipulate a conventional spinning tool or bat. Two men per tool were tried, but this combination prevented either man from obtaining the necessary metal flow feel so important in critical metal spinning work.

A hydraulically operated metal spinning bat was designed and built, wherein the main spinning pressure was applied hydraulically but enough manual pressure was used so that the single operator could obtain the necessary feel. With this tool, greater or lessened spinning pressures are obtained by a hydraulic valve control located



This rotary fixture permits automatic orientation of parts and patte Complex contours are quickly duplicated without any additional machini

nvenient to the operator's thumb. It was also discovered that avail- le metal spinning lathes operated o fast for most aircraft produc- on work in the heavier gages. To fset this, clutches were designed d installed to permit lathe oper- ion at variable speeds downward 50 rpm.

Precision Modifications—Some of ie modifications in standard equip- ent are made for the sole purpose obtaining the high degree of pre- sion necessary in all aircraft com- onents. One of these modifica- ons appears on our hydraulic raightening presses. Critical dial dicators are installed on each ma- ine.

These indicators are actuated ly after the part becomes crit- ally straight in the press, then easure the over-straightening ecessary to exactly offset spring ack when the part is removed om the press. After the first art is straightened and spring ack measured, each subsequent art can be critically straightened sing the same dial indication.

Some Improve Productivity—In few cases, standard machines are odified to improve their produc- on potential. We installed a high- ycle router motor on a Hydro-Vari achine, then equipped it with a owered horizontal rotary fixture or the orientation of part and pat- ern. Thus despite complicated ex- ernal contours on the part, a pat- ern may be duplicated rapidly and fficiently, and without the neces- ity of subsequent machining on ug areas, attachment areas, or ther external contour variations.

Other Innovations—At Douglas, ve have made many other innova- ions to improve short-run produc- ion in our punch press depart- ent. Some of these modifications ad to do with machine operation, thers with the problem of constant ie changing, and still others with aterial handling and conservation.

To begin with, all our punch resses are installed with a sharp ackward slant so that punched lanks will automatically fall from he dies backward into a container t the rear of the machine. Rub- er of compression washers of bout Shore 40 hardness are glued n the pierced blank templates to lear blank from dies. This elimin-



Raising the lever just above the operator's left hand releases the die and when lever is pulled forward again, the new punch die is clamped into place

ates the necessity of the operator to pause between each operation to remove the blank.

Adjustable Feed—Secondly, each of our punch presses has been provided with an adjustable feed table so that all material feeding into the press is correlated with die height and angle. The need for blocking or angling of the material is entirely eliminated. A second adjustable table beyond the dies receives the scrap strip.

Another innovation was to provide each punch press with quick acting clamps for die installation. A single action releases the dies being removed; another action clamps the dies after they have been centered in position. The actual time involved in die changing is negligible.

Strip Pre-Cut—Raw material for the punch press department is furnished in pre-cut strip form. Prior to the production of each part, the width of strip stock from which it can be punched with a minimum of waste is determined. Production orders then denote the width of strip to use, and punch operators are further relieved of a responsibility.

When a production order enters the punch press department, it goes first to the man in charge of die storage. Here the proper die set is selected and sent along with the production order to the material man. The material man then places the specified strip stock, enough to produce the order, along with the dies and production order, and delivers the entire package to the punch press on which the parts will be blanked.

Next Order Waiting — Each punch press is provided with waiting tables just above the feed table. Thus, when the press operator completes one production order, the material and dies for the next are ready at hand. He merely releases the old dies, places them on a cart for return to storage, slips the new dies in place, clamps them, pulls the raw material down onto the feed table and is ready to go.

After the above innovations, production in the punch press department, without additional machines or personnel, increased an average of 50 per cent.



Cylinder walls are knurled on this McCulloch-built machine to a finished depth of about 0.003-inch. This improves service life and also lubrication properties

Another company-designed and built machine is this on for flame hardening the outer edges of saw cutterbars Oxyacetylene flame and water spray are on one mountin

Production Is Heavy On Lightweight Engines

Builder of power chain saws and other engine-driven products needs highly integrated operation. Specially built machines turn out complicated parts in volume

By NORMAN LYNN
Los Angeles Correspondent

PRODUCING identical parts requires integration, or close control of all phases of the manufacturing operation. In addition to integration, alert managements are finding specialization in machine utilization can also bring large savings in production. For example, one minute saved on an item produced at the rate of 50,000 a year can be worth as much as $5000 saved in labor and overhead.

A case in point is McCulloch Motors Corp., Los Angeles, manufacturer of power chain saws, which has carried the techniques of specialization and integration of machine tools to a fine degree of perfection. The McCulloch plant is designed for mass production of lightweight engines and engine-driven products. Main plant area is approximately 232,000 sq ft, exclusive of detached buildings.

Products Complicated — McCulloch's products are relatively complicated but lend themselves to volume production. Manufactured are: Model 5-49, model 7-55, chain saws; earth drills, post hole diggers, powered and portable centrifugal pumps, lightweight engines for military target airplanes, and, just recently added, a new and quite revolutionary twin-rotor helicopter.

The vast majority of components for the company's products are manufactured within its own plant, as a means of controlling quality and delivery. The company uses a variety of special purpose machine tools to achieve high production and high quality.

Crankshaft Production — The crankshaft line is one of the features of the McCulloch plant illustrating its mass production capabilities. Crankshafts enter the line as rough forgings and leave as finished units at a rate of about one per minute on current schedules. Machine tools, worth $250,000 in this line alone, include five automatic Sundstrand lathes equipped with top, front and back slides, an air chucks, Norton grinders, an induction heater for hardening.

The main saw engine assembl line, moved by a chain-driven con veyor, is manned by 19 operators each one performing from three t 13 operations, totaling 146 opera tions. Average output of engine per day is 300 for an 8-hour shift From 45 to 60 minutes are require to assemble each engine.

Fast Piston Turning — Sund strand automatic lathes are use to machine model 3-25 pistons. I 11 tool operations completed in 2 seconds, the lathes turn the out side piston diameter to tolerance o 0.00011-inch on outside diamete face the dome to 0.0006-inch, roug and finish cut and chamber rin grooves. The piston shirt i counterbored before this lathe oper ation takes place. An 11-operatio tolerance check insures acceptanc

A Barnes boring machine for bo ing pistons is driven by five electri

An Electrocardiogram for an O.B.I.?





What if doctors could re-design the human body? Maybe the first thing they'd do is strengthen the heart—fix it so it wouldn't give out before its time. A tough job for the doctors, but with presses it's a different matter. Because for years that's essentially the kind of treatment open back inclinable presses have had from Clearing engineers.

That's why the frames are all steel weldments, with more rugged bearings, pitman connections and adjustments. Clearing designers have analyzed functional disorders and engineered preventive maintenance into the press. So if you're looking for presses that stay young and trouble-free longer, find out about Clearing inclinables.

CLEARING MACHINE CORPORATION

6488 WEST 65TH STREET • CHICAGO 38, ILLINOIS

HAMILTON DIVISION—HAMILTON, OHIO



Illustrations on this page are of the Clearing 150 ton inclinable press.

℞ FOR A LONG, USEFUL LIFE



SEND FOR THIS CATALOG

It will show you what you get in a Clearing O.B.I. Write for free copy today.

1. **FRAME**—All steel welded, fully stress relieved. Ample reinforcing at critical points.
2. **BEARINGS**—Long wearing bronze. Split cartridge type for easy servicing.
3. **ADJUSTMENT**—Adjustment screw buttress threaded for greater strength. Easy to adjust in fine increments.
4. **CONNECTION**—Wrist pin supported from below eliminates shear stresses. Unique construction keeps dirt out of bearing surfaces.
5. **GIBS**—Extra long. Square gibs in rear hold finer alignment. Both front gibs adjustable.

INCLINABLE PRESSES FROM 30 TO 200 TONS

CLEARING PRESSES THE WAY TO EFFICIENT MASS PRODUCTION

CMC CLEARING



Finished hand saw weighs 25 pounds, develops 3 hp and is able to cut through 2-foot trees and logs in 1 to 2 minutes. The lightweight engine is McCulloch design

Stress relieving is done in this thermal cabinet which is heated by banks of lamps, 35 to a side. Speed can be set accurately according to thickness of the part

motors; four 3 hp and one 1 hp. Simultaneously three cylinders are rough bored and three finish bored while the operator is loading the third set of three cylinders. The machine is equipped with dial controls for indexing, starting, advancing; and cooling is operated manually or automatic. Nine small mechanical clamps hold the cylinder in place on an indexing table.

Cylinder Walls Knurled—To increase service life of cylinders and to improve lubrication properties, a special machine to knurl cylinders was built by McCulloch. After being knurled to a depth of 0.007-inch the cylinder is honed, chrome-plated, and honed a second time to remove fuzzy excess that tends to build up around edges of knurl. The finished depth of the knurl after honing is approximately 0.003-inch.

The knurl is rounded in cross-section and at the ends to avoid short corners, which are difficult to plate. An air cylinder actuates the cam in the knurl holder to advance the knurl to the required depth. Three rollers bearing against the inside diameter of the cylinder take thrust and compensate for any variation in bore.

Cycle Automatic—The knurling head is connected to the lead screw and rotates during the boring operation. A lead screw through a fixed nut advances the knurl along the length of the cylinder. A limit switch in a fixed location at the rear of the machine is acted upon by a cam on a movable cylinder assembly to shut off air pressure and retract the knurl from those areas on which no knurl is required.

In one cycle, the knurling head moves into the cylinder approximately ½-inch, then a cam actuates the limit switch causing the knurl to feed into all of the cylinder. Knurling continues until the intake and exhaust ports of the cylinder are reached.

A cam actuated limit switch on the unit shuts off the air and retracts the knurl. Another cam feeds the knurl to the proper depth. The machine knurls on both forward and advance strokes, with only one pass being required per piece. Production is 70 pieces per hour.

Hardening Cutter Bars—Another special McCulloch-designed and built machine is one for flame hardening. This machine hardens the outer edge of the saw cutter-bar from 79 to 84 on the Rockwell hardness A scale at a load of 60 kilograms. Output of bars 18 to 35 inches in length is 300 per day on an 8-hour shift, and 150 to 200 per day for sizes 40 to 60 inches. The setup can be changed for any size blade in minutes. Acetylene and oxygen gas mixture is used with a regular torch head and specially adapted tip.

Warm water is sprayed along with the torch in hardening and both gas and water are automatically shut off when the end of the bar is reached. To start again, the torch is automatically set off by natural gas pilot. Correct amount of water and flame is timed for adequate hardening. A variable speed transmission is used to set speed for particular hardening of bar and torch is guided by rack chain.

Stress Relief—To relieve work hardening of machined parts the company designed a special thermal machine. The machine has banks of four rows of lamps, 35 lamps on each side. The part is carried through the machine between the lamps by a conveyor at the top of the machine.

Speed is controlled by a Micro flex automatic timer that can be set accurately according to thickness of the part. To provide a temperature gradient along the line of travel, the wattage of the lamps varies from 350 watts at the start of travel to 150 watts at the end.

MATCHING YOUR Needs WITH

Performance

TOBLOC®

MOTOBLOX®

Vaughn®

COLD DRAWING EQUIPMENT



RINGBLOX®



NTINUOUS MACHINES

DRAWBENCHES

You set up your production requirements, and we'll be happy to show you how completely and profitably they can be met by the right Vaughn Equipment. Just tell us when!

THE VAUGHN MACHINERY CO.

Cuyahoga Falls, Ohio, U.S.A.

COMPLETE COLD DRAWING EQUIPMENT . . . Continuous or Single Hole . . . for the Largest Bars and Tubes . . . for the Smallest Wire . . . Ferrous, Non-Ferrous Materials or their Alloys.

V®

"Quick on the Draw!"



Supreme in its field, this mobile monster moved from drawing board t proving ground in record breaking time. Once there, it proceeded to shatter performance records too . . . a real tribute to the superb engineering and production power of the Army Ordnance Corps an the Chrysler Corporation.

BAY STATE abrasive products, among others, were used to accomplish this feat. In particular, BAYFLEX reinforced disc-wheels were used by many Chrysler suppliers for grinding "miles" of tank-hull welds.

BAY STATE is proud to play its part in this modern miracle of stepped-u production. We salute the Patton 48 and the forward-moving program of Army Ordnance and Chrysler.

BAY STATE

BAY STATE ABRASIVE PRODUCTS CO., Westboro, Mas

Branch Offices and Warehouses — Chicago, Cleveland, Detroit, Pittsburgh
Distributors — All Principal Cities
In Canada: Bay State Abrasive Products Co. (Canada) Ltd., Brantford, Ontario

ALL TYPES OF QUALITY PRODUCTS FOR GRINDING



Control panel and cabinet for electronic equipment are mounted near the operator



Flat template on adjustable holder is shown in the foreground. Cast steel shape roll being turned is mounted in the machine's neck holders

Lathe *Contours* Mill Rolls Automatically

All-electronic duplicating equipment controls the 60-inch tool to generate complex body outlines. To assure solid mounting, rolls are suspended on neck holders

FULLY AUTOMATIC contour duplication becomes an accomplished fact on a 60-inch roll-turning lathe U. S. Steel Corp. installed recently in its Homestead, Pa., roll shop. The setup is said to be the first machine tool of this size to have all-electronic duplicating equipment for controlling cutting action.

Also for the first time, according to the builder, a lathe of this type is used to generate on steel mill rolls the complex body outlines that produce beams, channels, ship sections and other rolled steel products.

A major advantage is indicated by the extreme flexibility of the lathe's control system and ease of maintaining electronic duplicating equipment. Pushbutton manual control of all motor-driven tool-feeds permits fast roughing of individual passes and rapid automatic roll finishing. Another advantage is found in longer roll life and resulting reduction in mill downtime through maintenance of extremely close tolerances on roll passes.

Floating Tracer Stylus—The duplicating device guides cutting tool motion from a flat template whose contours are exactly those of the roll to be machined in the lathe. A minutely-varying degree of angular deflection in a floating tracer stylus moving along the edge of a template is signalled to a control panel.

These signals are electronically amplified, interpreted and fed to two electric motors. The motors' combined action in response to the signals keeps the stylus traveling and hugging the template. Since the cutting tool is mounted on the same movable part of the lathe carriage as the stylus, tool travel duplicates the path of the stylus. Tool deflection presents no problem when taking heavy rough cuts. Compensation can be made during lighter finishing cuts.

Performance Record — Mackintosh-Hemphill Co., Pittsburgh, designer and builder of the lathe, reports it cuts estimated finishing time from 156 to 49 hours on one type of roll used to produce structural shapes at the Homestead shop. On another, time is cut from 196 to 49 hours. Discounting setup time, the firm says rate of metal removal ranges from two to one through six to one in favor of the contour lathe as opposed to the standard setup.

Using tungsten carbide tools, the unit turns at headstock spindle speeds up to 32 revolutions per minute. Present roll shop practice on the Mackintosh lathe calls for surface speed of 60 sfm on iron and 200 sfm on steel. Additional time and labor are saved by a continuous chip disposal conveyor which discharges into removable buckets in pits at end of the bed.

Roll - Housing Mount — Some mounting problems presented in machining rolls that may weigh as much as 35 tons are solved by mounting the roll solidly in roll housings. The steel company's lathe is said to be the first of its size capable of contouring rolls while they are supported on their necks—as in the mill—in the special housings.

Mounted on the lathe bed, the completely adjustable housings duplicate actual rolling mill conditions, lending stability to the rolls being machined.

American Builds World

to produce its New WHEELA

A FULLY HE

***PLANT**
Now in Commercial Operation
ALL S.A.E. SHOT SIZES AVAILABLE

▲ New from the ground up, the building was designe for one purpose only — to produce the world's best abr ive

Electric arc furnaces and American's patented shotting process produce round, solid shot free from cracks and of uniform chemical analysis.

▼

▲ Automatically controlled heat-treating equipment assures a non-varying metallurgical structure of tempered martensite for long life and economical cleaning.

WORLD'S LARG

rgest Steel Shot Plant*

ATOR® STEEL SHOT

EATED ELECTRIC STEEL ABRASIVE

e metallurgically superior steel shot
uniform quality for maximum economy
in blast cleaning operations

Blast cleaning history was made when *American* pioneered the first airless blast unit—the "Wheelabrator"; the first blast mill with endless belt conveyor—the "Tumblast"; the first Continuous Blasting Mill; and numerous other "firsts" of equal importance to industry.

Again, after years of research, *American* invented a practical process (patented) for making a quality steel shot in the commercial range of sizes used in blast cleaning.

Years of field experience taught us that a cast steel shot, when properly made and heat treated, has no superior for blast cleaning economy and efficiency. Our studies also emphasized the importance of absolute control over every step in manufacturing in order to produce a uniform, high quality steel shot.

To provide this quality product for our customers, *American* has now become the first and only manufacturer of blast equipment to build and operate its own shot producing plant, employing the finest equipment, methods and controls.

The name "Wheelabrator", proudly applied to this new steel shot, is *American's* assurance that you can use this abrasive with confidence in achieving improved performance and economy. Try it soon.

Send for Bulletin No. 89

Bulletin 89 tells the complete story about "Wheelabrator" Steel Shot and what it means to the user in terms of performance and economy. Write for your copy today.

THE AMERICAN MOLDER

American

WHEELABRATOR & EQUIPMENT CORP.

509 S. Byrkit St., Mishawaka, Indiana

ILDERS OF AIRLESS BLAST EQUIPMENT

Troubles Down... Output Up with Welded Studs

High production units weld 10 studs to farm machinery rasp bars in 80 seconds. Assembly and dynamic balancing is easier, so is field replacement of worn rasps

WAR-BORN ART of stud welding, which saved the shipbuilding industry 100 million manhours in three years, increases production and eliminates troublesome assembly problems on harvester-threshers built in the E. Moline, Ill., plant of International Harvester Co.

Use of granular flux-filled studs in place of through bolts which formerly fastened rasp bars to the stripping cylinders of combines, corn-shelling and cotton-ginning equipment is helping farm operators, too. The job of replacing worn rasps is greatly simplified, since it was difficult to remove fastening nuts without turning the countersunk bolts.

Faster Output—A special five-gun stud welding production unit developed by Nelson Stud Welding, a division of Gregory Industries Inc., Lorain, O., is used to end-weld the ten threaded studs to the back of each McCormick rasp bar. Each stud is welded in a split-second. Complete cycle, which includes loading studs into the welding guns, positioning the work and welding takes less than 40 seconds.

The ten studs used to fasten each rasp bar to the reinforcing bars on a combined rasp bar cylinder assembly are welded on production units at a rate of approximately 50 bars per hour. Five studs are welded at a time, after which the 6-foot bar is shifted by a simple locating mechanism to bring the other five points under the gun mounts. Guns are set up with a timing control to operate in series from a power unit.

Eliminates Difficulties—The uniformity resulting from this controlled method of assembly has eliminated difficulties sometimes caused by variation in the teeth and the danger that bolts, which were made to conform with rasp bar contour face, would turn to positions that would interfere with smooth operation.

Dynamic balancing of rasp bar cylinder assemblies has been simplified. After quickly fastening bars to the cylinder, each is checked for straightness balance on a dynamic balancer at speeds up to 1050 rpm.

Cost Savings—Some implement manufacturers using both single gun and multiple gun Nelson production units on rasp bars credit stud welding with dollar savings ranging from 75 cents to $1.54 per combine cylinder assembly. They report that shop balancing and tooth pitch problems have been materially reduced or eliminated.

One manufacturer, who uses eight studs per bar, and a multiple gun unit, reports an average production of 400 rasp bars per man day, as compared with a former rate of 100 per man day when the rasps were hand-welded to the reinforcing bars.

Farm operators using stud welded models can replace rasps in the field and know that the assembly will be balanced properly. Difficulties in controlling the distribution of weight in hand-welded replacement bars and backup plates made this practice almost impossible in the past.



A typical 5-gun production unit for welding studs to rasp bars. Cycle including loading studs into guns, indexing and welding takes 40 seconds

Closeup of harvester-thresher with cover plate removed shows stud-welded rasp bars on a finished machine. The worn bars can be quickly replaced



these Pennsylvania Transformers are cooled with Ross Exchangers

This bank of three 29,000 Kva, 230,000-volt transformers is typical of many such high voltage power units which Pennsylvania Transformer Company, Canonsburg, Pa. furnishes to major industries and electric utilities.

To prevent transformer oil from reaching excessive temperatures, through heat generated in normal operation, each of these Pennsylvania units is equipped with two Ross Exchangers. Utilizing water as a coolant, their function is to receive the hot oil from the transformer, cool it as required, and return it for its job of maintaining the transformer temperature in accordance with NEMA guarantees.

Why have Pennsylvania's engineers selected Ross Exchangers for these applications? Among other things: "Ross equipment has many excellent features and the Ross organization has a fine background of manufacturing experience...has been very cooperative with us in connection with our heat exchanger problems".

The desire and competence of Ross engineers to consult in the solution of any heat exchange problem ...plus the wide adaptability of Ross fully standardized, pre-engineered designs and sizes, have earned a preference for Ross Exchangers in practically every field of application: engines, compressors, turbines, speed changers, hydraulic machinery and numerous others.

To be familiar with the principal Ross benefits, make sure you have the latest Ross literature. Request Bulletin 2.1K1 for information on the removable tube bundle Type CP Exchangers used on Pennsylvania Transformers, or Bulletin 1.1K5 on all-copper and copper alloy Type BCF units. Write.

KEWANEE-ROSS CORPORATION
DIVISION OF AMERICAN RADIATOR & STANDARD SANITARY CORPORATION
1431 WEST AVENUE • BUFFALO 13, N. Y.

*National Electrical Manufacturers Association

KEWANEE-ROSS PRODUCTS

Serving home and industry: AMERICAN-STANDARD • AMERICAN BLOWER • CHURCH SEATS & WALL TILE • DETROIT CONTROLS • KEWANEE BOILERS • ROSS EXCHANGERS

FACING AT 1000 SFM WITH TRIANGULAR INSERTS
. . . drive varies from 100 rpm at 4 inches to 4000 at 1 inch

Expendable Tungsten Carbide Triples Insert Life

EXTENDED tool life, with good surface finish, is reported by a communications and recording equipment manufacturer in machining SAE C-1118 steel at 1000 sfm using Kendex expendable tungsten carbide triangular inserts. The operation performed by McElroy Mfg. Corp., Littleton, Mass., consists of facing two surfaces of a high-frequency transmitter component from a maximum 4 inches diameter down to 1-inch diameter center shaft.

Work is done on a ¾-hp Logan lathe having variable drive attachment. Machine surface must have a mirror-like finish because it is later plated with an 0.0002-inch thickness of copper followed by an 0.0012-inch silver application. The surface is then buffed down and rhodium flashed to prevent tarnish.

Variable Drive—To get the necessary machine finish, a surface-foot rate of 1000 is maintained throughout the cut. This is accomplished by varying the revolutions per minute from 1000 at the start to about 4000 at the finish of the cut with the lathe's variable drive unit. This drive is actuated by the tool slide, which is fed in at 0.0045-inch per revolution. Chip guard assures that finish machined surface will not be scratched.

At a lower foot rate, a satisfactory finish could not be obtained; at higher speed, tool life became a problem. The company reports the best tool life it received with several previous triangular insert grades was 20 pieces per cutting edge, or 60 pieces per insert.

Interchangeable Inserts — With K8 inserts — Kennametal's most abrasive grade — 180 pieces are faced, 60 with each of the three available cutting edges. Since depth of cut is only 0.007-inch, the left and right-hand tool inserts are interchanged to machine an additional 180 pieces to build the total faced to 360.

Talks Treat Foundry Safety

A two-day institute on foundry safety and health protection will be held at University of Wisconsion Mar. 24-25. The institute is sponsored jointly by the university's department of mining and metallurgy, the university extension division's engineering section, state board of health, industrial commission and American Foundrymen's Society.

Furnace Softens Scale

Lithium atmosphere annealin eases cleaning problems o the cast crankshafts at Ford

REMOVING foundry scale fro castings at Ford Motor Co. of Car ada Ltd. was resolved into a que tion of whether to clean crank shafts before annealing or after– and both procedures were regarde too costly with existing facilitie In the former case, normalizin scale had to be cleaned after an nealing, in the latter, the doubl scale required extra long cleanin

To overcome these condition Ford decided to adopt a heatin method that would reduce thick ness and toughness of the scale o the casting surface. This wa achieved by introducing a lithiu atmosphere into the furnace.

Required No Changes—Witho changing existing furnace desig or construction, two standar Lithium Co. vaporizers were a tached to each side of the dire fired furnace. Vaporizers are sma refractory lined chambers that a gas-fired and can be fitted to an furnace. Running through the mi dle of the chamber is a rectangul refractory tube in which rests boat of Lithium compound.

When the chamber is heated, t compound is vaporized and vap picked up by the products of co bustion which enter the tube a are carried into the furnace. T vapor is said not only to inhib additional oxide formation on t castings but also tends to chan the character of scale that was the metal when it was put into t furnace. It becomes relatively so thin and flaky.

Added Advantage—It was al discovered that the atmosphe permeating the furnace chamber form a coating on the crankshaf covers alloy parts such as furna rails, trays and other fixtures the furnace or which pass repe edly through it. This coating i hibits normal oxide attack, and i creases furnace life a reported per cent.

The company reports that t castings themselves are in mu better condition for cleaning. T operation now requires only five eight passes on the blast table stead of 12 to 15 needed befo

Pouring the Roll

WHERE EXPERIENCE COUNTS . . . for you

The critical step in roll making occurs in the pouring. Here, the experience and metallurgical knowledge of the roll maker determines the quality of the roll and its performance on your stands.

For more than forty years, National has been pouring rolls that are sound, long-wearing . . . rolls cast to the right hardness, chill depth and heat resistance, iron and alloy iron rolls that you can depend upon to give long tonnage life.

NATIONAL ROLLS

National Rolls

THE NATIONAL ROLL & FOUNDRY CO.

AVONMORE, PENNSYLVANIA

SPECIALISTS IN IRON AND ALLOY IRON ROLLS AND CASTINGS



200-ton 6-motor 98'-3" Span Crane w
two 100-ton Hoists and one auxiliary
ton Hoist. In Concentrator Grinding Be

DESIGNERS • MANUFACTURERS • CONTRACTORS
BLOOMING MILLS • PLATE MILLS • STRUCTURAL MILLS • ELECTRIC TRAVELING CRANES • CHARGING MACHINES • INGOT STRIPPING MACHINES • SOAKING PIT CRANES • ELECTRIC WELDED FABRICATION • LADLE CRANES • STEAM HAMMERS STEAM HYDRAULIC FORGING PRESSES • SPECIAL MACHINERY FOR STEEL MILLS

BUILT BY MORGAN Engineering

MORGAN CRANES AT "CHUQUI

Illustrated are three Morgan Hea
Duty Mill Type Cranes at Chi
Exploration Company's new pla
at Chuquicamata. These cranes are
very rugged construction, especial
designed for copper smelter servic
Your inquiries will be appreciate

THE MORGAN ENGINEERING CO.

ALLIANCE, OHIO PITTSBURGH—1420 OLIVER BUILDING



100-ton 6-motor 70'-0" Span Crane with two 25-ton Auxiliary Hoists. In West Converter Aisle.

100-ton 6-motor 70'-0" Span Crane with two 25-ton Auxiliary Hoists. In East Converter Aisle.



pical of small 2-high reversing ills installed in recent years by ecialty steelmakers is this 22-inch it installed at Watervliet, N. Y.



Pass schedule for 28-inch mill used to handle 16-inch ingots. After the even numbered passes, except 6 and 18, the ingot is turned 90 degrees

Small 2-High Reversing Mills Gain Favor

Lower production costs and greater operating flexibility are principal reasons why specialty steelmakers are shifting from former methods employed

By E. C. PETERSON
Birdsboro Steel Foundry & Machine Co.
Birdsboro, Pa.

ODERN small 2-high reversing ills for the rolling of semifinished ecialty steel products are becom- g increasingly popular. These nall mills are usually in the 18 to 3-inch size range and their in- easing use may be explained by vo factors: A tendency to adopt rger ingots of high alloy, stain- ss and tool steels to the point here conventionally used 3-high ill and forging hammer or press uneconomical to operate; increas- g versatility and flexibility of anipulation and reduction of man- ual labor are features built into the modern small 2-high reversing mills.

Most of these mills have water lubricated neck bearings of segmental block design. One recent mill has roller neck bearings to provide ease and accuracy of alignment of roll grooves plus freedom from eventual misalignment due to thermal expansion and wearing of the end thrust collars, as experienced with water lubricated bearings.

Close Settings—Screwdown motors are arranged for series or parallel magnetic control to obtain two speeds, or with variable voltage control. On these small mills it is practical for the operator to set the roll parting to one-half of 1/64-inch increments. Mechanical top roll counter-balance is preferred because of the simplicity of its operation and ease of maintenance.

A recent improvement in the lubrication of the universal spindles consists of an oil reservoir with appropriate feed line and metering

IN almost every country in the world and every state in the union where steel is produced or petroleum is refined you'll find McKee engineering. Every year sees an increase in the number and size of projects designed and constructed by McKee . . . new names added to the list of countries in which McKee has executed contracts.

The reason for this steady growth lies in the excellence of McKee engineering, the soundness of McKee construction and the close coordination of these functions with expeditious purchasing services. That's why steel men and oil men from all over the world come to McKee again and again for *engineering that means assured results.*



ENGINEERING, PURCHASING AND CONSTRUCTION FOR THE IRON AND STEEL AND PETROLEUM REFINING INDUSTRIES

Arthur G. McKee & Company • Established 1905

Headquarters: McKee Building, 2300 Chester Avenue, Cleveland 1, Ohio.
Offices: New York • Tulsa, Oklahoma • Union, New Jersey • Washington, D. C.
British representatives of Metals Division: Head, Wrightson & Company, Ltd.
Canada: **Arthur G. McKee & Company of Canada, Ltd., 350 Bay St., Toronto 1, Ont.**

New Calcinator Ups Coke Supply for Electrodes

Rotary calcinator installed at its Niagara Falls, N. Y., plant means an increased supply of calcined coke for production of graphitized carbon electrodes at International Graphite & Electrode Division, Speer Carbon Co. The coke will be used in manufacture of electrodes and anodes, and to supplement the raw material supply the firm uses for motor brushes and other specialties

valve to provide a steady supply of oil to the slippers.

Alloy steel is the usual material used in the rolls but iron is required occasionally for better surface conditions. In this case a removable steel spade is keyed to the end of the roll to provide sufficient strength in this highly loaded section. With a duplex changing rig, roll can be changed in 30 minutes.

Planned for Production — Front and back mill tables have close roll spacing to accommodate the relatively short ingots handled. Self-aligning bearings are used on roller journals to provide relief from the effect of roll warpage when the ingot heats a roll unevenly, as during a mill delay. Individual feed roll drive is used and two recent installations incorporated slip clutches in the floating shaft spindle which drives the feed roll, in order to minimize the shock which occurs when a piece leaving the rolls is driven against this roller.

A nest of rollers underneath the mill table carries the manipulator rams, and these rollers are journaled on antifriction bearings to minimize friction and permit rapid acceleration of the side guards. Finger lift motor and reduction unit can be mounted directly on the side guard. This makes a simple mechanical arrangement and does not slow down the side guard appreciably. The finger lift has a mechanical adjustment so that different lengths of stroke can be obtained. A recent installation accomplishes this end electrically, so that the stroke can be varied to suit the size of product being handled by turning a selector switch in the operator's pulpit. This is a helpful feature when a wide range of sizes is to be handled, since no single stroke will function properly for all of these sizes.

Since the conventional unit for producing semifinished products in the specialty steel industry has been the 3-high mill, the following are some of the advantages of the 2-high reversing mill as compared with the 3-high mill.

Bigger Ingots—First, relatively little work can be done in one fixed pass stand. The rolls are cut so deep that very little life is obtained, and breakage is always a problem. A 14-inch square ingot is reduced to a 6¾-inch square in a typical 28-inch 3-high mill. By contrast, an 18-inch square ingot is reduced to a 4-inch square in the rolls of a typical 26-inch 2-high mill.

Second, variable speed is an inherent characteristic of the 2-high mill and this factor is extremely important in handling specialty steels for the following reasons:

1. Spread may be controlled by varying the rolling speed. Since the spreading characteristics vary considerably from one grade of steel to another, a given series of reductions can be used successfully with different grades and different speeds. With a constant speed drive, such as is usually found on a 3-high mill, difficulty is encountered with underfilling and overfilling as grade and temperature are changed.

2. Difficulty in entering hard or slippery grades can be overcome by entering at low speed.

3. Production can be maximized by taking initial passes at low speed, where entry is difficult, and speeding up on the final low passes.

4. Slow speeds can be used to avoid rupturing the surface of tender grade ingots, until sufficient work has been done to permit faster rolling.

Makes Big Difference—Third, the mechanical screwdown of the 2-high mill gives the following advantages:

1. Only with the screwdown can the variations in reduction schedules required by different grades of steel be made without delay.

2. Different size ingots must be rolled and numerous different sizes of semifinished products produced, usually in small orders. The screwdown again provides the only practical method to make these size changes without delay.

3. The screwdown helps to make roll changing less complicated and less time-consuming on the 2-high mill, and permits the use of rigid, closed housings.

4. Specialty grades of steel are apt to develop split ends during rolling. By the skillful use of the screwdown, manipulator and reversing motor, the operator can save pieces that could not be entered into a fixed pass mill. Other accidents in rolling, such as partial turn-downs, can often be corrected by stopping the mill quickly and working the bar into rolling con-

U. S. DRILL HEAD COMPANY SAYS . . .

HEAT TREATING ELIMINATED

• REJECTIONS REDUCED

• WEARABILITY INCREASED AND

COSTS CUT 50%

WITH

STRESSPROOF®

SEVERELY COLD-WORKED, FURNACE-TREATED STEEL BARS

Multiple spindle, made by U.S. Drill Head Company, Cincinnati, Ohio, uses spindles made from STRESSPROOF.

Spindles for these multiple drill-heads must be straight. Formerly heat-treated, straightening was a difficult, costly job, and rejections were high.

Now produced from STRESSPROOF, heat-treating, with its attendant straightening problem, is eliminated; machinability is increased 25%; wearing properties have been improved; and costs reduced 50%.

STRESSPROOF makes a better part at a lower cost.

STRESSPROOF's value to manufacturers like U.S. Drill Head stems from its unique combination of four qualities in the bar: (1) Strength, (2) Wearability, (3) Machinability, and (4) Minimum Warpage. Yet STRESSPROOF costs less than other quality cold-finished steel bars. It comes in cold-drawn or ground and polished finish.

SEND FOR . . .
Free Engineering Bulletin
"New Economies in the Use of Steel Bars"



La Salle STEEL CO.

Manufacturers of the Most Complete Line of Carbon and Alloy Cold-Finished and Ground and Polished Steel Bars in America.

La Salle Steel Co.
1414 150th Street
Hammond, Indiana

Please send me your STRESSPROOF Bulletin.

Name_____

Title_____

Company_____

Address_____

City_____ Zone____ State_____



whatever your broaching problem may be count on American.... we make all three

You avoid "piece-meal" engineering when you solve your broaching problems the American-way . . . because American engineers are trained to design all three . . . broaches, machines and fixtures. Start American engineering your answer . . . just send a part-print and sample, if possible, with hourly requirements. You'll receive our recommendations without obligation. Address Dept. S.

American BROACH & MACHINE CO.
A DIVISION OF SUNDSTRAND MACHINE TOOL CO.
American Building - Ann Arbor, Michigan

SUNDSTRAND

Maximum Ingot Size Capacity of Small Mi With Mechanical Screwdown and Fixed Pass Maximum square ingot handled, in.		
Mill size, in.	Mills with mechanical screwdown	Mills wi fixed pass
32	..	16
30	..	15
28	22	14
26	20	13
24	18	12
22	16	11
20	14	10
18	12	9

tion again, an impossibility on a -high mill.

5. A mill without a screwdown s virtually useless for the productio of slabs, since the edging groove weaken the rolls excessively. Wi a screwdown relatively shallow ed ing grooves can be used and wi slabs produced.

Deformation Disappears — Fourth, the straight entry into t passes of a 2-high reversing mi eliminates improper deformation the steel and punishment of th table rollers, as occurs on the 3-high mill with tilting tables, whe both entry and delivery are at a angle.

Further, stroke of the tiltin table is constant, and it can nev be adjusted properly to the r passes, but must be a compromi with the varying diameters of th middle roll, and the differe groove depths.

Fifth, the side guard manipulato with finger lift, as used on the -high mill, is the most flexible ma ipulating arrangement yet devis Three-high mills with tilting tabl often use fingers located betwe the tilting table rolls to turn ov and manipulate. These arrang ments are inflexible, however, a limit the roll designer and operat in their choice of rolling schedu a very serious drawback in ha dling specialty steels.

A sixth advantage of the 2-hig mill for rolling specialty steels s the relatively small roll required handle a given ingot size. Th condition permits it to finish a much smaller billet satisfactor by reducing speed.

Seventh, the construction of e 3-high mill causes the passes t spring more under load, which is a disadvantage if a close tolerance is required on the billet.

Savings Significant — It is n economically practical to use a plain 3-high stand for cogging

Look around the coffee shop

for Metalworking products . . .

. . . made in the plants reached by STEEL

And don't stop in the coffee shop. *Wherever* you look you see the products of Metalworking . . . the biggest of all industrial markets . . . a fast-growing market that has doubled in size since 1940. If you agree this is a sales prize worth reaching for, put your advertising in STEEL. For STEEL reaches more of the men who influence orders in this market, than *any* metalworking publication. Decide now to use STEEL to stake out *your* claim in Metalworking.

STEEL • Penton Building • Cleveland 13, Ohio

The Key to your sales opportunity in Metalworking is in the operations involved in producing the multitude of metalworking products. Why? Because the men responsible for managing these operations buy *more* goods and services than any other group. And your advertising in STEEL reaches more of these men than in any other metalworking magazine.

The magazine of the men who manage, operate, and buy for the metalworking industry



ALAN WOOD'S 30″ STRIP MILL
SERVING YOU SINCE JANUARY 2, 1950

• The Alan Wood 30″ continuous mill continues to produce at top speed plates, sheets and strip.

Everything possible is being done to improve our facilities and to expedite production to give you the best possible service.

Remember, too, that Alan Wood's mine-to-mill integrated production line assures you of high grade steel.

Over A Century and a Quarter of Iron and Steel Making Experience

ALAN WOOD STEEL COMPANY

Conshohocken, Pennsylvania

IVY ROCK, PA. • SWEDELAND, PA. • DOVER, N. J. • OXFORD, N. J.

ept in those cases where very mall tonnages of high cost alloys re being produced.

Experience shows that with high lloy steels, a conversion cost from ngot to semifinished products of cents a pound can be reduced o 1 cent by changing from a sim-le 3-high mill with mechanical quipment to a modern 2-high re-ersing mill, and this does not nake any allowance for the addi-ional savings in the steel plant nd in yield due to the possible use f larger ingots.

Various features can be added o the 3-high mill. These include: direct current variable speed drive, ilting tables, side guard manipu-ator with finger lift, and top and ottom motor driven screwdown or op motor driven screwdown and oating middle roll.

Other Factors—While the revers-ng mill will do everything that the -high mill will do in reducing spe-ialty steel ingots, and will do nuch of it better than the 3-high nill from a quality standpoint, the ame cannot be said with regard o the forging process.

Two steel-producing plants hat recently installed reversing nills have found that about 95 per ent of their specialty grades can e roll cogged, and at a lower cost han by forging. Nevertheless, orging will always have a place in he cogging operation because of he peculiar properties of some of he special alloys.

The 3-high mill of simple design nas such serious drawbacks for uality and flexibility of production nd cost of operation as to make it mpractical for a modern installa-ion.

When it is doctored up with nechanical devices to eliminate la-or and add flexibility, it is worthy f consideration only when driven y alternating current constant peed equipment. Progressive mill perators in the specialty steel bus-ness are fast coming to realize that ariable speed drive on their mills s a necessity for quality and im-proved production. When direct urrent drive is added to the me-hanical cost of the complicated modern 3-high installation, with screwdowns, tilting tables and side guard manipulators, its cost equals that of the simpler and more effec-tive 2-high reversing mill.



Six magnetic impulse rappers are shown in this installation. Up to 24 of these units can be energized in a 60-second cycle from one power source

Continuous Rapping Bars Dust Buildup

Remote-controlled solenoid-actuated magnetic impulse system cleans precipitators in 60-second cycle. Dust clouds disappear as batch cleaning is eliminated

DEVELOPMENT by Research Corp., Bound Brook, N. J., offers electronic precipitator users a rapping system for continuous electrode cleaning. The company's magnetic-impulse (MI) method delivers continuous impacts of light and easily controlled intensities.

The system employs a solenoid-actuated rapper energized by a pulse generator. According to Research Corp., it can be installed easily on any standard precipitator used in electric, blast, open hearth and iron ore sintering furnace installations. Applications extend to fly ash and gypsum.

Dust Buildup—Of the two banks of electrodes that accomplish material recovery in precipitator operation, one discharges an electrical field that ionizes dust suspended in the gas; the other collects dust for disposal. However, all collected dust does not fall by gravity into disposal hoppers. Instead, a certain portion builds up into appreciable layers, particularly on the electrodes, affecting efficiency of equipment.

Unloading these accumulations with standard pneumatic or mechanical rapping devices previously was limited to an intermittent operation. Result, says the company, is batch removal rather than continuous cleaning that keeps efficiency at high level. In addition, continuous rapping means size of unloaded dust aggregates is kept small enough at all times to prevent clouding dust disturbances in the equipment.

Remote Control—A central remote control generator can deliver tripping impulses to each rapping unit—up to 24 per precipitator—at 2½-second intervals. The entire precipitator is rapped in 60 seconds or less. Power consumption rates about 300 w per precipitator. A separate remote control permits rapper monitoring from any convenient plant location to eliminate need for regular operating personnel.

To hold down maintenance, the only major moving part is hermetically sealed and permanently lubricated at time of manufacture.

A name to Remember



The next time you're taking estimates on new presses let the Warco representative in your area give you the facts that have caused more people to buy Warco Presses the past year than ever before.

A few minutes with a Warco representative is all you'll need to see why the added quality designed and built into Warco Presses guarantee extra life at lower maintenance costs. You'll be introduced to many features, exclusive with Warco, that spell added safety, less operator fatigue and greater press speeds.

Too, your Warco representative is a specialist who'll work with you in getting a press that will do the most efficient job per dollar invested. And, you'll appreciate, like hundreds of others, the johnny-on-the-spot after sale service for which Warco representatives are noted.

So, next time you think of presses be sure you have the Warco story — it will pay you in the long run. Warco representatives located in all principal cities.

Federal® WELDERS

Warco PRESSES®

THE FEDERAL MACHINE & WELDER COMPANY

WARREN, OHIO

Rappers for both discharge and collecting electrodes can be energized by a simple arrangement from one common supply source.

How It Works—The MI rapping case, containing its solenoid-actuated plunger and elements, is welded to the end of a horizontal rapper bar protruding through the precipitator wall and stuffing box. Horizontal rapper is welded along the edges of collecting plate electrode banks. Each bank is rapped in sequence.

Power supply for the MI units takes 115 v, single-phase 60-cycle current to the pulse generator. The latter includes a transformer for stepping up alternating current and a full wave rectifier for converting alternating current to direct current.

Current then flows through charging resistor and condensor where energy is stored. Pulse energy to individual solenoid rapper coils flows through the motor-driven distributor switch, which puts each unit consecutively in line to receive pulse energy released by the storage condensor.

Watts Keep Diesels Warm

Diesel engines used in cranes, switch engines, trucks and other outdoor equipment can be kept ready to operate in the coldest weather safely and automatically with electric heat. A few kilowatt-hours of electricity can save many man and equipment hours ordinarily lost waiting for engines to warm up.

To illustrate, Edwin L. Wiegand Co. cites an installation where three cranes and a switching engine at Buffalo Slag Co., Lackawanna, N. Y., are heated economically and efficiently with Chromalox electric circulation heaters attached to the engine block with angle iron. With flexible connections to the cooling system, regular types of antifreeze are circulated by natural convection through the heater and engine block, warming the engine in a short time. Special pumps are not required.

The electric circulation heater is a completely packaged unit with built-in elements, heating chamber, thermostat, and threaded inlet and outlet. On average winter morn-

Delpark

Self-Cleaning INDUSTRIAL FILTERS...

First Choice

OF OUTSTANDING

PATENTS PENDING



Compact DELPARK Filter installation in the Gallmeyer & Livingston Plant, Grand Rapids, Michigan. This DELPARK Filter supplies clean coolant to a Grand Rapids Model F 24 inch x 25 inch x 96 inch High Speed Production Type Hydraulic Feed Horizontal Spindle Surface Grinder.

Machine Tool Manufacturers!

In their shops as well as on the equipment they sell, DELPARK Filters are the major choice by outstanding manufacturers of machine tools for the filtration of coolants. The reasons are obvious when you know the finer points of DELPARK Filtration.

The DELPARK Filter is a gravity filter, it does not filter by *expensive forced methods.* DELPARK filtration is natural filtration, making use not only of the filter media but employing the swarf deposited on the belt as additional filter material.

The DELPARK Filter is full flow, continuous, self-cleaning and fully automatic. It supplies clean coolant to the grinding wheel at much lower and more uniform temperature due to removal of the heat bearing solids. Clean coolant also eliminates dermatitis and reduces loss of man hours.

Greater savings are achieved through longer wheel life, less wheel dressing, the elimination of down-time for desludging the reservoir, reduced pump wear and system maintenance, and fewer rejections on the production line.

For the finest in Filtration . . . See DELPARK, the *Original* Automatically Self-Cleaning Industrial Filter.

Delpark

INDUSTRIAL FILTRATION

Filters That Amortize Themselves Within a Year

BY MORE THAN 30 YEARS EXPERIENCE IN INDUSTRIAL FILTRATION

INDUSTRIAL FILTRATION COMPANY
99 Industrial Avenue, Lebanon, Indiana

Gentlemen: We would appreciate having more information on the Famous DELPARK Industrial Filters applied to coolants.

Name.....*Title*.....

Company.....

Address.....

City.....*State*.....

A man with a hate

● There's no halfway feeling about fire and its resulting destruction with an expert fire protection engineer... he actually hates to see a little fire roar into a raging inferno and create a sizeable loss.

This personal sense of responsibility is inherent with C-O-TWO Fire Protection Engineers... a definite plus in your behalf. Whether its fire detecting or fire extinguishing ... portables or built-in systems... C-O-TWO means top quality backed by experienced engineering that results in operating superiority for you at all times.

With C-O-TWO Fire Protection Equipment, simplicity, practicability, longevity and minimum maintenance are built-in features that guarantee fast, positive action the instant fire strikes. Furthermore, extensive manufacturing and field installation skills, together with approvals such as the Underwriters' Laboratories, Inc., Factory Mutual Laboratories, Armed Forces and Government Bureaus assure you of the finest in modern fire protection equipment.

Rushed production periods and future expansions are some of the many problems carefully considered in a plant-wide firesafety recommendation by C-O-TWO Fire Protection Engineers... the prime objective always being the best type fire protection equipment for the particular fire hazard concerned.

WHEN BUSINESS STOPS . . . INCOME STOPS!

Don't take chances with your investment. Secure the benefits of highly efficient fire protection engineering today... our extensive experience over the years is at your disposal without obligation. Get the facts now!

C-O-TWO

MANUFACTURERS OF APPROVED FIRE PROTECTION EQUIPMENT

Squeez-Grip Carbon Dioxide Type Fire Extinguishers
Dry Chemical Type Fire Extinguishers
Built-In High Pressure and Low Pressure Carbon Dioxide Type Fire Extinguishing Systems
Built-In Smoke and Heat Fire Detecting Systems

C-O-TWO FIRE EQUIPMENT COMPANY
NEWARK 1 • NEW JERSEY

C-O-TWO FIRE EQUIPMENT OF CANADA, LTD. • TORONTO 8 • ONTARIO

Sales and Service in the Principal Cities of United States and Canada

AFFILIATED WITH PYRENE MANUFACTURING COMPANY

ngs, a 150°F setting is sufficient to heat most engines in 30 minutes. In colder weather, the heaters may be operated all night at 90°F.

Computing Air Gage

Where more than one variable has an effect on the reading, this gage reduces your figuring

ORIGINAL application of air gaging was made for checking internal and external diameters. As its advantages became more apparent, it was applied to multiple and complex measuring problems such as checking tapered cylindrical parts, center distances, squareness between face and bore and concentricity.

When the air gage is used for one of these measuring problems,



HUMAN ELEMENT
. . . the gage cuts it down

the setup is complicated by the fact that there is always more than one variable involved, since readings are not only affected by variation of the above factors, but also by variations in diameter. The total effect of both variables must be considered in arriving at the final result. It is necessary therefore to use at least two air circuits and a like number of indicators to arrive at the desired result.

Paper Work—Operator frequently has to take readings from two air indicators, then add or subtract the respective readings before the final answer can be obtained. This computation is required when checking tapered parts, center distances between holes and clearances between mating parts.

When checking concentricity between diameters or squareness of bore to face, it is usually not necessary to obtain results from sepa-

LOW COST
IRIDITE®
FINISHES

for zinc, cadmium, aluminum and cuprous metals

provide
corrosion resistance
paint base
choice of appearance

And they are easy to apply! Just a simple chemical dip for only a few seconds produces the coating.

LOW MATERIAL AND SHIPPING COSTS

combine to make Iridite the most economical chromate finish you can buy. Many Iridite chemicals are packed in powder form, thus can be shipped to you in steel pails at freight savings of up to 75%! Pails take less storage space, are easier to handle, eliminate carboys, need not be returned.

WHY NOT TEST IRIDITE ON YOUR PRODUCTS? Write for literature and send samples for free test processing. See "Plating Supplies" in your classified telephone directory or write direct.

Iridite is approved under government specifications.

ALLIED RESEARCH PRODUCTS
INCORPORATED
4004-06 E. MONUMENT STREET • BALTIMORE 5, MD.

Manufacturers of Iridite Finishes
for Corrosion Protection and Paint Systems on Non-Ferrous Metals; ARP Plating Brighteners.
West Coast Licensee: L. H. BUTCHER COMPANY

fall in with the

T-COMPOUND
Rare-Earth Procession

Castings for today and tomorrow need constant improvement. A new help is now offered. Use of Rare Earth materials yields better, definitely uniform physical properties, and gives added assurance of meeting specifications.

A special product, "Rare-Met" T-Compound, developed by the Molybdenum Corporation, is most convenient and most thoroughly approved for use in both steel and nodular iron.

Having its own huge rare-earth deposits, the Molybdenum Corporation has devoted special research to these materials and can give advice on a wide variety of applications. You may wish to investigate.

As a supplier of Molybdenum, Tungsten, Boron, and other alloying materials, the Molybdenum Corporation welcomes correspondence on any requirement.

AMERICAN Production, American Distribution, American Control, Completely Integrated

Offices: Pittsburgh, New York, Chicago, Cleveland, Detroit, Los Angeles, San Francisco

Sales Representatives: American Steel and Supply Co., Chicago; Edgar L. Fink, Detroit; Brumley-Donaldson Co., Los Angeles, San Francisco

Subsidiaries: Cleveland-Tungsten, Inc., Cleveland, O.

Works: Washington, Pa.; York, Pa.

MOLYBDENUM CORPORATION OF AMERICA
Grant Building Pittsburgh, Pa.

MCA

Controls at Sandvik

U.S. research equipment finds service around the world. Here, a technician at Sandvik Steel Works, Sandviken, Sweden, makes analyses with an x-ray diffraction and Geiger counter x-ray spectrometer installation supplied by North American Philips Co. Inc., Mt. Vernon, N. Y. The Swedish firm uses the equipment for both production control and development operations

---

gate indicators and then compute an answer. However, due to the usual permissible variation in diameter involved, position of the tolerance range on the scale will change if diameter varies from its mean value.

Margin of Error—According to the maker of the new gage, Taft-Peirce Mfg. Co., Woonsocket, R. I., when applying the standard type air gage circuit and indicator to these measuring problems, more responsibility is placed on the operator and the human element has not been entirely eliminated.

With the Taft-Peirce computing indicator, it is possible to remove the effect of one of the variables (diameter) on the results shown for value of taper, concentricity and clearance.

This is done by applying the diameter variation to both sides of the differential measuring device, thereby nullifying its effect on the reading obtained on the dial.

Thus it is possible to obtain readings for these dimensional characteristics on a single dial with a single pointer. This means greater speed, accuracy, convenience and economy.

the *tougher* the cutting job . . .
the *better* the opportunity for . . .

Abrasive Cutting



"FOR HEAVEN'S SAKE, SAWYER . . . HOW DID YOU GET INTO THIS FIX?"

Unusual cutting conditions like this are the exception . . . but whether you have a specialized application or a mass production job, you can depend on Allison Wheels. Whatever the material to be cut, there is an Allison Abrasive Cutting Wheel processed and formulated to fit the job. This means faster cutting with fewer rejects and reduced operating costs.

If you have a cutting problem, go to Allison — the specialist in abrasive cutting.

Allison ABRASIVE CUTTING WHEELS

THE *best* WAY TO CUT MANY MATERIALS
THE *only* WAY TO CUT SOME



SEND FOR THIS HELPFUL BOOK ON ABRASIVE CUTTING

THE ALLISON COMPANY
255 Island Brook Ave., Bridgeport 8, Conn.

Please send me your free booklet on Abrasive Cutting:

NAME:.....

ADDRESS:.....

GALB2

INSIDE AN EXIDE-IRONCLAD

Inside . . . where it counts most . . . EXIDE-IRONCLAD is entirely different than any other battery. It's made that way by EXIDE'S exclusive IRONCLAD slotted-tube construction . . . a principle that provides direct operating-hour savings for you.

OF *ALL* BATTERIES, ONLY EXIDE-IRONCLADS HAVE POWER TUBE POSITIVES

The positive plate is different . . . unique . . . exclusive. It is the most effective retainer of active material yet demonstrated in heavy duty service. Slotted tubes contain the active material. So fine are the slots that, while permitting easy access of electrolyte, they retard the active material from washing out, hold it during repeated cycles of charge-discharge, and the vibration of rough use.

Today's battery-powered equipment is being used harder than ever before. Unless the batteries have internal shock protection they tend to deteriorate under hard usage—both electrical and mechanical. Only Exide-Ironclad has the plus-protection of the tubular positive that can withstand today's more exacting and rigorous heavy-duty battery services.

Your EXIDE sales engineer will give you the factual inside story. See for yourself why *only* an EXIDE-IRONCLAD gives maximum day-after-day service under the most difficult operating conditions . . . *with a minimum of maintenance expense.*

THE ELECTRIC STORAGE BATTERY CO.
Philadelphia 2
Exide Batteries of Canada, Limited, Toronto

1888 . . . DEPENDABLE BATTERIES FOR 65 YEARS . . . 1953

Cross section shows relation of positive plate to separators and negative plate. Note the much greater exposure of active material to electrolyte as compared with that of the usual flat positive plate. This greater exposure makes possible the high power ability and uniform-voltage characteristics of the Exide-Ironclad. The negative plates have been made extra heavy to balance the increased capacity of the power tube positives.

Running through center of each tube is an alloy core which is cast with the heavy top cross bar. These form the sturdy, non-buckling grid. Both core and top bar are made of Exide's new corrosion-resistant Silvium, an alloy of silver, lead and other components, which adds greatly to plate's long life.

New polyethylene insulating tube sealer of acid-proof, non-corroding plastic fits snugly into bottom of slotted tubes and further reduces loss of active material. Thus more active material remains available, and the high battery capacity is maintained for a longer working life.





Exide-Ironclad

YOUR BEST POWER BUY . . . AT ANY PRICE

"Exide-Ironclad" and "Silvium" *Reg. T.M. U.S. Pat. Off.*


ou'll Find The Difference

Build "Sales Features" into your Products with SPECIAL BOLTS

Why limit the design of your products to ordinary fasteners? Special Circle Ⓑ bolts can often add sales appeal in improved design with greater strength. Equally important, you can figure on faster, easier assembly at lower unit cost. Call on our experience to gain plenty of practical advantages.

In specifying and ordering standard fasteners, you will find our Catalog No. 51 very helpful. Write for your copy.

BUFFALO
BOLT COMPANY
Division of Buffalo-Eclipse Corporation
North Tonawanda, N. Y.
Sales Offices in Principal Cities
PRODUCERS OF CIRCLE Ⓑ PRODUCTS — BOLTS • NUTS • RIVETS AND SPECIAL FASTENERS



Heart of the Reheater

This low-pressure spindle for one of two 120,000-kw cross-compound reheat steam turbines will be installed in Wisconsin Electric Power Co.'s Oak Creek, Wis., station. Allis Chalmers Mfg. Co. reports the longest blade of the 178,000-pound spindle is 40 inches; maximum tip diameter, 13 feet 4 inches. Top speed of the longest blade will be 1260 feet per second.

Foundry Package Available

Four-in-one foundry package of synthetic materials required for the shell molding process and for traditional sand casting is available from General Electric Co.'s Chemical Division.

Included are two materials essential to shell molding—S-105 phenolic resin binder and SM-5 silicone parting agent to release shell molds from their metal patterns. These, with GE's liquid core binder resin and Permafil for impregnating porous castings, enable foundries to obtain all necessary synthetics from a single supplier and receive application assistance.

Film Shows Welding Practice

Series of film strips for use by instructors to introduce students to the welding process, its equipment and where it is used is available from Lincoln Electric Co. Cleveland. The series presents in color preliminary steps in making basic joints with emphasis on safe practice. Closeups of the arc in action show each step in holding and moving the electrode, preparing and making joints, in several positions.

DELTA Cut-Off Saws mitre-cut aluminum frames for 2.9¢* each

*Includes all charges for depreciation, interest on investment in tools, maintenance, power and labor

At Orange Screen Co., with an output of 900 pieces per hour, cost of making mitre cuts on aluminum frames on double Delta cut-off saws is only 2.9 cents each, including all charges for depreciation, interest on investment in tools, maintenance, power and labor.

HERE'S HOW ORANGE SCREEN CO. SAVES

Delta abrasive cut-off saws set in pairs and specially tooled make the mitre cuts on both ends of aluminum window frame members at the same time at a cost of 2.9 cents per piece at the Orange Screen Co., Dover, N. J.

Says E. J. Belliveau, chief manufacturing engineer: *"These set-ups have worked like a charm for nine years. We need their high speed —4000 rpm spindle speed and 10,500 fpm surface speed. An operator—man or woman—can feed an 18' extrusion ½" x ⅜" up to 3" x 1" and turn out 900 pieces per hour. In spite of this fast pace, women operators regularly get incentive production 30 to 80 per cent above base.*

"As a matter of fact, we've standardized on Delta tools all over the plant. Our Delta tools— 20 cut-off machines, 27 drill presses, 3 belt sanders, 5 band saws and 2 circular saws— all have a fine record for accuracy, and with their small initial cost and long life, depreciation is extremely low."

There it is—history repeating itself. Another alert management that's found that low-cost, adaptable, accurate Delta tools out-produce and out-profit far more costly tools. It's easy to find out how you, too, can get these production savings. Talk to your Delta dealer listed in the yellow pages of your phone book under "Tools" or "Machinery." And send for the most useful tool catalog you can have in your desk—Delta AB-Catalog. Delta Power Tool Division, Rockwell Manufacturing Co., 638C North Lexington Ave., Pittsburgh 8, Pa.



range Screen Co. keeps blades sharp, es 10" steel blades that average 36,000 s between sharpenings. Maintenance in e years has been negligible, they report.



DELTA MILWAUKEE®
DELTA QUALITY MAKES THE DIFFERENCE

DELTA QUALITY POWER TOOLS
Another Product of **Rockwell**

stainless

Parts and Fasteners

CAMCAR
COLD-FLOW

Camcar specialists have developed Cold-Flow techniques for working Stainless and other non-corrosive materials to give you the same prompt service supplied on standard materials. You can choose material specifications from Camcar's inventory of Stainless Steels to solve both design *and* delivery problems.

STANDARD Stainless Fasteners supplied from stock for prompt shipment. Monthly stock list mailed on request.

AIRCRAFT SCREWS •

PHILLIPS • SEMS •

THREAD CUTTING • SHEET METAL

When you need Stainless— or any fasteners or special parts

Telephone 5-9451

Teletype RK8653

CAMCAR SCREW & MFG. CORP.
603 Eighteenth Avenue • Rockford, Illinois

"PRODUCTION-DESIGNED FOR YOUR ASSEMBLY LINE"

CALENDAR
OF MEETINGS

March 8-11, American Institute of Chem Engineers: Annual spring meeting, H Buena Vista, Biloxi, Miss. Institute dress: 120 E. 41st St., New York 17. retary: Stephen L. Tyler.

March 11, Foundry Education Foundati Annual meeting and technical, university industry advisory committee confere Hotel Cleveland, Cleveland. Foundation dress: Terminal Tower, Cleveland 13. ecutive director: George K. Dreher.

March 11-12, Society of the Plastics Indus Inc.: Annual Canadian conference, Gene Brock hotel, Niagara Falls, Canada. ciety address: 67 W. 44th St., New Y 36. Executive vice president: William Cruse.

March 15-19, American Chemical Socie Spring meeting, Hotels Statler and Biltmo Los Angeles. Society address: 1155—1 St. NW., Washington 6. Assistant sec tary: R. M. Warren.

March 16-18, National Association of Wa Material Dealers: Annual meeting, Ho Conrad Hilton, Chicago. Association dress: 271 Madison Ave., New York 16

March 16-20, National Association of Cor sion Engineers: Annual conference, Ho Sherman, Chicago. Association address: Milam Bldg., Houston 2. Secretary: A. Campbell.

March 16-20, National Association of Mar facturers: Institute on Industrial Relatio Hollywood Beach hotel, Hollywood-by-t Sea, Fla. Association address: 14 W. 4 St., New York 20. Director, employee lations division: Sybil S. Patterson.

March 17-18, Steel Founders' Society America: Annual meeting, Edgewater Be hotel, Chicago. Society address: 920 M land Bldg., Cleveland. Secretary: F. Ker Donaldson.

March 18-20, American Society of Tool En neers: Annual meeting, Hotel Statler, troit. Society address: 10700 Puritan A Detroit 21. Executive secretary: Harry Conrad.

March 19, National Industrial Confere Board: General session, Netherland-Pl hotel, Cincinnati. Board address: 247 P Ave., New York. Secretary: Clyde Rogers.

March 19-20, Porcelain Enamel Institute: W Coast conference, Hotel Statler, Los Ange Institute address: DuPont Circle Bl Washington. Secretary: John C. Oliver.

March 19-20, American Hot Dip Galvani Association Inc.: Annual meeting, Net land Plaza hotel, Cincinnati. Associa address: 1506 First National Bank Bl Pittsburgh 22. Secretary: Stuart Swenss

March 23-25, Liquefied Petroleum Gas A ciation: Annual Southeastern district vention & trade exhibit, Hotel Biltmore, lanta. Association address: 11 S. La St., Chicago 3. Publicity: Robert E. Bor

March 23-27, American Society for Me Western metals congress & exposition, Pacific Auditorium, Los Angeles. Infor tion: 7619 Beverly Blvd., Los Angeles. ciety address: 7301 Euclid Ave., Cleve 3. Secretary: W. H. Eisenman.

March 23-27, National Association of P Engineers Inc.: Annual spring meeting exhibit, Hotel Sherman, Chicago. Ass tion address: 176 W. Adams St., Ch 3. Secretary: A. F. Thompson.

March 25-27, Pressed Metal Institute: An meeting, Hotel Carter, Cleveland. Inst address: 2860 E. 130th St., Clevelan Managing director: Orrin B. Werntz.

March 25-27, Society of Automotive neers: National production meeting, Statler, Cleveland. Society address: 2 39th St., New York 18. Secretary: A. C. Warner.

March 26-27, Instrument Society of Am and Carnegie Institute of Technology: & steel instrumentation conference, Roosevelt, Pittsburgh. Society address Ridge Ave., Pittsburgh 12. Secretary: ard Rimbach.

(Continued on p. 139)



at UNITED STATES STEEL COMPANY

These blowers never take a "breather"

There's no time out for this trio of De Laval blast furnace blowers at the Gary Steel Works of the United States Steel Company. These three 12,350 hp, 110,000 cfm units help keep vital steel production rolling year in year out.

There are good reasons for this power-saving dependability. These heavy-duty machines are built to take punishment. Their rugged casings, husky, perfectly balanced rotors and externally mounted, cylindrically seated bearings are design features that reduce maintenance and insure continuous operation for long periods of service. And remember, there's no divided responsibility—both turbine and blower are De Laval designed and De Laval made.

De Laval blower experience covers a wide range of industries — steel, refining, metal mining, chemical processing, high pressure gas transmission, manufactured gas, sewage aeration and many others. And all this engineering and manufacturing experience is ready to solve your specific blower application.

DE LAVAL *Centrifugal Blowers*

DE LAVAL STEAM TURBINE COMPANY
860 Nottingham Way, Trenton 2, New Jersey

DL 130

Send for Bulletin 0500 containing complete data.

How Tubular Parts with Formed End Can be Produced most ECONOMICALLY



Here is a typical case of economy. Shown is a section of a cylindrical part now made in one piece from Wolverine tube with both ends almost closed by means of the Wolverine Spun End Process.

Having no seams or joints, this redesigned part offers assurance against leaks; and makes the complete unit more dependable at all times.

This product was formerly made from a cylindrical form capped at both ends and silver soldered at the joints.

*A PATENTED PROCESS RE. 22465.

Tubular parts requiring tapered rounded, flat or other shaped end can be made easily, quickly an economically by the Wolverin Spun End Process*.

By virtue of their improved de sign, the finished parts made by this proce perform more efficiently, and their mode lines add to the sales appeal.

This streamlined design also has the a vantage of eliminating several parts, thereb reducing labor and material costs and a sembly time as well.

A request on your letterhead will bring y a copy of our brochure "Spun End Proces

Other Wolverine Products

CAPILATOR* —the capillary tube for restriction purposes
COMMERCIAL TUBE
AUTOMOTIVE TUBE
CONDENSER TUBE
COPPER WATER TUBE (K-L-
ELECTRIC WELDED STEEL TUBE
FABRICATED TUBULAR PARTS
WOLVERINE TRUFIN* —the integral finned tube
REFRIGERATION AND AI CONDITIONING TUBE (Plain or Tin Plated)
S.P.S. PIPE
SPUN-END TUBE†

*Reg. U.S. Pat. Off.
† A Patented Process RE 224

Wolverine Trufin and the Wolverine Spun End Process available in Canada through the Unifin Tube Co., London, Ontario

WOLVERINE TUBE DIVISION
of CALUMET & HECLA, INC.
Manufacturers of Tubing Exclusively
1439 CENTRAL AVENUE • DETROIT 9, MICHIGAN

ESTABLISHED 1916

Plants in Detroit, Mich. & Decatur, Ala. Sales offices in Principal Cities

Export Department, 13 E. 40th St., New York 16, N. Y.

. . . and Back of WOLVERINE ELECTRIC WELDED STEEL TUBES

. . . is a history of more than 35 years of concentrated experience in making tube—not just ordinary tube, but tube of most dependable quality.

In entering this new field of electric welded steel tube production, we are drawing on all the best skills and techniques that have proved successful and won for Wolverine the high reputation it enjoys in the copper tube production—and you can accept the new Wolverine Welded Steel Tube with absolute confidence.

As a part of your condensers, heat exchangers or boilers, this quality tube will prove a valuable factor in making your equipment operate at top efficiency.

Wolverine engineers will help you select the right tube for your particular need.

Available
in Sizes . . .
¼" to 3" O.D.
in Analyses . . .
SAE 1016 SAE 1018 SAE 1020
SAE 1025 SAE 1010

ESTABLISHED 1916

WOLVERINE TUBE DIVISION
of CALUMET & HECLA, INC.

Manufacturers of Tubing Exclusively

1439 CENTRAL AVENUE • DETROIT 9, MICHIGAN

Plants in Detroit, Mich. & Decatur, Ala. *Sales offices in Principal Cities*

Export Department, 13 E. 40th St., New York 16, N. Y.

Items like these available QUICKLY at CHASE® warehouses

COPPER NAILS and TACKS

COPPER STORM NAILS

BRASS and BRONZE BOLTS and NUTS



BRASS and BRONZE CAP, MACHINE and LAG SCREWS

BRASS COTTER PINS
BRASS ESCUTCHEON PINS



BRASS and COPPER RIVETS, BURS

BRASS, BRONZE and COPPER WASHERS



SOLDERING COPPERS



INDUSTRIAL WIRE CLOTH and BRASS STRAINER CLOTH



INDUSTRIAL and AUTOMOTIVE FITTINGS



PERFORATED METAL IN BRASS, BRONZE and COPPER



BEARING BRONZE BARS

CALL US FOR ANYTHING from Bearing Bronze Bars to Brass or Bronze Bolts . . . or any other brass or copper item for maintenance, repair, operating or production.

Twenty-three Chase warehouses are located in major industrial centers from coast to coast. Phone the one nearest you. We can usually fill your orders from stock.

Chase® BRASS & COPPER

WATERBURY 20, CONNECTICUT • SUBSIDIARY OF KENNECOTT COPPER CORPORATION

The Nation's Headquarters for Brass & Copper

Albany†	Chicago	Denver†	Kansas City, Mo.	Newark	Pittsburgh	San Francisco
Atlanta	Cincinnati	Detroit	Los Angeles	New Orleans	Providence	Seattle
Baltimore	Cleveland	Houston†	Milwaukee	New York	Rochester†	Waterbury
Boston	Dallas	Indianapolis	Minneapolis	Philadelphia	St. Louis	(†sales office only)

(Continued from p. 134)

h 31-April 2, The Magnesium Association: ernational magnesium exposition, National ard Armory, Washington. Association iress: 122 E. 42nd St., New York 17. :retary: Martha I. Hanson.

7-9, Steel Shipping Container Institute: nual meeting, Biltmore hotel, Palm ach, Fla. Institute address: 600 Fifth e., New York 20. Secretary: L. B. Miller.

8-10, Society of the Plastics Industry : Pacific Coast conference, Last Frontier tel, Las Vegas, Nevada. Society address: W. 44th St., New York 36. Executive e president: William T. Cruse.

9-10, Malleable Founders' Society: Mar- development conference, Cornell Uni- sity, Ithaca, N. Y. Society address: ion Commerce Bldg., Cleveland 14. Man- ng director: Lowell D. Ryan.

9-11, Lead Industries Association: An- al meeting for members, The Greenbrier, ite Sulphur Springs, W. Va. Association iress: 420 Lexington Ave., New York 17. :retary: Robert L. Ziegfeld.

12-15, American Supply & Machinery nufacturers Association: Annual meeting l conference booth program, Hotel Co- bus, Miami, Fla. Association address: Clark Bldg., Pittsburgh 22. Secretary: Kennedy Hanson.

12-16, Electrochemical Society Inc.: An- l spring meeting, Hotel Statler, New k. Society address: 235 W. 102nd St., w York 25. Secretary: Dr. Henry B. Lin- d.

13-15, International Acetylene Associa- n: Annual spring meeting, Hotel Biltmore, anta. Association address: 30 E. 42nd . New York 17. Secretary: H. F. Rein- d.

13-15, American Society of Lubrication gineers: Annual meeting and exhibit, tel Statler, Boston. Society address: 343 Dearborn St., Chicago 4. Secretary: lliam P. Youngclaus Jr.

13-16, National Industrial Conference ard: Annual meeting for members, Miami, . Board address: 1900 Arch St., Phila- phia 3. Secretary: H. R. Rinehart.

14-16, Conveyor Equipment Manufac- ers Association and University of Illinois partment of Engineering: Conveyor insti- e, University of Illinois, Champaign, Ill.

16-17, American Machine Tool Distribu- s Association: Spring meeting, Netherland aza hotel, Cincinnati. Association ad- ss: 1900 Arch St., Philadelphia 3. Secre- y: Thomas A. Fernely Jr.

16-19, Grinding Wheel Institute: Spring eting, The Homestead, Hot Springs, Va. titute address: 2130 Keith Bldg., Cleve- d 15. Manager: Hunter-Thomas Associ- s, re F. A. Peterson.

18-19, Packaging Machinery Manufac- ers Institute: Spring meeting, Hotel Sher- n, Chicago. Institute address: 342 Madi- Ave., New York 17. Secretary: Helen L. atton.

19-23, American Hardware Manufactur- Association: Spring meeting, Hotel Adol- s, Dallas. Association address: 342 Madi- Ave., New York 17. Secretary: Arthur Faubel.

20-22, AIME Blast Furnace, Coke Oven Raw Materials Committee and National n Hearth Steel Committee: Annual con- ence, Hotel Statler, Buffalo. Institute ad- ss: 29 W. 39th St., New York 18.

20-22, Metal Powder Association: An- l meeting and exhibit, Hotel Cleveland, veland. Association address: 420 Lexing- Ave., New York 17. Secretary: Robert Ziegfeld.

20-23, National Screw Machine Products ociation: Spring meeting, Hotel St. Mor- New York. Association address: 2860 130th St., Cleveland 20. Secretary: Orrin Werntz.

21-23, Caster & Floor Truck Manu- turers Association: Spring meeting, Edge- er Beach hotel, Chicago. Association ad- ss: 27 E. Monroe, Chicago. Secretary: P. Dolan.

27-28, Galvanizers Committee, American Institute: Annual meeting, Hotel Statler, Louis. Institute address: 60 E. 42nd St., York 17. Secretary-Treasurer: E. V. t.

Versatile! Variable Centers!

Faster Straightening Of An Extreme Range Of Shapes On This *New* Machine

MEDART

Two-Plane–Overhung Roll-Variable Center

SHAPE STRAIGHTENER



Model TPOMVC. Also available for single-plane straightening.

- Combines the fast, simple setup advantage of an overhung roll straightener, with exceptionally versatile control of bending stresses possible only in a movable-roll center type of machine.
- Variable center roll housings permit adjustment of bending spans for handling an extreme variety of shapes and sizes. This feature prevents overloading of bearings and assures uncommon accuracy.
- Bottom rolls can be moved directly under top rolls for cross-rolling or reforming cross sections of distorted extruded or other shapes simultaneous with straightening action.
- Top and bottom rolls, when set in opposing pairs, act as additional pinch-feed rolls for extra traction required for difficult-to-straighten shapes.
- Rolls are quickly and easily changed by removing locknut on end of each shaft.
- Rolls are of Medart Smavroc alloy steel hardened and ground to shape . . . All gears operate in oil within enclosed housings . . . Pinch-feed rolls at end are air-operated. Timken bearings throughout.

Write For Complete Details

THE MEDART COMPANY 3535 DE KALB STREET ST. LOUIS 18, MISSOURI

Two 75-ton Bedford Overhead Travelling Cranes at new Northwestern Steel and Wire Co. plant, Sterling, Ill., tend 150-ton top-charging electric furnaces.
Here too, they chose Bedford! Cranes!
Both 75-ton Bedfords at Northwestern are equipped with 10-ton auxiliary hoists . . . have ample overload capacity. Operators in air conditioned cabs have constant, precise control of these smooth-operating workhorses.

In steel mills, where material handling jobs are tough, more and more production men have compared . . . and chosen Bedford. Today, the list of steelmakers using Bedford overhead cranes is a "bluebook" of the industry. And there's a reason . . .

A half century of specialized experience—designing and building heavy duty precision-engineered overhead cranes for every type of application—assures Bedford's ability to meet *your* specific requirements.

Bedford Overhead Electric Cranes are available in all types and sizes . . . from 5 tons to 350 tons, *and up* . . . for all kinds of indoor and outdoor service. Consult a Bedford engineer before *you* choose . . . and make *your* next crane a Bedford.

(Write for complete catalog describing Bedford Cranes in detail.)

BEDFORD CRANES — SERVICE

ENGINEERED CRANES

BEDFORD

BEDFORD FOUNDRY & MACHINE COMPANY, INC. · BEDFORD, INDIANA

MEN OF INDUSTRY

(*Continued from Page* 90)

member of the New York sale staff of **Girdler Corp.'s** Votator D vision. He joined Girdler in 194 and in 1950 was assigned to th field service and engineering sta with headquarters in New York.

Timken Roller Bearing Co. appoint ed **Richard K. McConkey** assistan general manager of its industria division, Canton, O. He has bee district manager for the division a



RICHARD K. McCONKEY
. . . Timken appointment

the Moline, Ill., office. He su ceeds the late **Melvin H. Kuhl.**

Robert J. Heggie was elected a rector of **A. M. Castle & Co.**, C cago.

Philip A. Gaebe, associated wi the production department Kaiser Steel Corp. at its Fonta Calif., plant, has been appoin senior sales engineer for basic fractories and chemicals in Pittsburgh area for the chemi division of **Kaiser Aluminum Chemical Sales Inc.**

Tom Dwyer of Minneapolis named district sales manager **Duchess Co.**, Fairfield, Iowa.

James E. Drylie was appointed sistant sales manager in charg the Sup-R-Guy Products Divis **Guibert Steel Co.**, Pittsburgh.

Pembroke W. Taylor was na

A FAMOUS Name in Pumps Specifies a FAMOUS Name in Materials...

MEEHANITE® METAL



Fig. 1



Fig. 2

NO one familiar with industrial products will deny that Vickers, Inc., Detroit, Mich. is truly a famous name in mps and all types of hydraulic equipment.

Among the many important types of pumps produced by ckers is the combination Vane-Type Pump (Fig. 1). In this h pressure unit designed for compactness for successful oper- on in limited space it is obvious that the housing or body ig. 2) would have to be produced in a metal which would vide regularly and dependably pressure tightness, high ten- e strength, uniformity, freedom from defects and good chinability. It is for these reasons that Vickers regularly cify Meehanite castings.

The name Meehanite Metal has also earned itself fame ong design engineers, production executives, management d purchasing officers who concern themselves with the selec- n, specification and procurement of component parts and terials requiring the maximum, both property and quality- e.

Whether your castings require density and pressure tight- s; or high tensile strength; or heat treatability for toughness d wear resistance; investigate the wide range of materials ilable in Meehanite castings.

Remember that Meehanite "Bridges the Gap" between cast n and steel!

Take *YOUR* Casting Problem To
A MEEHANITE FOUNDRY

American Brake Shoe Co.	Mahwah, New Jersey
The American Laundry Machinery Co.	Rochester, New York
Atlas Foundry Co.	Detroit, Michigan
Banner Iron Works	St. Louis, Missouri
Barnett Foundry & Machine Co.	Irvington, New Jersey
E. W. Bliss Co.	Hastings, Mich. and Toledo, O.
Builders Iron Foundry	Providence, Rhode Island
Compton Foundry	Compton, Calif.
Continental Gin Co.	Birmingham, Alabama
Crawford & Doherty Foundry Co.	Portland, Oregon
The Cooper-Bessemer Corp.	Mt. Vernon, Ohio and Grove City, Pa.
De Laval Steam Turbine Co.	Trenton, New Jersey
M. H. Detrick Co.	Peoria, Ill. and Newark, N. J.
Empire Pattern & Foundry Co.	Tulsa, Oklahoma
Farrel-Birmingham Co., Inc.	Ansonia, Connecticut
Florence Pipe Foundry & Machine Co.	Florence, New Jersey
Fulton Foundry & Machine Co., Inc.	Cleveland, Ohio
General Foundry & Manufacturing Co.	Flint, Michigan
Greenlee Foundry Co.	Chicago, Illinois
The Hamilton Foundry & Machine Co.	Hamilton, Ohio
Hardinge Company, Inc.	New York, New York
Hardinge Manufacturing Co.	York, Pennsylvania
Johnstone Foundries, Inc.	Grove City, Pennsylvania
Kanawha Manufacturing Co.	Charleston, West Virginia
Koehring Co.	Milwaukee, Wisconsin
Lincoln Foundry Corp.	Los Angeles, California
London Concrete Company, Ltd.	Brantford, Ontario
E. Long Ltd.	Orillia, Ontario
Otis Elevator Co., Ltd.	Hamilton, Ontario
The Henry Perkins Co.	Bridgewater, Massachusetts
Palmyra Foundry Co., Inc.	Palmyra, New Jersey
Pohlman Foundry Co., Inc.	Buffalo, New York
Rosedale Foundry & Machine Co.	Pittsburgh, Pennsylvania
Ross-Meehan Foundries	Chattanooga, Tennessee
Shenango-Penn Mold Co.	Dover, Ohio
Sonith Industries, Inc.	Indianapolis, Ind.
Standard Foundry Co.	Worcester, Massachusetts
The Stearns-Roger Manufacturing Co.	Denver, Colorado
Traylor Engineering & Mfg. Co.	Allentown, Pennsylvania
Valley Iron Works, Inc.	St. Paul, Minnesota
Warren Foundry & Pipe Corporation	Phillipsburg, New Jersey

MEEHANITE®

NEW ROCHELLE, N. Y.

P&H OVERHEAD CRANES

Only P&H BUILDS

COMPLETE ELECTRICAL EQUIPMENT

— designed specifically for Crane Service

You'll find a big difference in the crane electrical equipment built by P&H and that assembled from various sources. P&H designs it specifically for the severity of crane service. General purpose motors are not used. P&H has learned how to build crane motors through more than 50 years!

You'll find a big difference in performance—the entire crane is designed and built as a coordinated unit. P&H understands how to give you the utmost in faithful performance.

And you'll find a big difference in service when you need it. For only in this way can you put *all* the responsibility in the hands of *one dependable source*. There's no buck-passing among suppliers—no confusion or delays. P&H service is complete—reliable—alert. It will save you time and money. It's good reason for insisting upon P&H equipment throughout.

P&H ***MAGNETORQUE*®** **AC Crane Control . . .** an exclusive P&H development which provides speed-load characteristics not excelled by any other type of control. You should have all the facts about it. Write us.

P&H OVERHEAD CRANE DIVISION

HARNISCHFEGER CORPORATION

Milwaukee 46, Wisconsin

the P&H *Line*



GORDON M. SOMMERS
. . . chief eng. at Clearing Machine

nager, distributor sales, **River-e Metal Co.**, Riverside, N. J. ior to serving the National Pro-ction Authority, he was with vere Copper & Brass Inc.

rdon M. Sommers was appointed ief engineer at the Hamilton, O., nt of **Clearing Machine Corp.**

o-Plate Co. Inc., Hartford, Conn., cted **Eugene B. Hotchkiss** chair-an of the board.

M. Sargent, founder and former esident of **Pioneer Engineering & fg. Co.**, resigned his interest in at firm to open his own consult-g engineering office at 10120 W. Nichols Rd., Detroit.

el Roskam, manufacturing man-er, was promoted to vice presi-nt-manufacturing, **Cessna Air-aft Co.**, Wichita, Kans.

erman A. Schaefer was elected cretary of **Hewitt-Robins Inc.** to ceed **George F. Goodyear** who tired last year when the com-ny's executive offices were con-lidated in Stamford, Conn.

harles C. Conley was appointed to e newly created position of su-rvisor of research of **Houdaille-ershey Corp.**, Detroit.

orothy M. Bryant and **Jerome inder** have become associated with **ooker Electrochemical Co.**, Ni-gara Falls, N. Y., as chemists in ne development and research de-artment. **Neil F. Tomlin** joins ne company as a draftsman and

Ormond W. Gay as a mechanical engineer in the engineering department.

Taco Heaters Inc., Providence, R. I., appointed **Robert H. Chaffee** sales manager, heating and cooling products. He will have headquarters at the Providence offices.

Utica Drop Forge & Tool Corp. appointed **Paul L. Thornburg** factory representative in Virginia, North Carolina, South Carolina and Tennessee.

Walter E. Bornemann, manufacturers' representative at New Orleans, was appointed Mississippi-Louisiana representative for **H. H. Buggie & Co.**, Toledo, O.

A. G. Moore is representative for the New Jersey marketing area in sales, field application and servicing of products for **John Hewson Co.**

Appointed credit manager in the treasury department of **U. S. Steel Corp.** in Chicago is **Joseph J. McGovern.** Assistant credit managers are **Donald C. Sheldon, James W. Schalles** and **Carl J. Harley.**

Dr. Sylvan Wallach was appointed senior scientist on reactor design development for **Walter Kidde Nuclear Laboratories**, Garden City, L. I., N. Y.

J. C. Thorburn was appointed branch manager of **Westinghouse Electric Corp.'s** manufacturing and repair plant at Buffalo.

Carl H. Drenske will represent **Republic Mfg. Co.**, Cleveland, covering California, Washington and Oregon. His headquarters are in Van Nuys, Calif.

Miller Electric Mfg. Co., Appleton, Wis., named **Alexander McKenzie** district sales manager for parts of Ohio, Pennsylvania and West Virginia.

John P. Andrews joined the Lukenweld Division, **Lukens Steel Co.**, Coatesville, Pa., as a sales engineer. **Henry F. Peters** becomes manager of the technical service department of the company.

Maynard C. Miller was appointed sales engineer at the Detroit office of **Commercial Contracting Corp.**

P&H ELECTRIC HOISTS



There's MONEY in the air!

In the average plant, materials handling accounts for 20% of the total cost of the product. How about your operation? Are skilled workers wasting your time and money being load-lifters? There's a better way —

Handle it "thru-the-air" *FASTER—FOR LESS!*

P&H can help you cut costs, with swift, safe movement of loads above floor congestion. There's a P&H Electric Hoist to suit your needs exactly; the Zip-Lift for loads up to 1 ton—the Hevi-Lift for loads up to 15 tons—available with hook, jib or trolley mounting. A P&H representative can show you where and how to save money.

Call your P&H Dealer

P&H ELECTRIC HOIST DIVISION

HARNISCHFEGER CORPORATION

MILWAUKEE 46, WISCONSIN

Galvanic Corrosion Study

Bureau of Standards research shows how little zinc it takes to cut steel corrosion

STUDY of underground corrosion of hot-dipped galvanized steel pipe was recently completed by National Bureau of Standards. Results confirm previous NBS work in showing that galvanized steel having 3 ounces of zinc per square foot of exposed surface is highly resistant to corrosion in many soils which are very corrosive to bare steel.

Short lengths of galvanized and uncoated steel pipe, and plates of zinc, were buried at 15 test sites for periods up to 13 years. Located in widely separated parts of the United States, the test sites represented a wide range of soil properties.

After each of five periods of exposure, a set of specimens of each material was removed and returned to the NBS laboratories. After removal of the corrosion products, determinations were made of loss in weight, depth of the deepest pits, and percentage of area of galvanized specimens on which coating remained.

Thickness Varied—Although the nominal weight of the zinc on all the coated specimens was 3 ounces per square foot, actual thickness varied over a wide range. This was shown by a large number of thickness measurements made by a magnetic method, using unexposed samples of pipe from the same lot as the buried specimens. Additional determinations by an electrolytic stripping method showed that a large part of the zinc that was applied to the steel pipe was converted into alloys of zinc and iron.

Zinc coatings provided good protection in most of the soils. In one soil in which bare steel pipe was perforated by corrosion after exposure for only a few years, the coating on the galvanized specimens remained perfectly continuous throughout the entire 13-year period. In only two of the 15 soils, both organic, was the zinc coating of negligible protective value.

Surprising Results—An interesting finding of the NBS study was the high corrosion resistance that the galvanized specimens continued to show in most of the soils after the outer zinc coatings, and even after the zinc-iron alloy layer, had entirely corroded away. This continuing protection is tentatively attributed to an inorganic coating, probably silicious, believed to have been deposited by galvanic action between the outer zinc coating and the underlying steel or alloy layer.

This tentative explanation is based in part on unpublished studies which indicate that the zinc-iron alloy layer does not protect steel sacrificially (cathodically), and that the alloy is no more resistant than steel to soil corrosion.



Conveyor Belt: 72-Inch Width Possible

Goodyear Tire & Rubber Co. has completed the first flat belt to be vulcanized on its new giant conveyor press belt. Designed and built by Farrel-Birmingham Co., the press is more than 80 inches wide and can vulcanize conveyor belts up to 72 inches wide. It allows 1500 pounds of working pressure on each of 3 rams. This in turn produces a pressure of 275 pounds psi on the press plate

Handling Clinics Travel

Traveling material handling clinics to discuss local handling problems with chapter members of the American Material Handling Society will be conducted in principal cities during 1953. Decision to conduct the sessions was made by directors of the Material Handling Institute Inc. at its recent meeting in New York.

Purpose of the clinics, according to the institute, will be to promote better understanding of correct handling equipment application. Each of several traveling groups will be headed by an MHI official with specialists in various handling problems selected from the membership.

Ethyl Chloride Handling Rules

Safety rules and regulations for handling, storing, shipping and disposing of ethyl chloride are outlined in safety sheet SD-50 published by Manufacturing Chemists Association Inc.

While ethyl chloride vapors are highly inflammable and tend to form explosive mixtures with air the booklet points out that the material can be handled with safety if employees are educated properly and are familiar with its hazards. Also listed are Interstate Commerce Commission regulations regarding loading and unloading plus first aid procedure to follow in case of exposure to excessive vapors or contact with skin.

Copies of the 16-page data sheet can be obtained for 25 cents from the association, 246 Woodward Bldg., Washington 5.



$80,000 Saved By Field Engineering

Elwell-Parker put flanged wheels on this crane for railroad car repair shop. This saved great expense of paving yard for rubber tire crane. This Elwell-Parker crane also cut man-hours 90% on replacing car wheels.

ELWELL-PARKER

truck installations are *Field Engineered* to your needs

Buyers of Elwell-Parkers get far more than just a quality truck. One of many plus values is a personal analysis of their material handling needs by an E-P Field Engineer. There are 40 of these E-P men, resident in all principal cities. The average experience of these truck specialists exceeds fifteen years . . . behind them is Elwell-Parker's unmatched, 47 years of truck know-how.

E-P Field Engineers can help you select exactly the right truck from the complete line of Elwell-Parker high and low lift platform trucks, fork trucks, or mobile cranes. To solve your individual handling problem, they will work closely with you to design a special or modified truck.

E-P Field Engineered installations insure the best possible truck performance at no extra cost.

Learn about all the other Plus Features of Elwell-Parkers by writing for this General Catalog. The Elwell-Parker Electric Co., 4102 St. Clair Ave., Cleveland 3, Ohio.

ELWELL-PARKER
POWER INDUSTRIAL TRUCKS
Established 1893

the first completely universal....

60-cycle **induction**

BILLET HEATER

THIS Loftus Universal Thermo-Induct... nace is the most flexible 60-cycle billet... ever designed. You can heat every non-... metal, in the same furnace, either consec... or simultaneously, to its respective for... extrusion temperature. The unit maintai... efficiency, constantly, eve... heating **short-length** billet...

Loftus Thermo-Induction ... you the most practical, d... able, and efficient met... heating non-ferrous metals... achieve uniform heating in a matter of s... Production is continuous, and completel... matic. The press operator controls the f... Separate, positive control of each coil is ... fingertips.



The Loftus 60-cycle Thermo-Induction ... illustrated is designed to heat copper ... aluminum, and cupro-nickel for extrus... poses. The unit is readily adap... forging and rolling processes. I... sible, with this billet heater to h... dia. Aluminum billet to 800° F., a... brass billet to 1550° F., and a 10" dia... nickel billet to 1950° ALL AT THE SA... IN THE ONE FURNACE. Each billet is ... independently . . . from a single contro...

Send Today for Booklet describing Loftus 60 Cycle Induction Heating in Detail

Loftus ENGINEERING CORPORATION

Designers and Builders of Industrial Furnaces

610 Smithfield Street • Pittsburgh 22, Pennsylvania

NEW PRODUCTS and equipment

Reply cards on page 171 will bring you more information on any new products and equipment in this issue

ombined Press, Seam Welder

. assembles, welds vessels

Combination assembly press and th seam welding fixture is designed for assembly and automatic lding of light vessels, such as nks for water heaters. The fixre, designated AW-205, handles nks to 24 inches diameter, 7 feet ng and weighing up to 4000 unds.

It features a 5-ton assembly pres- re for pressing tank heads on the

ds of the shell and two air-op- ated kick-out devices for rapid otting and removal of vessels. eadstock has a 10 to 1 variable eed range. Reed Engineering ., Dept. ST, 1003-17 W. Fairview ve., Carthage, Mo.

R MORE DATA—CIRCLE REPLY CARD NO. 1

ertical Chucking Grinder

. . six sizes: 30 to 74 inches

Vertical chucking grinder is ofred in six sizes, 30 through 74 ches, to meet large work size reuirements. Variable speed drive ovides infinitely variable table eeds, from creep to top speed as ecified. Grinding spindle speeds n be furnished to meet requireents, with maximum horsepower ting for main head grinding spines of 10 hp and for side head indles, 5 hp.

Dual control desks with pushbutton controls provide maximum operating ease and efficiency. Desks are interlocked, located on either side of the machine so the oper-

ator can work from the most advantageous side. To provide automatic lubrication, Trabon systems installed on main and side heads distribute oil, properly metered, to all bearings requiring lubrication. Bullard Co., Dept. ST, Bridgeport 2, Conn.

FOR MORE DATA—CIRCLE REPLY CARD NO. 2

Gage Block Comparator Stand

. . . magnification: 110,000 to 1

Universal Electrolimit circuit and gage block comparator stand are combined with the manufacturer's



electronic recorder to provide an instrument with 110,000 to 1 magnification. Recorder's 11-inch scale is equal to only 0.0001-inch, with each primary division equal to five millionth inch and secondary divisions equal to one millionth inch.

The electronic recorder is provided with a pen lifter and chart drive switch. Thus, under normal operation it is used as an indicating instrument. By using the switch, the chart carriage is started and measurements are recorded on the chart paper. Pratt & Whitney, division of Niles-Bement-Pond Co., Dept. ST, W. Hartford 1, Conn.

FOR MORE DATA—CIRCLE REPLY CARD NO. 3

Metal Treating Furnace

. . . combines draw, quench

Combination draw-quench metal treating furnace is applicable for bright, scale-free tempering and controlled oxidation tempering from 400 to 1400° F. Furnace is fully automatic, with heating chamber separated from the combination

cooling chamber and quench tank by a sealed inside door. Controlled endothermic atmosphere is provided in both heating and cooling chambers.

Parts being treated do not contact air at any time during tempering. Work previously bright hardened remains clean and scale-free, eliminating blasting or pickling. The controlled atmosphere also makes it possible to hold oxidation or blue tempering within strictly controllable limits. Quench

An Open Letter of Thanks to V.I.P.*



SLITTERS

COILERS



PAY-OFF REELS

Do You Fly?

2800 ft. E.W. runway and club house, private field 2 miles west of Salem, maintained for your convenience. Wire or phone arrival time. We will meet your plane.

H. D. PAXSON, PRESIDENT
THEDA L. PAXSON SEC. - TREAS.

PHONE 3486
P. O. BOX 214

PAXSON MACHINE COMPANY

Engineers and Builders of
COLD-ROLLED STRIP-MILL EQUIPMENT
Specializing in Slitting Lines
SALEM, OHIO

Users of Paxson Equipment
Coast to Coast
U. S. A.

Dear Customers:

Thanks to you, *VERY IMPORTANT PEOPLE for giving us the users' point of view in developing Paxson Slitting Equipment.

You, the actual users, are the ones who really engineered and designed Paxson Slitting Lines.

The combined knowledge, ideas and suggestions of slitting men in plants large and small have guided us in developing custom built lines that best meet your specific needs.

For the utmost in modern efficiency and economical operations, users rely on us for both general and heavy duty lines.

Now, more than ever, it truly can be said:
"PAXSON GIVES YOU THE EDGE".

Appreciatively yours,

PAXSON MACHINE COMPANY

H. D. Paxson, President

HDP/t

"PAXSON GIVES YOU THE EDGE"
REG. T. M.

PAXSON MACHINE CO.

SALEM • OHIO

Engineers and Builders of Cold-Rolled Strip-Mill Equipment SPECIALIZING IN SLITTING LINES

REMEMBER, ALL PAXSON LINES ARE CUSTOM BUILT

k and loading, intermediate and oading doors are air hydraulical- operated. Ipsen Industries Inc., pt. ST, 715 S. Main St., Rock- d, Ill.

MORE DATA—CIRCLE REPLY CARD NO. 4

rnace Line Addition

. for enamel, heat treat work

Model TF-24 electric furnace is uptable for porcelain enameling well as a wide variety of heat ating operations. Unit's 36 x 48 24-inch chamber size makes it ctical for handling large, heavy ns or production quantities of

aller products. It operates at 00° F with a work load of 350 unds per hour.

Heating elements are set on each le of the chambers, from front to ck. Sufficient power is provided t produce rapid recovery time er door is opened or closed dur- g load change. Other design fea- es include counterbalanced door d operation by foot-controlled air linder. Pereny Equipment Co., pt. ST, 893 Chambers Rd., lumbus 12, O.

MORE DATA—CIRCLE REPLY CARD NO. 5

nd Workability Resin

. eliminates clay balls

Lustrex 886 resin is designed to minate clay balls from foundry nd and make possible production truer and more economical cast- gs. Its application is said to per- t uniform packing, eliminating ost cracks, fissures and soft ots. Reductions in clean-up time sult.

Manufacturer reports 1 pound of e resin produces uniform clay stribution in 1 ton of foundry nd. Only about one-sixteenth of e resin is burned out each time

FOR THE VERY BEST
See ATLAS
TRANSFERS - SCALE CARS
COAL CHARGERS - COKE QUENCHERS
60-TON BOTTOM DUMP ORE TRANSFER CAR

This is one of the latest Atlas Transfer Car designs arranged for modern hydraulic operation. It provides close control of the discharge and eliminates freezing of air lines in the winter. A hydraulically operated pusher arm is provided of the latest horizontal telescoping type. The brakes also are hydraulically operated and apply automatically if pressure is low or if power fails.

At this plant the car must cross over to the coke track to shift coke cars. There is no conductor rail on the coke track so the car is equipped with a motor-driven cable reel attachment, enabling it to perform this switching function. When operating on the cable reel the collector shoes are cut out and automatically raised off of the conductor rails. The cab is overhung to give the operator a line of vision down the side of the car.

THE ATLAS CAR & MFG. CO.
ENGINEERS and MANUFACTURERS
1100 IVANHOE ROAD CLEVELAND 10, OHIO

bryant
internal grinding



no. 1309-W

Finishes 2 bores and a taper straight and concentric. 2 wheelheads are used on this semi-automatic. Max. traverse stroke, 6". Max. grinding length, 3½".



no. 1109

For high production o small bores where acc racy of size and finish ar required. Max. travers stroke, 6". Max. grindin length, 3½".

no. 1316

Two wheelheads for high production of jobs requiring face and bore, or face and O.D. grinding. Max. traverse stroke, 20". Max. grinding length, 8".



no. 1116

A general purpose ho grinder for tool room, smc shop, or general produ tion. Maximum travers stroke, 20". Maximu grinding length, 8".



no. 1416

Specially designed for grinding bores in long work, such as machine tool spindles. Maximum traverse stroke, 20". Maximum grinding length, 8".



no. 1209

A fully automatic, hig production machine f small and medium bo grinding. Max. traver stroke, 6". Max. grindi length, 3".



no. 1460

For production or single piece hole grinding on parts up to 60" diameter. Max. traverse stroke, 21". Max. grinding length, 16".

no. 2209

For precision and hi production grinding of b bearing races, gears, ro bushings, etc. Max. traver stroke, 6". Max. grindi length, ¾".



BELL mouth holes are a common internal grinding error. General available information advises simply turning the workhead or changing the length of traverse to correct this error, to generate a straight hole. In the case illustrated above, where bell mouth exists at one end of the hole, neither turning the workhead nor changing the length of stroke will correct this error.

In order to grind a straight hole the wheel must traverse the work in a straight line parallel to the axis of the work. The wheel path (the line in which the wheel traverses) is controlled by the slides under the wheelhead. If the slides are straight and true, the wheel path will be a straight line. If the path of the wheel varies from a straight line, the variation will be generated in the work.

At point "a" the wheel path and axis of the work are parallel and the wheel is set to grind a straight hole. Because of an error in the wheelslide ways, the wheel path is distorted and the wheel is plunged into the back end of the work and the wheel path and work axis diverge as shown at point "b". Wheelslide error can introduce distortion of many types within the work in addition to the one illustrated. The remedy is to correct the wheelslide ways which will, in turn, straighten the wheel path. The wheel contact will be improved, resulting in better finish.

Bryant Chucking Grinder Company
Springfield, Vermont, U. S. A.

Internal grinders • Internal & External thread gages

the sand is used. Plastics Division, Monsanto Chemical Co., Dept. ST, Springfield, Mass.

FOR MORE DATA—CIRCLE REPLY CARD NO. 6

Helix Milling Cutter

. . . with 90° cutting surface

This high helix shear type milling cutter has a cutting surface of more than 90 degrees and is designed to mill compound contoured surfaces. The teeth are always in contact with the workpiece, clean themselves and impart a smooth finish. Douglas Tool Co., Dept. ST, 2300 E. Nine Mile Rd., Hazel Park, Mich.

FOR MORE DATA—CIRCLE REPLY CARD NO. 7

Aluminum Oxide Compositions

. . . finishes aluminum castings

A series of aluminum oxide compositions for the coloring operation in the finishing of zinc base and aluminum die castings is available. It is claimed that compositions gi castings of these metals the desir luster or color quickly. They m also be used in steel and stainle steel finishing. Hanson-Van Wi kle-Munning Co., Dept. ST, Mat wan, N. J.

FOR MORE DATA—CIRCLE REPLY CARD NO. 8

Continuous Paint Stripping

. . . done by one-step chemica

Paint stripping from convey hooks, hangers and other li handling equipment, as well paint rejects, is a regular produ tion conveyor line operation wi one-step chemical treatment. T

procedure provides for running t conveyor line hangers, et through a tank of one-step chemic stripper at a given point.

Prior to reaching this stage, fi ished workpieces are removed. the stripping point, accumulat paint rejects can be placed on t line and stripped along with t equipment. Manufacturer repor the setup can mean a time savin of up to 90 per cent. The chemic can also be applied by spray met od if desired. Klem Chemicals In Dept. ST, 14401 Lanson Ave., Dea born, Mich.

FOR MORE DATA—CIRCLE REPLY CARD NO. 9

Automatic Small Part Elevator

. . . no personnel variables

Automatic elevator feeds sm parts on a variety of producti jobs. These include feeding e vated hoppers, transferring pa from conveyor to conveyor, e vating and metering parts to continuous furnace or feeding aut matic hoppers on machine too Continuous operation serves eliminate personnel variables production jobs.

Called the Magnavator, the e vator employs one or more Alni permanent magnets mounted in

Yes, you're seeing DOUBLE

In fact, when you watch Differential Air Dump Cars in action you're seeing double in several respects —

DOUBLE ACTION — they dump cars both ways, to left or to right. The 50° dumping angle assures a clean dump, and the massive air cylinders (two on each side) assure speedy, reliable dumping power. The double trunnion, double fulcrum design are key features in Differential's amazing performance.

DOUBLE UTILITY — Good for hauling in ore and good for hauling out waste materials. Car is built to withstand abuse and heavy service. If you haul as many as 400 to 500 carloads yearly, the savings with Differential equipment will pay for the cars.

Differential Products Include: Air Dump Cars, Locomotives, Mine Cars, Mine Supply Cars, Rock Larries, Mantrip Cars, Dumping Devices and Complete Haulage Systems

DIFFERENTIAL STEEL CAR COMPANY

FINDLAY, OHIO

SINCE 1915 — PIONEERS IN HAULAGE EQUIPMENT

r Brass and Copper Tubing that will LAST...

ert tubing buyers everywhere have been quick t take advantage of the savings offered by H & H ETALFLO. Originated and manufactured clusively by H & H, this BRAZED BRASS tubing n be substituted for seamless tubing wherever onomy is a factor . . . whether it be in the house- ld accessory field as illustrated above, or in the nufacture of bathroom fixtures, automotive, uck and tractor parts. So to cut *your* tubing sts, why not take this advice? For brass and pper tubing and fabricated parts that will t, see your nearby H & H representative *first*.

Think of H&H *First*



METALFLO
(BRAZED)

METALFLO is fabricated in O.D.'s of ¼" through 1¼" in wall thicknesses of .035" and lighter. It is also available in cut or random lengths, or formed to your specifications.

H&H TUBE AND MANUFACTURING COMPANY
255 North Forman Avenue, Detroit 17
Originators and sole makers of "Metalflo" — the economy tubing



METALFLO LOCKSEAM COIL STRIP AND SEAMLESS TUBING TUBULAR PARTS





D & J PRESS CO. LINES THEIR BALING PRESSES WITH SPEED TREAT STEEL PLATE TO STAND THE GAFF!

D & J Press Co., Inc., Buffalo, N. Y., builds scrap baling presses large enough to take an automobile and compress it into a bale 2' x 2' x 5', weighing about 1-ton. The charging box is 6' wide, 5' deep, 14' long. Compression, from one end and one side, is furnished by two 14", 2,000 lb. cylinders and two 17", 2,000 lb. cylinders. Construction is welded heavy boiler plate. Charging box and platens are lined with ¾" SPEED TREAT (X1545) open hearth, medium carbon steel plate — selected because it is so easy to machine (in this case, drilling holes), and because it ably resists abrasion and impact. In this application the SPEED TREAT plate has a tendency to work-harden and resists gouging.

SPEED TREAT Steel, one of the Speed Steels, has remarkable physical properties — speeds machining, increases tool life, readily polishes to a high lustre, suited to flame or induction hardening and other treatment — widely used for machine parts, hardened gears and sprockets, rubber molds, short run blanking dies, etc. Consult your nearest distributor.

SPEED STEELS

SINCE 1850 W. J. HOLLIDAY & CO. INC.

SPEED ALLOY • SPEED CASE • SPEED TREAT

DISTRIBUTED BY

Brown-Wales Co., Cambridge-Hartford-Auburn, - Bridgeport Steel Co., Milford, Conn. Beals, McCarthy & Rogers, Buffalo, N. Y. - Burger Iron Co., Akron, Ohio - Grammer, Dempsey & Hudson, Inc., Newark, N. J. - Earle M. Jorgensen Co., Los Angeles-Houston-Oakland-Dallas - Passaic County Steel Service, Inc., Paterson, N. J. - Peckover's Ltd., Montreal-Toronto - Peninsular Steel Co., Detroit, Mich. - Pidgeon-Thomas Iron Co., Memphis, Tenn. - Horace T. Potts Co., Philadelphia-Baltimore-York, Pa.

Produced by W. J. Holliday & Co., Inc., Speed Steel Plate Division, Hammond, Indiana. Plants: Hammond and Indianapolis, Indiana

nonmagnetic container. This container is suspended from a fabricated steel arm whose length varies to suit depth of container in which the parts are located. Prab Conveyors Inc., Dept. ST, 19875 Mack Ave., Detroit 26, Mich.

FOR MORE DATA—CIRCLE REPLY CARD NO. 10

Single-Spindle Bar Machine

. . . job changes in 1¾ hours

Model 126 single-spindle bar machine can be used in the turret lathe department or screw machine line. It has sufficient speed for aluminum and strength for high-temperature alloys. Machine can be changed from one average job to another in about 1¾ hours. Its

four standard cross slide cams cover all desired cross slide feeds. Universal turret cam provides infinite variation in cross strokes up to 6¾ inches and preselection of 10 automatically changed turret feeds.

Program drum or central control station governs cutting off, unchucking and stock feed stroke operation. The five shifter arms on the program drum preselect any one of 10 possible different turret feed gear ratios in the automatic transmission. New Britain Machine Co., Dept. ST, New Britain, Conn.

FOR MORE DATA—CIRCLE REPLY CARD NO. 11

Self-Indexing Bed Turret

. . . greater tool clearance

Self-indexing bed turret's tilt-head design makes it possible to swing tools as large as 6 inches diameter over the ram and gives working travel of 7¼ inches. Repeating accuracy is assured by a tapered locating pin that works in a sleeve bearing and locates in a mating seat.

One feature of the turret is its



FOR SPECIAL METAL FORMING PRESSES... CONSULT WITH US...

TYPICAL of many Hydraulic Presses built to customer specifications by Erie Foundry Company is this 500 ton metal forming press operating in the plant of a large eastern manufacturer. The importance of sound design and rugged construction becomes equally evident on production cost sheets whether the equipment is highly specialized or standard. For this practical reason special precision hydraulic presses by Erie Foundry Company are widely preferred. You are assured of the results you want when you take advantage of the half century of experience represented in Erie Foundry Company presses. Write for bulletin 350.

ERIE FOUNDRY COMPANY HYDRAULIC PRESSES

ERIE FOUNDRY COMPANY · ERIE, PA., U.S.A.

DETROIT 335 Curtis Building · CHICAGO 13 South Austin Blvd. · INDIANAPOLIS 2302 N. Meridian Street · NEW ENGLAND G. V. Eads, Kent, Conn.

More equipment rusts out than breaks down. Corrosion is a destructive force that every user of fastenings faces.

Many manufacturers today have found that fastenings by Harper mean longer life for equipment, better appearance, well-satisfied customers—because they resist corrosion.

The H. M. Harper Company is the world's largest exclusive producer of fastenings in brass, naval bronze, silicon bronze, monel, nickel, aluminum and all stainless steels. Over 7,000 items in these metals are carried in stock, bringing the advantage of a single source of supply for all fastenings.

Harper distributors are located in all market areas, and back of these distributors is a complete metallurgical and engineering service, ready to assist in solving any corrosion problem.

THE H. M. HARPER COMPANY
8207 Lehigh Avenue, Morton Grove, Illinois

HARPER

SPECIALISTS IN FASTENINGS

to solve corrosion problems

SPECIALISTS IN CORROSION RESISTANT FASTENINGS
HARPER
EVERLASTING FASTENINGS
BRASS • SILICON BRONZE • NAVAL BRONZE • MONEL • ALUMINUM • STAINLESS STEEL

Specify . . .
. . . WEIGER-WEED
for sound, clean welds!

(shown left)
WEIGER-WEED
Cold Formed
Offset Tip, Type D

WW®

Standard Replaceable
Cold Formed Offset

WELDING TIPS

Through the development of special cold forming equipment and methods, Weiger-Weed produces offset welding electrodes with these important advantages: . . .

- No loss of physical or electrical properties—cold formed offset tips have the same hardness and conductivity as straight tips.
- No distortion of taper—good electrical contact, no water leaks.
- Full cooling—water hole is as deep as in straight tips.
- Full workable nose length.
- Economy, quick delivery—most styles are formed quickly from standard straight tips.

Many other special cold formed electrodes to lick difficult clearance problems can be worked out by WW if quantities warrant the tooling. Give us the details of your problem.

WW®

22801A

WEIGER-WEED & CO., Division of Fansteel Metallurgical Corp. • 11644 Cloverdale Avenue • Detroit 4, Michigan

NEW PRODUCTS and equipment

long working stroke with short minimum index stroke. Through clutch arrangement, indexing can be done manually or automatically. The tur-



ret is designed for most 10, 11 and 12-inch lathes. A. K. Tool Co., Dept. ST, 2029 Blake Ave., Los Angeles 39, Calif.

FOR MORE DATA—CIRCLE REPLY CARD NO. 12

Steel Corner Guard

. . . protects products, equipment

Corner guard is employed to protect stored material and handling equipment from damage. The guard is adaptable to all types of storage—on skids, pallets, floors, etc.

It is constructed of heavy gage steel with brilliant black and yel-

low lithograph finish, in accordance with National Safety Council standards. It is constructed with a reinforced gusset plate on the back so it can slide directly under the load. This also serves to prevent it from falling. Randolph Metal Products Co., Dept. ST, 3843 W. 43 St., Chicago 32, Ill.

FOR MORE DATA—CIRCLE REPLY CARD NO. 13

Boiler System Treatment

. . . cuts scale and corrosion

Scale and corrosion, major operational problems common to steam boilers are said to be eliminated by a caustic extraction treatment. Called Borgana, the treatment

STAMPINGS

Our impartial use of three basic methods gives you economy regardless of length of run.

Most parts can be made by all three methods. But only **one** is **most** economical. The right decision is a technical one, based on **over-all** quantity, contour dimensions, tolerances and materials.

YOUR SUPPLIER SHOULD KNOW ALL THREE METHODS



This logarithmic chart shows the effect of these factors on the **specific part** illustrated. From 1 to 150 parts, our own **Machine-Cut Method** with no die cost whatsoever is most economical. At 150 parts, the **Short-Run Method** using economical blanking dies and stock punches is best. At 10,000 units, the standard **Production Method** with standard dies is most satisfactory.

SEND FOR INFORMATIVE LITERATURE

STAMPINGS DIVISION

LAMINATED SHIM COMPANY, INC.

3403 Union Street, Glenbrook, Conn.



BRIDGEPORT BRASS COMPANY

COPPER ALLOY BULLETIN

Bridgeport Brass Co. MILLS IN BRIDGEPORT, CONN. AND INDIANAPOLIS, IND.—IN CANADA: NORANDA COPPER AND BRASS LIMITED, MONTREAL



Silicon bronze cold headed and roll threaded fastenings are dependable in service and economical to fabricate — courtesy Scovill Mfg. Co., Waterville, Conn.

SILICON BRONZE FASTENINGS
Meet High Engineering Requirements

Vital equipment and, in fact, life itself may depend upon the reliability of metal fastenings used. Consequently, it is absolutely necessary from an engineering standpoint that the metal, from which fastenings are made, be reliable and dependable under the various service conditions encountered such as high stresses, corrosive environments of various kinds, moisture, fatigue, temperature changes, etc.

For all-around general engineering requirements for making cold headed items, Silicon Bronze 609 wire is widely used. It contains about 98% copper and 2% silicon and has the fine corrosion resistance and the workability of copper plus the strength and toughness of some grades of steel. Since they are not whittled away by rust, silicon bronze articles retain their original physical properties.

Resists Stress Corrosion Cracking

Silicon bronze is much more stable than the yellow brasses as far as resistance to stress corrosion or season cracking is concerned because of its very high copper content.

The chart shows the comparative behavior of accelerated stress corrosion tests on Silicon Bronze 609 versus yellow brass. The samples, while under tension, were immersed in concentrated ammonium hydroxide vapors. Tested after a 24-hour period, the silicon bronze had retained 87% of its tensile strength. Any loss was due to the reduction in cross-sectional area from the corrosive action of the solution. On the other hand, the yellow brass had cracked badly and only 12% of its original tensile strength remained.

This laboratory test is, of course, much more severe than encountered in actual service. It indicates that Silicon Bronze 609 is suitable for outdoor service conditions but yellow brass, under stressed conditions in the same environment, is not recommended.

Although Silicon Bronze 609 is moderately strong in the annealed condition (about 43,000 psi), it attains a very high tensile strength when hard drawn to the temper suitable for making screw products by cold forging and roll threading. The hard drawn wire is extremely malleable and is excellent for making cold headed products even with very large heads. No relief anneal is necessary for the finished products because the metal does not become brittle even after a high degree of cold working.

STRESS CORROSION TESTS — COMPARISON BETWEEN SILICON BRONZE AND YELLOW BRASS



Making a Cap Screw with an Oversized Head

The first operation reduced the .340″ wire to .276″ by "extrusion." This cold working operation not only increased the strength of the shank but pushed up extra stock required in order to fill the die for the large head. Extrusion and thread rolling increased the tensile strength of the shank to about 100,000 psi as compared with an ordinary low carbon steel screw which averages about 70,000 psi.



Steps for making a silicon bronze cap screw with an unusually large head — Scovill Mfg. Co.

The cold heading and roll threading processes have many advantages both from quality and economy standpoint — great strength, uniformly high quality, close tolerances, high speed manufacture, and very low scrap generation during fabrication.

Many Applications

Silicon bronze fasteners and special cold headed parts, as illustrated above, can be used to advantage for practically every product in every industry. Examples are: common bolts and nuts, clamps and special fastenings for high tension and standard voltage electric transmission equipment; builders', marine and pole line hardware; home appliances, outdoor signs, transit systems, automotive accessories, valve stems, instruments, water meters, signal systems, mine equipment, etc., etc.

More detailed information on wire alloys for cold heading is given in the Bridgeport Brass "Technical Handbook." Please contact Bridgeport's nearest sales office for laboratory help and your metal requirements. (964

AUSES OF CORROSION

his article is one of a series of discussions by L. Bulow, corrosion metallurgist of the ridgeport Brass Company.

Alloy Composition vs. Sodium Hydroxide Solution Containing Hydrogen Sulfide

In last month's column we showed at the corrosion resistance of the pper-zinc alloys towards sodium hyoxide solutions containing hydrogen lfide increased with increasing zinc ntent and other alloying elements.

The corrosion resistance of the cop-r-nickel alloys increases with deasing copper content. The effect of ckel is approximately the same as for equivalent amount of zinc (see curve Feb. 1953 issue).

These laboratory data clearly show at the 70 copper 30% nickel alloy is uch more resistant to the action of drogen sulfide in this alkaline solun as compared with alloys containing higher percentage of copper. These ata are in agreement with existing rvice and field data comparing 70-30 pper-Nickel alloy with 80-20 and -10 Copper-Nickel alloys in liquors nd vapors containing sulfides.

In the absence of hydrogen sulfide in sodium hydroxide solutions, the rate of corrosion of the copper-nickel alloys is considerably lower than shown in this curve. A test conducted in hot caustic liquors containing 10 to 50% sodium hydroxide and 5 to 16% sodium chloride showed that 70-30 Copper-Nickel alloy corroded at a rate of approximately .0002 ipy. In the same environment an 83-17 Copper-Nickel alloy corroded at a rate of .005 ipy.

It is evident from this information that the rate of corrosion of the Copper-Nickel alloys in sodium hydroxide solutions is influenced greatly by the presence of sulfides. Some of the variations in the corrosive action of sodium hydroxide encountered in service are due to the unrecognized influence of sulfides present even in small amounts.

It appears from the available test data that the corrosiveness of sulfur compounds towards copper and copper alloys decreases from hydrogen sulfide to the mercaptans. The mercaptans become progressively less corrosive with lengthening of the carbon chain with the 6 to 10 carbon chain mercaptans being very slightly corrosive. Aldehydes and other substances have been reported as being effective in reducing the corrosiveness of hydrogen sulfide towards copper and other metals.

CORROSION OF COPPER-NICKEL ALLOYS IN BOILING 0.8N SODIUM HYDROXIDE SOLUTION CONTAINING HYDROGEN SULFIDE AND SODIUM CHLORIDE (0.5N)



NEW DEVELOPMENTS

This column lists items manufactured or developed by many different sources. None of these items has been tested or is endorsed by the Bridgeport Brass Company. We will gladly refer readers to the manufacturer or other sources for further information.

Air Vise, foot controlled, is said to have instant open and shut responses. Jaw opens to 3 inches, leaves operator's hands free for work. Gripping force is 15 times air line pressure. Unit is compact, can be bolted to any bench. **No. 1285**

Carbide Tool Sharpener uses inexpensive silicon carbide paper belt instead of scarce diamond materials. Belt is joined by patented process to avoid ridges. Method is claimed to cost about two-thirds less than conventional methods per tool sharpened and to produce a longer lasting edge. Machine goes directly from rough-ground to micro-finishing stage in one operation and can grind any normal relief angle on cutting tool. **No. 1286**

Magnifying Spectacles for inspection or operations work where close tolerances are required or where eye strain is present, are said to employ same optical system as binoculars, give 2x magnification with clarity. **No. 1287**

Precision Hand Files are available in a kit containing eighteen units, from 0.009 to 0.072 in. thick. Tolerance is within 0.0004 to 0.0007 inches. They are said to be useful for precision slot filing, gap filing of electrical contacts and can be entered into locations inaccessible to thicker files. **No. 1288**

Conveyorized Grinding Machine operates at 6500 fpm, carries parts to be ground or finished in jigs or holders attached to heavy-duty conveyor belt under grinding wheel. After grinding, machine dumps parts automatically into tote boxes. Wheel is reported to have adjustable drive to compensate for wear and maintain grinding speed and can be contour dressed to suit the operation. **No. 1289**

Baked Enamel Hammer Finish for metal products is said to adhere well, and it is chip and scratch resistant. Covers surface imperfections with one coat, does not require primer. Applied by spraying, it bakes for ½ hour at 300° F or for 1½ min. at 425° F. Available in a variety of colors in 5-gal. cans and 55-gal. drums. **No. 1290**

BRASS, BRONZE, COPPER, DURONZE, NICKEL SILVER, CUPRO NICKEL
BRIDGEPORT BRASS
BRIDGEPORT BRASS COMPANY, BRIDGEPORT 2, CONN. • ESTABLISHED 1865
Mills at Bridgeport, Connecticut, and Indianapolis, Indiana • In Canada: Noranda Copper and Brass Limited, Montreal
Warehouse Service with Slitting Facilities in Principal Cities
(Advertisement)

liquid is added at a rate of about 1 quart per 100 boiler horsepower per week on boilers under 400 psi.

The product is nontoxic to personnel, either internally or externally. In addition, it is noninjurious to metals, gaskets or packing materials and will not contaminate process materials. Treatment does not depend upon chemical reaction, but dissolves scale by detergent action. Secondary action is effective against corrosion, foaming and embrittlement. Strong, Carlisle & Hammond Co., Dept. ST, Cleveland 13, O.

FOR MORE DATA—CIRCLE REPLY CARD NO. 14

Oil Fog Lubricator

. . . for air powered devices

Micro-Fog lubricator for bearings, spindles, gear boxes and small air powered devices produces an extremely fine and uniform oil fog at low air flow. Its features include a constant oil level, 360 degree visibility of oil flow and accurate metering of oil delivery into air line to as little as one drop in 20 minutes by air control. C. A. Norgren Co., Dept. ST, Englewood, Colo.

FOR MORE DATA—CIRCLE REPLY CARD NO. 15

Packaging Machine

. . . forms, seals automatically

Auto-Pak packaging machine automatically forms two sheets of heat-sealing material around products, seals the four sides, cuts off and delivers a sealed package. The packager plugs into any ordinary light circuit, makes packages from



1-inch square by ½-inch thick to 6 inches square from most heat sealing webs.

Attachments, including belt, turret and hopper, are available for automatic feeding. When products are hand fed, speed reaches 40 packages per minute. Automatic or semiautomatic feeding ups this rate and eliminates operator error. Pak-Rapid Inc., Dept. ST, 530 N. 21st St., Philadelphia 30, Pa.

FOR MORE DATA—CIRCLE REPLY CARD NO. 16

Multiple-Action Scrubber

. . . controls stack dust

Multiple-action scrubber combines six different precipitation stages to control a wide range of stack dust. It is especially adapted to controlling emission from rotary dryers, cyclones, kilns, roasters, mixers and pulverizer exhausts. Important to efficiency and operating economy is the average draft loss—about 2 inches of water column.

The scrubber is built in sizes for capacities from 1500 to 48,000 cfm. A recirculating system can be used

...ON CARAVAN AXLES

Rutted ground or high grade highway . . . equipment mounted on CARAVAN axles is ready to roll over any surface. These quality-built assemblies assure positive trail at high speeds as well as stability for the heaviest equipment over the roughest ground.

CARAVAN axles feature double-acting spring cushioned draw bar to minimize stopping and starting shock, sturdy solid steel axle beam construction, extra-heavy center arm stop blocks and heavy-duty steering knuckle. Wide inside wheel turning angle assures maximum maneuverability and eliminates jack-knifing.

CARAVAN units are available as single-axle two-wheel assemblies and as four-wheel running gear equipped with automotive type steering. They are recommended for mounting military and industrial equipment as well as field service and construction machinery weighing up to 14,000 lbs.

Write today for the new Bulletin No. 53 for further information.

1169-UM

THE UNITED MANUFACTURING CO.

319 INTERSTATE STREET • BEDFORD, OHIO

TOPS SHAKES...PUTS PURR-R-R IN POWER

PENFLEX TUBING
TAMES POWER THROB... OPERATION COOLER

When two large diesels roar into action, there can be plenty of vibration transmitted to all points. This was true on one installation . . . engine vibration created a regular power throb.

The answer was found in a length of Penflex four wall interlocked air jacketed exhaust tubing on each exhaust. The flexibility of the tubing absorbed the vibration . . . put a purr in power. At the same time it achieved a circulation of air and efficient cooling action . . . prevented breakage due to thermal expansion.

Whether your problem is vibration of exhaust lines or air lines . . . the transmission of liquids, volatiles, granular material or coarse abrasive products, Penflex engineers will be glad to work with you in the application of tubing from ⅛" I.D. on up. Penflex also manufactures barrel fillers, pneumatic rivet passers and a complete line of accessories and fittings.

Get your copy of this folder on "Flexineering."

Pennsylvania Flexible Metallic Tubing Company, Inc., 7219 Powers Lane, Phila. 42, Pa.
Branch Sales Offices: Boston • New York • Chicago • Houston • Cleveland • Los Angeles

PENFLEX

HEART OF INDUSTRY'S LIFE LINES

STANDARD'S SHIELDED BEARINGS

Are Expressly Designed for Foundry Conveyor Service





Every Standard roller conveyor is equipped with specially designed bearings that provide the maximum of protection and durability in foundry service. Spillage of hot iron is guarded against by special steel shields. These convex shaped shields fit into the ends of rollers to repel foreign matter. An exit for small particles is provided by an opening at bottom of shield.

Foundry conveyors are designed and built in their entirety by Standard—in a wide range of sizes, weights and types. You can depend on Standard for the right conveyor for your needs — we have been designing and building foundry conveyors since 1906.

STANDARD CONVEYOR COMPANY
General Offices: N. St. Paul 9, Minn.
Sales and Service in Principal Cities

Engineered Conveyor Systems • Portable Conveyor Units • Spiral Chutes • Pneumatic Tube Systems

Send for Standard's special catalog, ST-33, "Conveyors for Foundries"—a valuable reference book illustrating and describing conveyor installations in leading foundries.

ENGINEERED FOR LOW-COST PRODUCTION

where water supply is a problem For best results, the system requires about 2 gallons of water per minute at 40 to 50 psi for each 1000 cu ft of gas per minute. Cor-

rosion-resistant metal linings are installed where corrosion is a problem. Johnson-March Corp., Dept ST, 1726 Chestnut, Philadelphia Pa.

FOR MORE DATA—CIRCLE REPLY CARD NO. 17

Welding Torch Mixer

. . . attached without wrench

This welding torch mixer uses Gas-tite servene seating rings. The gasket type seating permits mixer to be attached to torch handle without using a wrench. Apparatus permits changing from welding to cutting or vice versa, using the same Torchweld handle. National Cylinder Gas Co., Dept. ST 840 N. Michigan Ave., Chicago 11 Ill.

FOR MORE DATA—CIRCLE REPLY CARD NO. 18

Adjustable Conveyor

. . . many jobs in one area

Belt conveyor has extendable boom with overall 11-foot length when entirely retracted and 18-foot length fully extended. It is mounted

on four swivel casters and driven by a ¾-hp right angle worm and gearhead motor. Convey-

Definitely designed for dependable service



Philadelphia SPIRAL BEVEL – HELICAL Speed Reducing Units



Available in single, double and triple reductions in standard ratios up to 238 to 1. Send for Catalog SB-50.

Into the design and manufacture of these units go many years of specialized experience and engineering knowledge. From the size and contour of the housings to the proper selection and placement of gears and bearings, greatest care is given to insure economical and reliable transmission of power with minimum maintenance. Indicative of advanced designing is the dry well construction which prevents oil-drip around the output shaft of the vertical unit.

Philadelphia Gear Works, INC.

ERIE AVE. AND G ST., PHILADELPHIA 34, PA.

NEW YORK • PITTSBURGH • CHICAGO • HOUSTON • LYNCHBURG, VA.

Industrial Gears and Speed Reducers
LimiTorque Valve Controls



with Veelos on your machines...

v-belt replacement takes up to 90% less time

Actual in-plant records prove that Veelos v-belt can be installed *and operating* in up to 1/10th the time regularly needed to do the same job using endless v-belts.

Matched sets of Veelos are quickly made up in your own stockroom or at the machine by just coupling the correct lengths for the particular drive. Even outboard bearing drives are no problem. You *never* remove these outboard bearings, because Veelos is installed by simply coupling it around the shafts and running it onto the sheaves. And maintaining adequate stocks of Veelos is practically automatic. A quick check of the Veelos 100-foot reel will tell the inventory story.

For full vibrationless power delivery, for fast adjustability to keep sets matched, for ease of controlling inventory and for quick, simplified replacement — standardize on Veelos.



Have you seen this Veelos Facts Book?

Your Veelos v-belt distributor's salesman will be glad to give you a quick trip through this fact-packed, 36 page book. You'll find it well worth the few minutes it takes. Next time the salesman calls, ask him to show it to you.

VEELOS
THE LINK
V-BELT

Write for a copy of the VEELOS DATA BOOK. It's fully illustrated and packed with useful engineering data. We'll be glad to send a copy along and you'll be glad to have it!

MANHEIM MANUFACTURING AND BELTING COMPANY
613 Manbel St., Manheim, Pa.

ADJUSTABLE TO ANY LENGTH • ADAPTABLE TO ANY DRIVE

lt speed reaches a maximum of fpm.

Extended conveyor portion is nstructed with 2 x 2 x ⅛-inch gle iron for carrying the top llers. The truss is composed of -inch diameter rods and the en- e section is carried on twelve ¼-inch diameter flanged rollers. ction will retract automatically nen conveyor belt is allowed to n and latches are opened. A. B. urquhar Division, Oliver Corp., pt. ST, 142 N. Duke St., York, ..

R MORE DATA—CIRCLE REPLY CARD NO. 19

l Hydraulic Pumps

. meet variable delivery need

Line of variable delivery hydrau- pumps is suitable for open or osed hydraulic circuits. They are rticularly adapted to heavy ma- inery drives requiring precise rque control, acceleration and de-



leration, speed or reversal. Hy- aulic motors in the series are de- gned to reverse quickly under full ad and to run at extremely slow eeds under full torque.

Units are available in ten sizes th capacities 28 to 2300 gpm at ted speeds, and 50 to 4000 hp in 00 to 3000 psi pressure range. aterbury Tool, division of Vickers c., Dept. ST, Waterbury 20, Conn.

R MORE DATA—CIRCLE REPLY CARD NO. 20

crew Locking Insert

. . make threads in blind holes

A knurled insert is available for oviding threads in blind holes in l kinds of materials. It has a rge band of diamond knurling on grip area. Besides locking the rew, inserts require no special ols. Devices are made in a range sizes to accept screws from 4-40

high production

UNIFORM RESULTS

WHENEVER Surface ROTARY HEARTH FURNACES ARE USED

ANOTHER 'SURFACE' SOLUTION TO PRODUCTION PROBLEMS

It's in the records of many prominent companies with mass production schedules—versatile 'Surface' Rotary Hearth Furnaces measure up to the job with *profitable results.* The experience of Ross Gear & Tool Company, Lafayette, Ind. is typical. Here, the clean hardening of steering arms and lever shafts is required.

A 'Surface' Rotary Hearth Furnace equipped with radiant tubes and an RX prepared gas atmosphere does the job. Steering levers and shafts—*1,000 lbs. every hour*—are uniformly clean hardened. The furnace operates 24 hours a day, and during two years of continuous service, has never been down for repairs. Only one operator is required for the operation.

For controlled atmosphere or direct-fired heat treating processes, it will pay *real dividends* to check the outstanding advantages of 'Surface' Rotary Hearth Furnaces in your production picture.

Write today for bulletin and for the full story on Ross Gear & Tool Company's experience.

SURFACE COMBUSTION Corporation

TOLEDO 1, OHIO

'Surface' INDUSTRIAL FURNACES AND BURNERS

Kathabar HUMIDITY CONDITIONING SYSTEMS

Janitrol AUTOMATIC HEATING EQUIPMENT

Headquarters for

52100

Steel Tubing and Bars

Largest Stocks in the Country

of this versatile steel. 52100 is hard, tough and long-wearing, yet it's easy to machine and is right for bearings, sleeves, pins, collars and many other machine parts.

Over 200 seamless tube sizes to choose from .898" O.D. to 8.250" O.D. Bar sizes from .171" round to 7.5" round. Also ring forgings in any analysis.

Write for our Latest Stock List Now

New Headquarters of Peterson Steels, Inc., Union, New Jersey



PETERSON STEELS, INC.

DEPT. S, SPRINGFIELD ROAD
UNION, NEW JERSEY

Detroit, Mich. • Chicago, Ill.

NEW PRODUCTS and equipment

to 1/4-20. Brush Nail Expansion Bolt Co., Dept. ST, Greenwich, Conn.

FOR MORE DATA—CIRCLE REPLY CARD NO. 21

Chamfering, Deburring Machine

. . . 8 seconds per ring gear

All the teeth in a 14-inch diameter 156-tooth flywheel ring gear can be deburred and chamfered in 8 seconds by the model BM-2029 Burr-Master. A locating finger, moving with the cutting tools, automatically locates the gear teeth radially on each stroke of form-

type cutting tools. This compensates for any out-of-round condition or flatness variation.

When cutting cycle is complete, a cycle indicator light signals, and the operator ejects the gear. Design features include alloy bronze rocker arms, an overload clutch that prevents damage to machine parts in event of accidental overloads and precision indexing mechanism operating in oil bath. Modern Industrial Engineering Co., Dept. ST, 14230 Birwood Ave., Detroit 4, Mich.

FOR MORE DATA—CIRCLE REPLY CARD NO. 22

Adjustable Speed Drive

. . . offers stepless control

Simplified addition to the manufacturer's line of Thy-mo-trol packaged electronic adjustable-speed drives offers stepless speed control, close regulation and preset speed control. Drive is designed for use on such equipment as testing machines, conveyors, variable-volume pumps and machine tools. It is made ¾ to 3 hp drives.

Standard speed ranges are 5 to 1 and 20 to 1, in reversing and non-reversing forms. Dynamic brak-

STEEL PLATE WORK



TURBINE CASINGS and other heavy steel plate work are fabricated at Pusey-jones of Hot-Rolled, High-Strength, Low-Alloy Steel.

Every facility for large scale metal fabricating: — Heavy plate shop equipment — Rolls — Shears — Bending furnaces. Stress relieving furnace 33'x18'x16' up to 2100°F. Machine shop for facing, turning, and boring. 50 ton capacity gray iron foundry. Deep-water transportation on one side, the Pennsylvania RR on the other. Talk to our development engineers.

Metals Fabrication Division
THE PUSEY AND JONES CORP.
506 Front St., Wilmington, Del.
Established 1848

PUSEYJONES



There's a growing preference for ROLLWAY BEARINGS

...and with good reason!

Unwavering right-line rotation—free of skew, side-shock and end-rub—greatly extends the life expectancy of a Rollway Roller Bearing. Add to longer life the definite gains in smoother operation and lower maintenance costs and it's understandable why, today, demand for Rollways has reached a new peak.

Our increased facilities are expanding Rollway output as fast as possible. We are continuing to improve the balance between supply and demand, so that service to both established and new customers will be geared to their quantity requirements . . . another reason why bearing users can confidently specify "The bearings that *roll* right because they're *made* right."

Our complete engineering and metallurgical services will gladly work with you on your problems. Simply write or wire any sales office. No cost. No obligation.

Rollway Bearing replacements are available through authorized bearing distributors in principal cities. Consult your classified 'phone directory.

ROLLWAY BEARING CO., INC.
SYRACUSE 4, N. Y.

RIGHT ANGLE

ROLLER ENDS, precisely square to avoid end-rub, oscillation and side-shock.



RIGHT ANGLE

BEARING SURFACES with parallelism that results in unwavering right-line rolling.



RIGHT ANGLE

SEPARATOR SLOTS accurately machined to prevent roller skew, slide and uneven wear.



SALES OFFICES

Syracuse	Chicago
Cleveland	Pittsburgh
Houston	Detroit
Boston	Los Angeles
Philadelphia	Toronto

ROLLWAY BEARINGS

Complete Line of Radial and Thrust Cylindrical Roller Bearings



ENJOY ECONOMICAL TWO-WAY VENTILATION WITH BURT FREE-FLOW FAN VENTILATORS

Many structures do not require full time power ventilation. For them, Burt's Free-Flow Fan Ventilator is both economical and efficient because it supplies all normal exhaust needs by gravity. But, when greater exhaust is required, its Axial Flow Burt Airfoil Fan accelerates almost six times the removal of extra heat and impurities. It provides positive controlled ventilation. See Sweet's for further details or write for Bulletin SPV-10A.

FAN & GRAVITY VENTILATORS • LOUVERS • SHEET METAL SPECIALTIES

The Burt Manufacturing Company

905 So. High St. Akron II, Ohio

ing, standard overload and undervoltage protection are two of the features included that are found on the firm's larger systems. Wide

speed range selection is accomplished by turning a single knob. General Electric Co., Dept. ST, Schenectady 5, N. Y.

FOR MORE DATA—CIRCLE REPLY CARD NO. 23

Plating Processes

. . . use no nickel

Two decorative plating processes have been developed for use on parts commonly having a copper-nickel chrome finish. No nickel is used in the process. Designated as Probrite CR-723, both finishes can be deposited over steel or copper. Parts can be color buffed after plating. Promat Division, Poor & Co., Dept. ST, 851 S. Market St., Waukegan, Ill.

FOR MORE DATA—CIRCLE REPLY CARD NO. 24

Automatic Sheet Lubricator

. . . speeds metal forming

This machine applies lubricants automatically to sheets and blanks, using the company's dry lubricant to reduce stock preparation costs and speed production in many met-



al forming operations. Material can be processed at speeds up to 55 fpm.

The machine includes three sep-

TOUGH, highly uniform and economical to use, 20th Century *Normalized shot and grit is right on the mark in hundreds of foundries and metal-working plants. Close laboratory control and modern production methods assure the high quality of this metallic abrasive. It lasts three times longer than conventional shot and grit.
One of the world's largest producers of quality shot, grit and powder—Hard Iron—Normalized—Cut Wire.
Write for our new catalog.
*Copyrighted trade name.
THE CLEVELAND Metal Abrasive CO.
802 East 67th Street Cleveland 8, Ohio
Howell Works: Howell, Michigan
20th Century
the persuasive abrasive



why design yourself into
co$tly
fa$tener$?

...when the **M**ilford **M**ethod may save you thousands of dollars in costly fasteners and assembly!

ask about the Milford Method



This scientific approach to product and parts assembly is a fastener-engineering consulting service which analyzes your needs at the blueprint stage...before you invest in expensive tools and dies! It projects for you the right fastener. Look into the economies of the "MILFORD METHOD" now. Send your blueprints and samples for analysis and planning by the "MILFORD METHOD", or write for the "Milford Method" brochure today.

the MILFORD RIVET & MACHINE CO.
EST. 1919

MILFORD, the name to rivet in your memory for fasteners.

931 Bridgeport Ave., Milford, Conn.
880 Illinois Ave., Aurora, Ill.
1160 W. River St., Elyria, Ohio
80 Plain Street, Hatboro, Penn.
757 So. Palm Ave., Alhambra, Calif.

arate units. In the first, sheets or blanks are cleaned. Stock then enters a self-contained coater with solution tanks that can handle blanks up to 48 inches wide. In the last stage, the stock is run through a drying element available with steam, gas or electrically-heated ovens. Gilron Products Co., Dept. ST, 6007 Euclid Ave., Cleveland 3, O.

FOR MORE DATA—CIRCLE REPLY CARD NO. 25

Suspension-Type Cutter

. . . provides 150 tons thrust

Suspension cutter, Guillotine model 25-EE, combines 150-ton thrust with relative mobility. The model will cut up to 2¾-inch diameter steel rod in 13 seconds. It is



also adaptable for riveting 1-inch cold rivets and for punching and pressing.

Two electric hydraulic pumps mounted in tandem produce the 150-ton thrust. The unit provides a 360-degree swivel. Cutting head weighs 470 pounds. Manco Mfg. Co., Dept. ST, Bradley, Ill.

FOR MORE DATA—CIRCLE REPLY CARD NO. 26

Screw Drivers

. . . blades from 12 to 1¼ inches

A line of screw drivers consists of patterns in round blades, square blades, Phillips style and stubbies. Blades are made of SAE chrome

USE A
REPLY CARD
Just circle the corresponding number of any item in this section for more information.

NFORMATION

AVAILABLE FOR THE ASKING

6 Heavy Duty Drill

urt Orban Co. — Specifications design features of German-made el BK-25 Alfing heavy duty drill s are contained in 4-page illus- ed folder. Drilling capacity is 1 n mild steel, and spindle speed e is 150 to 1640 rpm.

7 Dust Collection

merican Air Filter Co.—Reprint aper "Operation, Application and ctiveness of Dust Collection pment" contains charts on costs quipment, range of particle sizes lled, concentrations, collector per- ances, list of practical "don'ts" data on selection, installation and ation.

7 Lift Truck Scales

artin-Decker Corp.—Description specifications of scales for de- ining the weight of loads on any raulic type lift truck are con- ed in this 2-page illustrated data t. Weight of each load is read tly. Models range from 2000 to 00 lb capacity.

7 Piston Balancing Machine

orris Machine Tool Co.—How the ris automatic piston balancing hine works is described in 6- e illustrated brochure No. 60 PB. es of photographs shows opera- and close-up of various machine ponents. Specs are given.

7 Walkie Type Trucks

oto-Truc Co.—Design features, ifications and illustrations of ous models of battery operated tie type trucks are found in 6- e bulletin No. 51. You'll never w there are so many different s for various uses until you read

7 Metallizing

etallizing Co. of America—"Mo- Metallizing Gun" is title of 20- e illustrated booklet which dis- es the use of this equipment for protection against corrosion, rebuilding worn parts and correcting mismachined products. Available metallizing gun models, auxiliary equipment, application techniques, case studies and related information are presented.

75. Ball Transfers

Mathews Conveyer Co.—General and specific data on construction and use of ball transfers is presented in 4-page folder BT 52. Transfers facilitate moving materials horizontally in any direction.

76. Pipe & Tube Straightening

Mackintosh-Hempill Co. — Production experience records on straightening pipe and tubing in seven different plants are cited in technical bulletin 52. This 8-page illustrated booklet shows, in case study form, variety of methods and equipment for rotary straightening work.

77. Rectifier Welders

Miller Electric Mfg. Co.—Specifications for four models of Miller selenium rectifier direct current type welders are presented in this 4-page folder. Possible fields of application are outlined.

78. Rotating Parts Tester

Warren Brothers Roads Co., Mfg. Div.—Spintesting, the rotation of a part at high speeds to check mechanical perfection and vibration characteristics, is described and equipment for it illustrated in 4-page bulletin. Three models are covered, specs given and turbine rotor testing is outlined.

79. Magnesium Dockboards

Magnesium Co. of America—How light weight-heavy duty magnesium dockboards can speed and make safe loading and unloading at the shipping dock is shown in this 4-page illustrated folder. Ten photographs show them in action. The ramp-dockboard combination is described.

STEEL 3-9-53

Penton Building, Cleveland 13, Ohio

Please send literature or detailed information on subjects circled at left to—

NAME _____ TITLE _____

COMPANY _____

PRODUCTS MANUFACTURED _____

ADDRESS _____

CITY AND STATE _____

This card MUST be completely filled out. Please TYPE or PRINT

1	11	21	31	41	51	61	71	81
2	12	22	32	42	52	62	72	82
3	13	23	33	43	53	63	73	83
4	14	24	34	44	54	64	74	84
5	15	25	35	45	55	65	75	85
6	16	26	36	46	56	66	76	86
7	17	27	37	47	57	67	77	87
8	18	28	38	48	58	68	78	88
9	19	29	39	49	59	69	79	89
10	20	30	40	50	60	70	80	90

FIRST CLASS
Permit No. 36
(Sec. 34.9 P.L.&R.)
CLEVELAND, OHIO

BUSINESS REPLY CARD

No Postage Stamp Necessary if Mailed in the United States

— POSTAGE WILL BE PAID BY —

STEEL
Penton Building
Cleveland 13, Ohio

Readers Service Dept.

80. Surface Roughness

Micrometrical Mfg. Co.—"How To Specify Surface Roughness — and Why" is title of 4-page illustrated bulletin L21. It explains the term "surface roughness" as applied to machines and finished surfaces, and describes the practical advantages of surface roughness specification. How to establish such specs, how to specify them on drawings and other data are included.

81. Portable Tachometers

Metron Instrument Co.—Technical data sheet 48HJK deals with accurate portable tachometers for speed measurements in range of 36 to 100,000 rpm or similar units. Accuracy is within 0.25 per cent full scale.

82. Sheet Steel Separator

Basco Mfg. Co.—Sizes of magnetic sheet steel separators described and shown in 2-page bulletin include a three-high heavy duty unit and a smaller two-high unit. Height, width, number of magnets and maximum stack height are covered. Units speed sheet and strip feeding to presses.

83. Vertical Enclosed Motor

U. S. Electrical Motors Inc.—Users of deep well turbine pumps will find many interesting developments in vertical motor design outlined in 16-page illustrated bulletin "Vertiosed Motors." Offered in sizes from 1½ to 400 hp, these motors a available in wide range of enclosu for all types of service, includi hazardous.

84. Air Cylinders

Miller Motor Co.—Engineering, sign, construction and mounting da on cushioned and noncushion single and double acting, single a double rod end, spring return a over-sized rod air cylinders is fered in 8-page bulletin A-105 Thirteen different mounting styles 1½ through 14-in. bores are draw

85. Sealed Mercury Switches

Minneapolis - Honeywell Regulat Co., Micro Div.—Features, uses a available types of Honeywell m cury switches are subject of regul publication "Mercury Pool". T tailed in first issue is the new plas embedded mercury switch which sures ample protection for glass t element of control. Actual applic tions are described.

86. Dust Control

Dracco Corp.—Equipment for recovery or control of dust resulti from various plant operations processes is fully described and ill trated in 40-page bulletin No. 8 Machinery's operation and featu are shown as well as numerous stallations. You can analyze dust problem in your specific ope tion with the help of this booklet

EDITORIAL REPRINTS:

87. Carbide Cutters

Purchasing only the cemented carbide tips, Solar Aircraft Co. of San Diego, Calif., mills, brazes and sharpens its own tools. Savings amount to as much as $50,000 a year. The story is in STEEL reprint "Carbide Cutters: Made and Maintained at Home," by M. S. Schlegel, company's chief tool engineer.

88. Instrument Testing

Shock, harmonic vibration, tumbling, temperature, moisture and waterproof tests, as well as electrical checking are among the rigors devised at Weston Electrical Instrument Corp. to test the stamina of their electrical instruments for meeting military specs. They're described in STEEL reprint "Electrical Instruments Can Take It."

89. Standardization Trend

Industry - military cooperat which was evident during World W II continues to work today to ma defense efforts more productive. standardization trend advances, evidenced by the recent cross-ind ing of chemically equivalent spec cations. More will come. R STEEL reprint "Teamwork Smoo out Specification Troubles."

90. Barrel Plating

Three automatic barrel machi form the backbone of the zinc p ing line at Ford's River Rouge pl Special handling equipment redu handling needs and permits an put of 3000 lb of parts an hour machine. STEEL reprint "St Parts Barrel Through Plating" H. Chase tells the story.

1	11	21	31	41	51	61	71	81
2	12	22	32	42	52	62	72	82
3	13	23	33	43	53	63	73	83
4	14	24	34	44	54	64	74	84
5	15	25	35	45	55	65	75	85
6	16	26	36	46	56	66	76	86
7	17	27	37	47	57	67	77	87
8	18	28	38	48	58	68	78	88
9	19	29	39	49	59	69	79	89
10	20	30	40	50	60	70	80	90

STEEL
Penton Building, Cleveland 13, Ohio

3-9-53

Please send literature or detailed information on subjects circled at left to—

NAME _____ TITLE _____

COMPANY _____

PRODUCTS MANUFACTURED _____

ADDRESS _____

CITY AND STATE _____

This card MUST be completely filled out. Please TYPE or PRINT

BUSINESS REPLY CARD

No Postage Stamp Necessary if Mailed in the United States

POSTAGE WILL BE PAID BY—

STEEL
Penton Building
Cleveland 13, Ohio

FIRST CLASS
Permit No. 36
(Sec. 34.9 P.L.&R.)
CLEVELAND, OHIO

Readers Service Dept

anadium electric furnace steel. lade lengths range from 12 to 1¼ ches. Utica Drop Forge & Tool orp., Dept. ST, Utica, N. Y.

R MORE DATA—CIRCLE REPLY CARD NO. 27

lultiple-Head Tapper

. . lead screw protection

Multiple tapping of two or more nall holes can be done with lead rew protection on any drill press ith this self-contained lead screw ultiple tapping unit. Work can



done even though tap sizes, tches, or both, are dissimilar.

The unit consists of a reversing ead, a three-spindle multiple head nd a fixture. It taps two 0-80 oles in aluminum. The lead screw, aving a fast pitch, runs slower han the taps and is completely enosed during operation. Ettco ool Co. Inc., Dept. ST, 594 Johnon Ave., Brooklyn 37, N. Y.

R MORE DATA—CIRCLE REPLY CARD NO. 28

lastic Coating

. . protects and identifies

Insulcolor is a plastic coating for e as both protection and color entification on insulated refrigerat, cold water, steam and other nes and insulated equipment. It ill withstand temperatures to 160° without cracking, shrinking or azing. Armstrong Cork Co., Dept. T, Lancaster, Pa.

R MORE DATA—CIRCLE REPLY CARD NO. 29

USE A REPLY CARD

Just circle the corresponding number of any item in this section for more information.

for a fabulous finish...

JEWEL BRAND Abrasive Belts

for grinding, sanding, polishing — metal, wood, leather, plastics, rubber

ABRASIVE PRODUCTS, INC.
511 Pearl Street
South Braintree 85, Massachusetts

Which Office Sir!



CONSULT OUR NEAREST OFFICE FOR THE PURCHASE AND SALE OF SCRAP

LURIA BROTHERS AND COMPANY, INC.

MAIN OFFICE
LINCOLN-LIBERTY BLDG.
Philadelphia 7, Penna.

PLANTS
LEBANON, PENNA. DETROIT (ECORSE), MICHIGAN
READING, PENNA.
MODENA, PENNA. PITTSBURGH, PENNA.
ERIE, PENNA

OFFICES

BIRMINGHAM, ALA.	DETROIT, MICH.	PITTSBURGH, PENNA.
BOSTON, MASS.	HOUSTON, TEXAS	PUEBLO, COLORADO
BUFFALO, N. Y.	LEBANON, PENNA.	READING, PENNA.
CHICAGO, ILLINOIS	LOS ANGELES, CAL.	ST. LOUIS, MO.
CLEVELAND, OHIO	NEW YORK, N. Y.	SAN FRANCISCO, CAL.
	SEATTLE, WASH.	

LEADERS IN IRON AND STEEL SCRAP SINCE 1889

The Market Outlook

THERE'S more of a peacetime look in the steel market now than there has been for a long time.

You can tell that from the way demand for light, flat-rolled steel is moving ahead of demand for the forms of steel, such as large bars and heavy plates, customarily in heavy need during war periods.

THE SCORE—This shouldn't be interpreted as any diminution in demand for steel for war and defense purposes. What's happening is this: Defense demand is remaining constant while demand for civilian usage is swelling.

This development became possible largely from the stabilizing of the defense program and the substantial increase in the steel industry's production capacity. Had the steel industry not increased its capacity in the last three years there would be little room for thinking in terms of additional steel for civilian purposes.

UPSURGE—Now that the government has open-ended the Controlled Materials Plan and is considering further decontrols for steel, various civilian goods industries, particularly the automobile producers, are upping their production schedules. Result: An upsurge in demand for the light, flat-rolled forms of steel that are characteristic in civilian goods.

STIMULATED—The intensified demand from producers of civilan goods is having a pronounced effect not only on major grades of hot-rolled and cold-rolled carbon sheets but also on enameling sheets and electrical sheets, such as are used in household appliances. About the only major sheet item not moving rapidly is galvanized sheets, particularly in the lighter gages, 24 to 28.

Reflecting the stronger tone in civilian durable goods, foundries are operating at higher levels to supply the needed castings. Iron supply for these foundries should remain adequate.

THOUGHTS ON DECONTROL—In preparation for further decontrol of the distribution of steel, government agencies were concerned last week with devising a system for giving priority to defense requirements after June 30, when the present controls are to expire. Under consideration were three systems: 1. A simple DO (defense order) rating band. 2. A little CMP. 3. A programming setup in which task forces from the steel, copper and aluminum industries would confer with the armed services, Atomic Energy Commission and other qualified claimants to ascertain requirements and parcel them out on the basis of capacity relationships of the various producers.

As these systems were being studied, it became known that Russian Premier Joseph Stalin was gravely ill and passing from actively heading the Russian state. First reaction was that there would be no relaxation in the United States defense effort but that decontrol would continue to shape up in accordance with earlier thinking.

RECORD BREAKING—The heavy steel production that is helping make decontrol possible pushed up to a record high in the week ended Mar. 7. It hit 101 per cent of capacity, and with capacity at an all-time high the yield was the greatest ever attained—2,277,000 net tons of steel for ingots and castings. The preceding week's rate was 100.5 per cent. The 101 per cent rate gives the long month of March a good start toward setting an all-time monthly high record of steel ingot production.

PRICES CUT—Even though demand for the major grades of steel is intense, the return of peacetime characteristics in the steel market is bringing an occasional price reduction. In the Boston area, competition forced leading producers to make a 10 per cent cut in prices of smaller sizes of electric welded carbon steel tubing.

Many buyers of steel are becoming increasingly selective. They're not taking steel just because it is available. With increasing frequence they're insisting on getting just what they want and are refusing alternates. For instance, some consumers who need fairly heavy and wide plate are declining offers of narrower and lighter plate that comes from strip mills.

NATIONAL STEELWORKS OPERATIONS



DISTRICT INGOT RATES

Percentage of Capacity Engaged at Leading Production Points

	Week Ended Mar. 7	Change	Same Week 1952	Same Week 1951
Pittsburgh	106.5	+ .5	103.5	101
Chicago	102.5†	— .5*	103	105.5
Mid-Atlantic	96†	+ 1	98	99.5
Youngstown	107	+ 1	105	106
Wheeling	101†	0	100	96
Cleveland	103†	0	98.5	103
Buffalo	106.5	0	104	104
Birmingham	98	0	104	78
New England	85†	— 4	90	90
Cincinnati	101†	+ 5.5	92	102
St. Louis	96	+ 2	79	95
Detroit	105.2	+ .6	102	108
Western	110.5	+ 1.5	103	103.5
Estimated national rate	101	+ .5	101.5	101

*Change from preceding week's revised rate.
†Estimated rates are based on Jan. 1, 1953, capacities; others on Jan. 1, 1952 capacities.
Weekly steelmaking capacity is estimated at 2,254,459 net tons in 1953; 2,077,040 tons in 1952; 1,999,034 tons in 1951.

Composite Market Averages

FINISHED STEEL PRICE INDEX: Bureau of Labor Statistics	Mar. 3 1953	Feb. 24 1953	Month Ago	February Average
(1947-1949=100)	130.5	130.5	130.6	130.5

AVERAGE PRICES (BUREAU OF LABOR STATISTICS)
Week Ended Mar. 3, 1953

Units are 100 lb except where otherwise noted below in parentheses. For complete description of products see insert following p. 28, STEEL, Sept. 8, 1952.

Rails	$3.775	Sheets, C.R. carbon	$5.275
Tracks spikes	6.650	Sheets, galv.	6.765
Track bolts	9.958	Strip, C.R. carbon	5.100
Tie plates	4.775	Strip, C.R. stainless (lb)	0.325
Joint bars	4.925	Pipe, black, buttweld (100 ft).	7.090
Plates, carbon	4.150	Pipe, galv., buttweld (100 ft).	8.778
Structural shapes	4.200	Boiler tubes (100 ft)	31.663
Bars, tool steel (lb)	1.576	Tin plate (100 lb base box)	8.950
Bars, 3120 alloy	6.575	Terne plate (100 lb base box).	7.750
Bars, stainless (lb)	0.149	Wire, carbon, merchant	6.075
Bars, carbon	4.100	Wire, fence, galv.	6.425
Bars, reinforcing	4.050	Nails (100 lb kegs)	7.410
Bars, C.F. carbon	5.925	Wire, barbed (80 rod spool)	5.880
Sheets, H.R. carbon	4.125	Woven wire fence (20 rod roll)	13.629

FINISHED PRICE INDEX, Weighted:

Calculated by STEEL*	Mar. 5 1953	Week Ago	Month Ago	Year Ago	5 Yrs. Ago
Index (1935-39 av.=100)	181.31	181.31	181.31	171.92	134.56
Index in cents per lb.	4.912	4.912	4.912	4.657	3.645

ARITHMETICAL PRICE COMPOSITES:

Calculated by STEEL*					
Finished Steel NT	$110.98	$110.98	$110.98	$106.32	$81.136
No. 2 Fdry, Pig Iron, GT.	55.04	55.04	55.04	52.54	39.84
Basic Pig Iron, GT.	54.66	54.66	54.66	52.16	39.376
Malleable Pig Iron, GT	55.77	55.77	55.77	53.27	40.48
Steelmaking Scrap, GT.	43.00	43.00	43.00	43.00	40.17

* For explanation of weighted index see STEEL, Sept. 19, 1949, p. 54; of arithmetical price composites, STEEL, Sept. 1, 1952, p. 130.

Comparison of Prices

Comparative prices by districts, in cents per pound except as otherwise noted. Delivered prices based on nearest production point.

FINISHED MATERIALS	Mar. 5 1953	Week Ago	Month Ago	Year Ago	5 Yrs. Ago
Bars, H.R., Pittsburgh	3.95	3.95	3.95	3.70	2.90
Bars, H.R., Chicago	3.95	3.95	3.95	3.70	2.90
Bars, H.R., del Philadelphia	4.502	4.502	4.502	4.223	3.356
Bars, C.F., Pittsburgh	4.925	4.925	4.925	4.55	3.55
Shapes, Std., Pittsburgh	3.85	3.85	3.85	3.65	2.80
Shapes, Std., Chicago	3.85	3.85	3.85	3.65	2.80
Shapes, del., Philadelphia	4.13	4.13	4.13	3.918	2.968
Plates, Pittsburgh	3.90	3.90	3.90	3.70	2.95
Plates, Chicago	3.90	3.90	3.90	3.70	2.95
Plates, Coatesville, Pa.	4.35	4.35	4.35	4.15	3.45
Plates, Sparrows Point, Md.	3.90	3.90	3.90	3.70	2.95
Plates, Claymont, Del.	4.35	4.35	4.35	4.15	3.65
Sheets, H.R., Pittsburgh	3.775	3.775	3.775	3.60-75	2.80
Sheets, H.R., Chicago	3.775	3.775	3.775	3.60	2.80
Sheets, C.R., Pittsburgh	4.575	4.575	4.575	4.35	3.55
Sheets, C.R., Chicago	4.575	4.575	4.575	4.35	3.55
Sheets, C.R., Detroit	4.775	4.775	4.775	4.55	3.71
Sheets, Galv., Pittsburgh	5.075	5.075	5.075	4.80	3.95
Strip, H.R., Pitts.	3.975-4.225	3.975-4.225	3.975-4.225	3.75-4.00	3.05
Strip, H.R., Chicago	3.725	3.725	3.725	3.50	3.05
Strip, C.R., Pittsburgh	5.10-5.80	5.10-5.80	5.10-5.80	4.65-5.35	3.80
Strip, C.R., Chicago	5.35	5.35	5.35	4.90	3.85
Strip, C.R., Detroit	5.30-6.05	5.30-6.05	5.30-6.05	4.85-5.60	3.71
Wire, Basic, Pitts.	5.475-5.225	5.475-5.225	5.475-5.225	4.85-5.10	3.775
Nails, Wire, Pittsburgh	6.35	6.35	6.35	5.90-6.20	5.20
Tin plate box, Pittsburgh	$8.95	$8.95	$8.95	$8.70	$6.70
SEMIFINISHED					
Billets, forging, Pitts. (NT)	$70.50	$70.50	$70.50	$66.00	$54.00
Wire rods, ⅞-⅜", Pitts.	4.425	4.425	4.425	4.10-30	3.175
PIG IRON, Gross Ton					
Bessemer, Pitts.	$55.50	$55.50	$55.50	$53.00	$40.996
Basic Valley	54.50	54.50	54.50	52.00	39.00
Basic, del. Phila.	59.25	59.25	59.25	56.61	42.004
No. 2 Fdry, Pitts.	55.00	55.00	55.00	52.50	40.496
No. 2 Fdry, Chicago	55.00	55.00	55.00	52.50	39.00
No. 2 Fdry, Valley	55.00	55.00	55.00	52.50	39.50
No. 2 Fdry, del. Phila.	59.75	59.75	59.75	57.11	42.504
No. 2 Fdry, Birm.	51.38	51.38	51.38	48.88	37.88
No. 2 Fdry (Birm.) del. Cin.	58.93	58.93	58.93	55.49	40.74
Malleable, Valley	55.00	55.00	55.00	52.50	39.50
Malleable, Chicago	55.00	55.00	55.00	52.50	39.50
Charcoal, Lyles, Tenn.	68.50	68.50	68.50	66.00	55.00
Ferromanganese, Etna, Pa.	228.00	228.00	228.00	188.00	151.00*

* F.o.b. cars, Pittsburgh.

SCRAP, Gross Ton (including broker's commission)

No. 1 Heavy Melt, Pitts.	$44.00	$44.00	$44.00	$44.00	$40.25
No. 1 Heavy Melt, E. Pa.	48.50	41.50	41.50	42.50	39.00
No. 1 Heavy Melt, Chicago	42.50	42.50	42.50	42.50	38.75
No. 1 Heavy Melt, Valley	45.25	45.25	44.00	44.00	40.25
No. 1 Heavy Melt, Cleve.	44.25	44.25	43.00	43.00	39.75
No. 1 Heavy Melt, Buffalo	42.75	42.75	43.00	43.00	44.00
Rails, Rerolling, Chicago	52.50	52.50	52.50	52.50	49.75
No. 1 Cast, Chicago	43.00	43.00	43.00	49.00†	66.00

† F.o.b. shipping point.

COKE, Net Ton

Beehive, Furn, Connlsvl.	$14.75	$14.75	$14.75	$14.75	$12.50
Beehive, Fdry, Connlsvl.	17.00	17.00	17.00	17.50	14.875
Oven Fdry, Chicago	24.50	24.50	24.50	23.00	19.25

PIG IRON

F.o.b. furnace prices quoted under GCPR as reported to STEEL. Minimum delivered prices are approximate and do not include 3% federal tax. Key to producing companies published on second following page.

PIG IRON, Gross Ton	Basic	No. 2 Foundry	Malleable	Bessemer
Bethlehem,Pa. B2	$56.50	$57.00	$57.50	$58.00
NewYork, del.	....	60.78	61.28	....
Newark, del.	59.52	60.02	60.52	61.02
Philadelphia, del.	59.25	59.75	60.25	60.75
Birmingham District				
AlabamaCity,Ala. R2	50.88	51.38	....	....
Birmingham R2	50.88	51.38	....	....
Birmingham S9	....	51.38	....	....
Woodward,Ala. W15	50.88	51.38	....	....
Cincinnati, del.	....	58.93	....	....
Buffalo District				
Buffalo R2	54.50	55.00	55.50	....
Buffalo H1	54.50	55.00	55.50	....
Tonawanda,N.Y. W12	54.50	55.00	55.50	....
No.Tonawanda,N.Y. T9	....	55.00	55.50	....
Boston, del.	65.15	65.65	66.15	....
Rochester,N.Y., del.	57.52	58.02	58.52	....
Syracuse,N.Y. del.	58.62	59.12	59.62	....
Chicago District				
Chicago I-3	54.50	55.00	55.00	55.50
Gary,Ind. U5	54.50	....	55.00	....
IndianaHarbor,Ind. I-2	54.50	....	55.00	....
So.Chicago,Ill. W14	54.50	55.00	55.00	....
So.Chicago,Ill. Y1	54.50	55.00	55.00	....
So.Chicago,Ill. U5	54.50	....	55.00	55.50
Milwaukee, del.	56.67	57.17	57.17	57.67
Muskegon,Mich., del.	....	61.30	61.30	....
Cleveland District				
Cleveland A7	54.50	55.00	55.00	55.50
Cleveland R2	54.50	55.00	55.00	....
Akron,O., del. from Cleve.	57.11	57.61	57.61	58.11
Lorain,O. N3	54.50	....	....	55.50
Duluth I-3	....	....	55.00	....
Erie,Pa. I-3	54.50	55.00	55.00	55.50
Everett,Mass. E1	....	59.50	60.00	....
Fontana,Calif. K1	60.50	61.00	....	....
GraniteCity,Ill. G4	56.40	56.90	57.40	....
St.Louis, del. (inc. tax)	57.15	57.65	58.15	....
Ironton,Utah C11	54.50	55.00	....	....
Geneva,Utah C11	54.50	55.00	....	....
LoneStar,Tex. L6	50.50	*51.00	51.00	....
Minnequa,Colo. C10	56.50	57.50	57.50	....
Rockwood,Tenn. T3	....	....	58.50	....
Pittsburgh District				
NevilleIsland,Pa. P6	....	55.00	55.00	55.50
Pitts., N.&S. sides, Ambridge				
Aliquippa, del.	....	56.37	56.37	56.87
McKeesRocks, del.	....	56.04	56.04	56.54
Lawrenceville, Homestead,				
Wilmerding, Monaca, del.	....	56.66	56.66	57.16
Verona, Trafford, del.	....	57.19	57.19	57.69
Brackenridge, del.	....	57.45	57.45	57.95
Bessemer,Pa. U5	54.50	....	55.00	55.50
Clairton,Rankin,So.Duquesne,Pa. U5	54.50	....	....	....
McKeesport,Pa. N3	54.50	....	....	55.50
Monessen,Pa. P7	56.50	....	....	....
Sharpsville,Pa. S6	....	....	55.00	55.50
Steelton,Pa. B2	56.50	57.00	57.50	58.00
Swedeland,Pa. A3	58.50	59.00	59.50	60.00
Toledo,O. I-3	54.50	55.00	55.00	55.50
Cincinnati, del.	59.97	60.47	....	....
Troy,N.Y. R2	56.50	57.00	57.50	58.00
Youngstown District				
Hubbard,O. Y1	54.50	55.00	55.00	....
Youngstown Y1	54.50	55.00	55.00	....
Youngstown U5	54.50	....	....	55.50
Mansfield,O., del.	59.15	59.65	59.65	60.15

* Low phos, southern grade.

PIG IRON DIFFERENTIALS

Silicon: Add 50 cents per ton for each 0.25% Si or percentage thereof over base grade, 1.75-2.25%, except on low phos iron on which base is 1.75-2.00%.

Phosphorus: Deduct 38 cents per ton for P content of 0.70% and over.

Manganese: Add 50 cents per ton for each 0.50% manganese over 1% or portion thereof.

Nickel: Under 0.50% no extra; 0.50-0.74%, incl., add $2 per ton; each additional 0.25%, add $1 per ton.

BLAST FURNACE SILVERY PIG IRON, Gross Ton

(Base 6.0-6.50% silicon; add $1.50 for each 0.5% Si)

Jackson,O. G2 J1	$6
Buffalo H1	6

ELECTRIC FURNACE SILVERY PIG IRON, Gross Ton

(Base 14.01-14.50% silicon; add $1 for each 0.5% Si to 18%; $1 each 0.5% Mn over 1%; $2 per gross ton premium for 0.045% max

NiagaraFalls,N.Y. P15	$9
Keokuk,Iowa, Openhearth & Fdry, frt. allowed K2	9
Keokuk, OH & Fdry., 12½ lb piglets, 16% Si, frt. allowed K2	9
Wenatchee, Wash., OH & Fdry., frt. allowed K2	9

CHARCOAL PIG IRON, Gross Ton

(Low phos semi-cold blast; differential charged for silicon over base grade; also for hard chilling iron Nos. 5 & 6)

Lyles,Tenn. T3	$6

LOW PHOSPHORUS PIG IRON, Gross Ton

Cleveland, intermediate, A7	$
Steelton,Pa. B2	
Philadelphia, delivered	
Troy,N.Y. R2	

(Material in this department is protected by copyright and its use in any form without permission is prohibited)

Semifinished and Finished Steel Products

Mill prices quoted under GCPR as reported to STEEL, Mar. 5, 1953, cents per pound except as otherwise noted. Changes shown in italics
Code numbers following mill points indicate producing company; key on next two pages.

TS, Carbon, Forging (NT)
ana,Calif. K1 ....$81.00
nall,Pa. U5 .....54.00
le S24 .....75.00

TS, Alloy (NT)
oit R7 .....$57.00
ana,Calif. K1 ....83.00
ton S5 .....65.00
and,Pa. C18 .....57.00
nall,Pa. U5 .....57.00

TS, BLOOMS & SLABS
rbon, Rerolling (NT)
emer,Pa. U5 ....$59.00
rtonPa. U5 .....59.00
ey,Ala. T2 .....59.00
field,Ala. T2 .....59.00
ana,Calif. K1 ....78.00
,Ind. U5 .....59.00
stown,Pa. B2 ....59.00
awanna,N.Y. B2 ..59.00
nall,Pa. U5 .....59.00
hicago,Ill. U5 ....59.00
quesne,Pa. U5 ..59.00

Carbon, Forging (NT)
emer,Pa. U5 ....$70.50
alo R2 .....70.50
on,O. R2 .....70.50
ton,Pa. U5 .....70.50
land R2 .....70.50
hohocken,Pa. A3 ..77.50
oit R7 .....73.50
y,Ala. T2 .....70.50
field,Ala. T2 .....70.50
ana,Calif. K1 ....89.50
Ind. U5 .....70.50
ra,Utah C11 .....70.50
ton S5 .....78.50
stown,Pa. B2 ....70.50
awannaN.Y. B2 ..70.50
ngeles B3 .....89.50
hall, Pa. U5 .....70.50
tle B3 .....89.50
hicago R2,U5,W14..70.50
quesne,Pa. U5 ..70.50
anFrancisco B3 ...89.50

Alloy, Forging (NT)
lehem,Pa. B2 ....76.00
alo R2 .....76.00
on, O. R2 .....76.00
on,O. T7 .....78.60
hohocken,Pa. A3 ..83.00
oit R7 .....79.00
ana,Calif. K1 ....95.00
Ind. U5 .....76.00
ton S5 .....84.00
Harbor,Ind. Y1 ....76.00
stown,Pa. B2 .....76.00
awanna,N.Y. B2..76.00
ngeles B3 .....96.00
sillon,O. R2 .....76.00
and,Pa. C18 .....76.00
hall,Pa. U5 .....76.00
hicago R2,U5,W14..76.00
quesne,Pa. U5 ..76.00
thers,O. Y1 .....76.00
ren,O. C17 .....76.00

NDS, SEAMLESS TUBE (NT)
alo R2 .....87.50
on,O. R2 .....87.50
eland R2 .....87.50
ana,Calif. K1 ....108.50
Ind. U5 .....87.50
sillon,O. R2 .....87.50
hicago,Ill. R2 ....87.50
quesne,Pa. U5 ..87.50

T BARS (NT)
ana,Calif. K1 ...93.18

P
uippa,Pa. J5 .....3.65
hall,Pa. U5 .....3.55
ren,O. R2 .....3.55
gstown R2 U5 ....3.55

RODS
n,Ill L1 .....4.70
amaCity,Ala. R2 ..4.325
alo W12 .....4.325
eland A7 .....4.325
ora,Pa. A7 .....4.325
field,Ala. T2 .....4.325
ana,Calif. K1 ....5.125
ston S5 .....4.725
stown,Pa. B2 ....4.325
t.Ill A7 .....4.325
asCity,Mo. S5 ...4.665
ngeles B3 .....5.125
nequa,Colo. C10 ...4.575
ssen,Pa. P7 .....4.525
onowanda,N.Y.B11 4.325
burg,Calif. C11 ...4.975
smouth,O. P12 ....4.525
ling,N.J. R5 .....4.425
hicago,Ill. R2 .....4.325
rowsPoint,Md. B2..4.425
ing,Ill.(1) N15 ....4.325
thers,O. Y1 .....4.325
ance,Calif. C11 ...5.125
ester,Mass. A7 ...4.625

T STEEL PILING
Harbor,Ind. I-2 ...4.675
awanna,N.Y. B2 ..4.675
hall,Pa. U5 .....4.675
hicago,Ill. U5 ....4.675

STRUCTURALS

Carbon Steel Stand. Shapes
AlabamaCity,Ala. R2 ..3.85
Aliquippa,Pa. J5 .....3.85
Bessemer,Ala. T2 .....3.85
Bethlehem,Pa. B2 .....3.90
Clairton,Pa. U5 .....3.85
Fairfield,Ala. T2 .....3.85
Fontana,Calif. K1 .....4.50
Gary,Ind. U5 .....3.85
Geneva,Utah C11 .....3.85
Houston S5 .....4.25
Ind.Harbor,Ind. I-2 ...3.85
Johnstown,Pa. B2 .....3.90
KansasCity,Mo. S5 ....4.45
Lackawanna,N.Y. B2 ..3.90
LosAngeles B3 .....4.45
Minnequa,Colo. C10 ...4.30
Munhall,Pa. U5 .....3.85
Niles,Calif.(22) P1 ....4.56
Phoenixville,Pa. P4 ....4.95
Seattle B3 .....4.50
So.Chicago,Ill. U5 W14..3.85
So.SanFrancisco B3 ....4.40
Torrance,Calif. C11 ....4.45
Weirton,W.Va. W6 ....4.10

Wide Flange
Bethlehem,Pa. B2 .....3.90
Clairton,Pa. U5 .....3.85
Fontana,Calif. K1 .....5.05
Johnstown,Pa. B2 .....3.90
Lackawanna,N.Y. B2 ..3.90
Munhall,Pa. U5 .....3.85
So.Chicago,Ill. U5 .....3.85

Alloy Stand. Shapes
Clairton,Pa. U5 .....4.725
Fontana,Calif. K1 .....5.925
Gary,Ind. U5 .....4.725
Munhall,Pa. U5 .....4.725
So.Chicago,Ill. U5 ....4.725

H.S., L.A. Stand. Shapes
Aliquippa,Pa. J5 .....5.80
Bessemer,Ala. T2 .....5.80
Bethlehem,Pa. B2 .....5.80
Clairton,Pa. U5 .....5.80
Fairfield,Ala. T2 .....5.80
Fontana,Calif. K1 .....6.45
Gary,Ind. U5 .....5.80
Geneva,Utah C11 .....5.80
Ind.Harbor,Ind. I-2 ....5.80
Ind.Harbor,Ind. Y1 ....6.30
Johnstown,Pa. B2 .....5.80
Lackawanna,N.Y. B2 ..5.80
LosAngeles B3 .....6.35
Munhall,Pa. U5 .....5.80
Seattle B3 .....6.40
So.Chicago,Ill. U5 .....5.80
So.SanFrancisco B3 ....6.30
Struthers,O. Y1 .....6.30

H.S., L.A. Wide Flange
Bethlehem,Pa. B2 .....5.80
Lackawanna,N.Y. B2 ..5.80
Munhall,Pa. U5 .....5.75
So.Chicago,Ill. U5 .....5.75

BEARING PILES
Munhall,Pa. U5 .....3.85
So.Chicago,Ill. U5 .....3.85

PLATES,High-Strength Low-Alloy
Aliquippa,Pa. J5 .....5.95
Bessemer,Ala. T2 .....5.95
Clairton,Pa. U5 .....5.95
Cleveland J5, R2 .....5.95
Conshohocken,Pa. A3 ...6.20
Ecorse,Mich. G5 .....6.90
Fairfield,Ala. T2 .....5.95
Fontana,Calif.(30) K1 ..6.65
Gary,Ind. U5 .....5.95
Geneva,Utah C11 .....5.95
Ind.Harbor,Ind. I-2 ....5.95
Ind.Harbor,Ind. Y1 ....6.45
Johnstown,Pa. B2 .....5.95
Munhall,Pa. U5 .....5.95
Pittsburgh J5 .....5.95
Seattle B3 .....6.85
Sharon,Pa. S3 .....5.95
So.Chicago,Ill. U5 .....5.95
SparrowsPoint,Md. B2 ..5.95
Warren,O. R2 .....5.95
Youngstown Y1 .....6.45
Youngstown U5 .....5.95

PLATES, Open-Hearth Alloy
Claymont,Del. C22 ....5.35
Coatesville,Pa. L7 .....5.75
Conshohocken,Pa. A3 ..5.55
Fontana,Calif. K1 .....6.20
Gary,Ind. U5 .....5.25
Johnstown,Pa. B2 .....5.25
Munhall,Pa. U5 .....5.25
Sharon,Pa. S3 .....5.70
So.Chicago,Ill. U5 .....5.25
SparrowsPoint,Md. B2 ..5.25

FLOOR PLATES
Cleveland J5 .....4.95
Conshohocken,Pa. A3 ..4.95
Ind.Harbor,Ind. I-2 ....4.95
Munhall,Pa. U5 .....4.95
So.Chicago,Ill. U5 .....4.95

PLATES, Ingot Iron
Ashland,c.l. (15) A10 ..4.15
Cleveland,c.l. R2 .....4.50
Warren,O.,c.l. R2 .....4.50

PLATES, Carbon Steel
AlabamaCity,Ala. R2 ..3.90
Aliquippa,Pa. J5 .....3.90
Ashland,Ky. (15) A10..3.90
Bessemer,Ala. T2 .....3.90
Clairton,Pa. U5 .....3.90
Claymont,Del. C22 .....4.35
Cleveland J5, R2 .....3.90
Coatesville,Pa. L7 .....4.35
Conshohocken,Pa. A3 ..4.35
Ecorse,Mich. G5 .....4.45
Fairfield,Ala. T2 .....3.90
Fontana,Calif.(30) K1 ..4.55
Gary,Ind. U5 .....3.90
GraniteCity,Ill. G4 .....4.60
Geneva,Utah C11 .....3.90
Harrisburg,Pa. C5 .....6.50
Houston S5 .....4.30
Ind.Harbor,Ind. I-2, Y1.3.90
Johnstown,Pa. B2 .....3.90
Lackawanna,N.Y. B2 ..3.90
Minnequa,Colo. C10 ....4.70
Munhall,Pa. U5 .....3.90
Pittsburgh J5 .....3.90
Seattle B3 .....4.80
Sharon,Pa. S3 .....4.15
So.Chicago,Ill. U5, W14.3.90
SparrowsPoint,Md. B2 ..3.90
Steubenville,O. W10 ....3.90
Warren,O. R2 .....3.90
Weirton,W.Va. W6 .....4.20
Youngstown R2, U5, Y1.3.90

PLATES, Carbon A.R.
Fontana,Calif. K1 .....5.70
Geneva,Utah C11 .....5.05

PLATES, Wrought Iron
(Add 4.7% to base and extras)
Economy,Pa. B14 .....8.60

BARS, Hot-Rolled Carbon
AlabamaCity,Ala. R2 ..3.95
Aliquippa,Pa. J5 .....3.95
Alton,Ill. L1 .....4.50
Atlanta,Ga. A11 .....4.50
Bessemer,Ala. T2 .....3.95
Buffalo R2 .....3.95
Canton,O. R2 .....3.95
Clairton,Pa. U5 .....3.95
Cleveland R2 .....3.95
Detroit R7 .....4.10
Ecorse,Mich. G5 .....4.30
Emeryville,Calif. J7 ....4.70
Fairfield,Ala. T2 .....3.95
Fontana,Calif. K1 .....4.65
Gary,Ind. U5 .....3.95
Houston S5 .....4.35
Ind.Harbor,Ind. I-2 Y1.3.95
Johnstown,Pa. B2 .....3.95
KansasCity,Mo. S5 ....4.55
Lackawanna,N.Y. B2 ..3.95
LosAngeles B3 .....4.65
Milton,Pa. B6 .....4.55
Minnequa,Colo. C10 ....4.40
Niles,Calif. P1 .....4.65
N.Tonawanda,N.Y. B11.3.95
Pittsburg,Calif. C11 ....4.65
Pittsburgh J5 .....3.95
Seattle B3, N14 .....4.70
So.Chicago R2,U5,W14 ..3.95
So.Duquesne,Pa. U5 ...3.95
So.SanFran.,Calif. B3...4.70
Sterling,Ill. N15 .....4.55
Struthers,O. Y1 .....3.95
Torrance,Calif. C11 ....4.65
Weirton,W.Va. W6 .....4.10
Youngstown R2, U5 ....3.95

BAR SIZE ANGLES; S. Shapes
Aliquippa,Pa. J5 .....3.95
Atlanta A11 .....4.50
Niles,Calif. P1 .....4.65
SanFrancisco S7 .....5.00

BAR SIZE ANGLES; H.R.CARBON
Bethlehem,Pa. B2 .....4.15

BARS, Hot-Rolled Alloy
Bethlehem,Pa. B2 .....4.675
Buffalo R2 .....4.675
Canton,O. R2 .....4.675
Canton,O. T7 .....4.72
Clairton,Pa. U5 .....4.675
Detroit R7 .....4.825
Ecorse,Mich. G5 .....5.025
Fontana,Calif. K1 .....5.725
Gary,Ind. U5 .....4.675
Houston S5 .....5.075
Ind.Harbor,Ind. I-2,Y1.4.675
Johnstown,Pa. B2 .....4.675
KansasCity,Mo. S5 ....5.275
Lackawanna,N.Y. B2 ..4.675
LosAngeles B3 .....5.725
Massillon,O. R2 .....4.675
Midland,Pa. C18 .....4.675
So.Chicago R2,U5,W14.4.675
So.Duquesne,Pa. U5 ..4.675
Struthers,O. Y1 .....4.675
Warren,O. C17 .....4.675
Youngstown U5 .....4.675

BAR SHAPES, Hot-Rolled Alloy
Clairton,Pa. U5 .....4.925
Gary,Ind. U5 .....4.925
Youngstown U5 .....4.925

BARS & SMALL SHAPES, H. R., High-Strength Low-Alloy
Aliquippa,Pa. J5 .....5.925
Bessemer,Ala. T2 .....5.925
Bethlehem,Pa. B2 .....5.925
Clairton,Pa. U5 .....5.925
Cleveland R2 .....5.925
Ecorse,Mich. G5 .....6.675
Fairfield,Ala. T2 .....5.925
Fontana,Calif. K1 .....6.975
Gary,Ind. U5 .....5.925
Ind.Harbor,Ind. I-2 ...5.925
IndianaHarbor,Ind. Y1.6.425
Johnstown,Pa. B2 .....5.925
Lackawanna,N.Y. B2 ..5.925
LosAngeles B3 .....6.625
Pittsburgh J5 .....5.925
Seattle B3 .....6.675
So.Duquesne,Pa. U5 ..5.925
So.SanFrancisco B3 ...6.675
Struthers,O. Y1 .....6.425
Youngstown U5 .....5.925

BARS, Cold-Finished Carbon
Ambridge,Pa. W18 ...4.925
BeaverFalls,Pa. R2 ...4.925
BeaverFalls,Pa. M12 ..4.925
Buffalo B5 .....4.975
Camden,N.J. P13 .....5.375
Carnegie,Pa. C12 .....4.925
Chicago B5 .....4.925
Chicago W18 .....4.925
Cleveland A7, C20 ....4.925
Detroit P17, R7 .....5.075
Donora,Pa. A7 .....4.925
Elyria,O. W8 .....4.925
FranklinPark,Ill. N5 ..4.925
Gary,Ind. R2 .....4.925
GreenBay,Wis. F7 ....4.925
Hammond,Ind. L2,M13.4.925
Hartford,Conn. R2 ....5.475
LosAngeles R2 .....6.375
Mansfield,Mass. B5 ....5.475
Massillon,O. R2, R8...4.925
Monaca,Pa. S17 .....4.925
Newark,N.J. W18 .....5.375
Plymouth,Mich. P5 ....5.175
Pittsburgh J5 .....4.925
Putnam,Conn. W18 ...5.475
Readville,Mass. C14 ...5.475
St.Louis,Mo. M5 .....5.30
So.Chicago,Ill. W14 ...4.925
SpringCity,Pa. K3 ....5.375
Struthers,O. Y1 .....4.925
Waukegan,Ill. A7 .....4.925
Youngstown Y1 .....4.925
Youngstown F3 .....4.925

BARS, Cold-Finished Alloy
Ambridge,Pa. W18 .....6.00
BeaverFalls,Pa. M12 ...6.00
Bethlehem,Pa. B2 .....6.00
Buffalo B5 .....6.00
Camden,N.J. P13 .....6.40
Canton,O. R2 .....6.00
Canton,O. T7 .....5.99
Carnegie,Pa. C12 .....6.00
Chicago B5 .....6.00
Chicago W18 .....6.00
Cleveland A7 .....6.05
Cleveland C20 .....6.00
Detroit P17, R7 .....6.15
Donora,Pa. A7 .....6.05
Elyria,O. W8 .....6.00
Gary,Ind. R2 .....6.00
Hammond,Ind. L2, M13.6.00
Hartford,Conn. R2 ....6.45
Lackawanna,N.Y. B2 ..6.00
Mansfield,Mass. B5 ....6.45
Massillon,O. R2, R8 ....6.00
Midland,Pa. C18 .....6.00
Monaca,Pa. S17 .....6.00
Newark,N.J. W18 .....6.35
Plymouth,Mich. P5 .....6.20
So.Chicago,Ill. R2, W14.6.00
SpringCity,Pa. K3 .....6.20
Struthers,O. Y1 .....6.00
Warren,O. C17 .....6.00
Waukegan,Ill. A7 .....6.05
Worcester,Mass. A7 ....6.35
Youngstown Y1 .....6.00
Youngstown F3 .....6.00

BARS, Reinforcing (Fabricators)
AlabamaCity,Ala R2 ...3.95
Atlanta A11 .....4.50
Buffalo R2 .....3.95
Cleveland R2 .....3.95
Emeryville,Calif. J7 ....4.70
Fairfield,Ala. T2 .....3.95
Fontana,Calif. K1 .....4.65
Gary,Ind. U5 .....3.95
Houston S5 .....4.35
Ind.Harbor,Ind. I-2, Y1.3.95
Johnstown,Pa. B2 .....3.95
KansasCity,Mo. S5 ....4.55
Lackawanna,N.Y. B2 ..3.95
LosAngeles B3 .....4.65
Milton,Pa. B6 .....4.55
Minnequa,Colo. C10 ....4.75
Niles,Calif. P1 .....4.65
Pittsburg,Calif. C11 ....4.65
Pittsburgh J5 .....3.95
SandSprings,Okla. S5 ..4.85
Seattle B3, N14 .....4.70
So.Chicago,Ill. R2 .....3.95
So.Duquesne,Pa. U5 ....3.95
So.SanFrancisco B3 ....4.70
SparrowsPoint,Md. B2 ..3.95
Sterling,Ill.(1) N15 ....4.70
Struthers,O. Y1 .....3.95
Torrance,Calif. C11 ....4.65
Youngstown R2, U5 ....3.95

BARS, Reinforcing
(Fabricated; to consumers)
Huntington,W.Va. W7 ..5.50
Johnstown, ¼-1" B2 ...5.25
KansasCity S5 .....6.05
LosAngeles B3 .....5.45
Marion,O. P11 .....5.25
Seattle B3, N14 .....5.50
SandSprings S5 .....6.45
So.SanFrancisco B3 ....5.45
SparrowsPt. ¼-1" B2 ..5.25
Williamsport,Pa. S19 ...5.35

RAIL STEEL BARS
ChicagoHts.(3,4) C2 ...4.75
ChicagoHts.(3,4) I-2 ...4.75
Franklin,Pa.(3,4) F5 ...4.75
FortWorth,Tex.(26) T4..4.85
Huntngt,W.Va.(3) W7 ..5.75
Marion,O.(3) P11 .....4.75
Moline,Ill.(3) R2 .....4.05
Tonawanda(3,4) B12 ...5.00
Williamsport(3) S19 ...5.25
Williamsport(4) S19 ...5.35

BARS, Wrought Iron
(Add 4.7% to base and extras)
Economy,Pa.(S.R.) B14.9.60
Economy,Pa.(D.R.)B14 11.90
Economy(Staybolt)B14 12.20
McK.Rks.(Staybolt) L5 14.50
McK.Rks.(S.R.) L5 ....9.60
McK.Rks.(D.R.) L5 ...13.00

SHEETS, Hot-Rolled Steel
(18 gage and heavier)
AlabamaCity,Ala. R2 ..3.775
Ashland,Ky.(8) A10 ...3.775
Butler,Pa. A10 .....3.775
Cleveland J5, R2 .....3.775
Conshohocken,Pa. A3 ..4.175
Detroit M1 .....4.40
Ecorse,Mich. G5 .....3.975
Fairfield,Ala. T2 .....3.775
Fontana,Calif. K1 .....4.825
Gary,Ind. U5 .....3.775
Geneva,Utah C11 .....3.875
GraniteCity,Ill. G4 .....4.30
Ind.Harbor,Ind. I-2, Y1.3.775
Irvin,Pa. U5 .....3.775
Lackawanna,N.Y. B2 ..3.775
Munhall,Pa. U5 .....3.775
Niles,O. N12 .....5.425
Pittsburg,Calif. C11 ...4.475
Pittsburgh J5 .....3.775
Sharon,Pa. S3 .....4.175
So.Chicago,Ill. W14 ...3.775
SparrowsPoint,Md. B2..3.775
Steubenville,O. W10 ...3.775
Torrance,Calif. C11 ...4.475
Warren,O. R2 .....3.775
Weirton,W.Va. W6 ....3.775
WestLeechburg,Pa. A4.3.925
Youngstown U5, Y1 ...3.775

SHEETS, H.R. (19 gage)
AlabamaCity,Ala. R2 ..4.925
Dover,O. R1 .....5.825
Mansfield,O. E6 .....5.65
Niles,O. N12 .....5.675
Torrance,Calif. C11 ...5.575

SHEETS, H.R. (14 ga. heavier)
High-Strength Low-Alloy
Cleveland J5, R2 .....5.675
Conshohocken,Pa. A3 ..5.925
Ecorse,Mich. G5 .....6.225
Fairfield,Ala. T2 .....5.675
Fontana,Calif. K1 .....6.775
Gary,Ind. U5 .....5.675
Ind.Harbor,Ind. I-2 ...5.675
Ind.Harbor,Ind. Y1 ...6.175
Irvin,Pa. U5 .....5.675
Lackawanna(35) B2 ...5.675
Munhall U5 .....5.675
Pittsburgh J5 .....5.675
Sharon,Pa. S3 .....5.675
So.Chicago,Ill. U5 ....5.675
SparrowsPoint(36) B2..5.675
Warren,O. R2 .....5.675
Weirton,W.Va. W6 ....6.025
Youngstown U5 .....5.675
Youngstown Y1 .....6.175

SHEETS, Cold-Rolled
High-Strength Low-Alloy
Cleveland J5, R2 .....6.925
Ecorse,Mich. G5 .....7.475
Fontana,Calif. K1 .....7.875
Gary,Ind. U5 .....6.925
IndianaHarbor,Ind. Y1.7.425
IndianaHarbor,Ind. I-2.6.925
Irvin,Pa. U5 .....6.925
Lackawanna(37) B2 ...6.925
Pittsburgh J5 .....6.925
SparrowsPoint(38) B2..6.925
Warren,O. R2 .....6.925
Weirton,W.Va. W6 ....7.275
Youngstown Y1 .....7.425

SHEETS, Cold-Rolled Steel (Commercial Quality)

Butler,Pa. A10	4.575
Cleveland J5, R2	4.575
Ecorse,Mich. G5	4.775
Fairfield,Ala. T2	4.575
Follansbee,W.Va. F4	5.575
Fontana,Calif. K1	5.675
Gary,Ind. U5	4.575
GraniteCity,Ill. G4	5.275
Ind.Harbor,Ind. I-2,Y1	4.575
Irvin,Pa. U5	4.575
Lackawanna,N.Y. B2	4.575
Middletown,O. A10	4.575
Pittsburg,Calif. C11	5.525
Pittsburgh J5	4.575
SparrowsPoint,Md. B2	4.575
Steubenville,O. W10	4.575
Warren,O. R2	4.575
Weirton,W.Va. W6	4.575
WestLeechburg,Pa. A4	5.45
Youngstown Y1	4.575

SHEETS, Galv'd No. 10 Steel

AlabamaCity,Ala. R2	5.075
Ashland,Ky.(8) A10	5.075
Canton,O. R2	5.075
Delphos,O. N16	5.675
Dover,O. R1	5.775
Fairfield,Ala. T2	5.075
Gary,Ind. U5	5.075
GraniteCity,Ill. G4	5.50
Ind.Harbor,Ind. I-2	5.075
Irvin,Pa. U5	5.075
Kokomo,Ind.(13) C16	5.475
MartinsFerry,O. W10	5.075
Niles,O. N12	6.275
Pittsburg,Calif. C11	5.825
SparrowsPoint,Md. B2	5.075
Steubenville,O. W10	5.075
Torrance,Calif. C11	5.825
Weirton,W.Va. W6	5.075

SHEETS, Galvanized No. 10, High-Strength Low-Alloy

Irvin,Pa. U5	7.625
SparrowsPoint(39) B2	7.775

SHEETS, Galvannealed Steel

Canton,O. R2	5.625
Irvin,Pa. U5	5.625
Kokomo,Ind.(13) C16	6.025
Niles,O. N12	6.825

SHEETS, ZINCGRIP Steel No. 10

Butler,Pa. A10	5.325
Middletown,O. A10	5.325

SHEETS, Electro Galvanized

Cleveland R2 (28)	5.925
Niles,O. R2 (28)	5.925
Weirton,W.Va. W6	5.775

SHEETS, Well Casing

Fontana,Calif. K1	5.34

BLUED Stock, 29 ga.

Yorkville,O. W10	7.90
Follansbee,W.Va. F4	7.10
Follansbee (23) F4	6.425

SHEETS, Enameling Iron

Ashland,Ky.(8) A10	4.925
Cleveland R2	4.925
Gary,Ind. U5	4.925
GraniteCity,Ill. G4	5.625
Ind.Harbor,Ind. I-2	4.925
Irvin,Pa. U5	4.925
Middletown,O. A10	4.925
Youngstown Y1	4.925

BLACK PLATE (Base Box)

Aliquippa,Pa. J5	$6.50
Fairfield,Ala. T2	6.60
Gary,Ind. U5	6.50
GraniteCity,Ill. G4	6.70
Ind.Harbor,Ind. I-2, Y1	6.50
Irvin,Pa. U5	6.50
Niles,O. R2	6.50
Pittsburg,Calif. C11	7.25
SparrowsPoint,Md. B2	6.60
Warren,O. R2	6.50
Weirton,W.Va. W6	6.50
Yorkville,O. W10	6.50

HOLLOWARE ENAMELING Black Plate (29 gage)

Follansbee,W.Va. F4	6.10
Gary,Ind. U5	6.10
GraniteCity,Ill. G4	6.30
Ind.Harbor,Ind. Y1	6.10
Irvin,Pa. U5	6.10
Yorkville,O. W10	6.35

SHEETS, Culvert No. 16

	Cu Alloy	Cu Fe
Ashland,Ky. A10	5.875	....
Canton,O. R2	5.925	6.375
Fairfield,Ala. T2	5.875	6.125
Gary,Ind. U5	5.875	6.125
Ind.Harbor I-2	5.875	6.125
Irvin,Pa. U5	5.875	6.125
Kokomo,Ind. C16	6.525	....
MartinsFy.,O.W10	5.875	....
Pittsburg,Cal.C11	6.625	....
SparrowsPt. B2	5.875	....
Torrance,Cal.C11	6.625	....

SHEETS, Culvert, No. 16 Pure Iron

Ashland,Ky. A10	6.125
Fairfield,Ala. T2	6.125
MartinsFerry,O. W10	6.125

SHEETS, Hot-Rolled Ingot Iron 18 Gage and Heavier

Ashland,Ky.(8) A10	4.025
Cleveland R2	4.375
Ind.Harbor,Ind. I-2	4.025
Warren,O. R2	4.375

SHEETS, Cold-Rolled Ingot Iron

Butler,Pa. A10	5.075
Cleveland R2	5.175
Middletown,O. A10	5.075
Warren,O. R2	5.175

SHEETS, Galvanized Ingot Iron No. 10 flat

Ashland,Ky.(8) A10	5.325
Canton,O. R2	5.825

SHEETS, ZINCGRIP Ingot Iron

Butler,Pa. A10	5.575
Middletown,O. A10	5.575

SHEETS, ALUMINIZED

Butler,Pa. A10	8.425

TIN PLATE, American 1.25 Coke (Base Box)

	1.50 lb
Aliquippa,Pa. J5	$8.95
Fairfield,Ala. T2	8.95
Gary,Ind. U5	8.95
Ind.Har. I-2, Y1	8.95
Irvin,Pa. U5	8.95
Pitts.,Cal. C11	9.70
Sp.Pt.,Md. B2	9.05
Warren,O. R2	....
Weirton,W.Va.W6	8.95
Yorkville,O. W10	8.95

TIN PLATE, Electrolytic (Base Box)

	0.25 lb	0.50 lb	0.75 lb
Aliquippa,Pa. J5	$7.40	$7.65	$8.05
Fairfield,Ala. T2	7.50	7.75	8.15
Gary,Ind. U5	7.40	7.65	8.05
GraniteCity,Ill. G4	7.60	7.85	8.25
IndianaHarbor,Ind. I-2, Y1	7.40	7.65	8.05
Irvin,Pa. U5	7.40	7.65	8.05
Niles,O. R2	7.40	...	...
Pittsburg,Calif. C11	8.15	8.40	8.80
SparrowsPoint,Md. B2	7.50	7.75	8.15
Weirton,W.Va. W6	7.40	7.65	8.05
Yorkville,O. W10	7.40	7.65	8.05

SHEETS, SILICON, H.R. or C.R.(22 Ga.) COILS (Cut lengths ½c lower)

	Field	Armature	Electric	Motor	Dynamo
BeechBottom W10 (cut lengths)	...	...	7.85	9.10	9.90
Brackenridge,Pa. A4	...	...	8.35	9.60	10.40
GraniteCity,Ill. G4 (cut lengths)	...	...	8.55	9.80	...
IndianaHarbor,Ind. I-2	7.55	7.85	(34)	(41)	...
Mansfield,O. E6 (cut lengths)	7.20	7.35	7.85	9.10	9.90
Niles,O. N12 (cut lengths)	7.05	7.35	7.85	...	...
Vandergrift,Pa. U5	...	7.85	8.35	9.60	10.40
Warren,O. R2	7.55	7.85	8.35	9.60	10.40
Zanesville,O. A10	...	7.85	8.35	9.60	10.40

SHEETS, SILICON (22 Ga. Base) COILS (Cut Length ½c lower)

Transformer Grade	72	65	58	52
BeechBottom W10 (cut lengths)	10.45	11.00	11.70	12.50
Brackenridge,Pa. A4	10.95	....	....	....
Vandergrift,Pa. U5	10.95	11.50	12.20	13.00
Warren,O. R2	10.95	....	....	....
Zanesville,O. A10	10.95	11.50	12.20	13.00

H.R. or C.R. COILS AND CUT LENGTHS, SILICON (22 Ga.)

	T-100	T-90	T-80	T-73
Butler,Pa. A10 (C.R.)	....	....	15.35	15.85
Vandergrift,Pa. U5	13.50	14.35	15.35	15.85

MANUFACTURING TERNES (Special Coated)

Fairfield,Ala. T2	$7.85
Gary,Ind. U5	7.75
Irvin,Pa. U5	7.75
Yorkville,O. W10	7.75

SHEETS, LT. Coated Ternes, 6 lb

Yorkville,O. W10	$8.65

SHEETS, Mfg. Ternes, 8 lb (Commercial Quality)

Gary,Ind. U5	$9.75
Yorkville,O. W10	9.75

SHEETS, Long Terne Steel (Commercial Quality)

BeechBottom,W.Va. W10	5.475
Gary,Ind. U5	5.475
Mansfield,O. E6	6.05
Middletown,O. A10	5.475
Niles,O. N12	6.275
Weirton,W.Va. W6	5.475

SHEETS, Long Terne, Ingot Iron

Middletown,O. A10	5.875

ROOFING SHORT TERNES (8 lb Coated)

Gary,Ind. U5	9.75

STRIP, Hot-Rolled High-Strength Low-Alloy

Bessemer,Ala. T2	5.65
Conshohocken,Pa. A3	5.90
Ecorse,Mich. G5	6.30
Fairfield,Ala. T2	5.65
Fontana,Calif. K1	6.55
Gary,Ind. U5	5.65
Ind.Harb.,Ind. I-2	5.65
Ind.Harbor,Ind. Y1	6.15
Lackawanna,N.Y. B2	5.70
LosAngeles(25) B3	6.40
Seattle(25) B3	6.65
Sharon,Pa. S3	5.65
So.SanFrancisco(25) B3	6.40
SparrowsPoint,Md. B2	5.70
Warren,O. R2	5.65
Weirton,W.Va. W6	6.10
Youngstown Y1	6.15
Youngstown U5	5.65

STRIP, Cold-Rolled High-Strength Low-Alloy

Cleveland J5	7.45
Cleveland A7	7.30
Dover,O. G6	8.00
Ecorse,Mich. G5	8.15
Lackawanna,N.Y. B2	7.90
Sharon,Pa. S3	7.30
SparrowsPoint,Md. B2	7.90
Warren,O. R2	7.30
Weirton,W.Va. W6	7.95
Youngstown Y1	7.80

STRIP, Hot-Rolled Carbon

Ala.City,Ala.(27) R2	3.725
Alton,Ill. L1	4.20
Ashland,Ky.(8) A10	3.725
Atlanta A11	4.275
Bessemer,Ala. T2	3.725
Bridgeport,Con.(10) S15	4.225
Buffalo(27) R2	3.725
Butler,Pa. A10	3.725
Carnegie,Pa. S18	4.225
Conshohocken,Pa. A3	4.125
Detroit M1	4.40
Ecorse,Mich. G5	4.025
Fairfield,Ala. T2	3.725
Fontana,Calif. K1	5.175
Gary,Ind. U5	3.725
Houston,Tex. S5	4.125
Ind.Harbor,Ind. I-2,Y1	3.725
Johnstown,Pa.(25) B2	3.725
KansasCity,Mo.(9) S5	4.325
Lackawanna,N.Y.(32) B2	3.725
LosAngeles(25) B3	4.475
Milton,Pa. B6	4.35
Minnequa,Colo. C10	4.775
NewBritain(10) S15	4.225
N.Tonawanda,N.Y. B11	3.725
Pittsburg,Calif. C11	4.475
Riverdale,Ill. A1	3.725
SanFrancisco S7	5.00
Seattle(25) B3	4.725
Seattle N14	4.75
Sharon,Pa. S3	4.225
So.Chicago,Ill. W14	3.725
So.SanFrancisco(25) B3	4.475
SparrowsPoint,Md. B2	3.725
Sterling,Ill. N15	4.725
Torrance,Calif. C11	4.475
Warren,O. R2	3.725
Weirton,W.Va. W6	3.825
WestLeechburg,Pa A4	3.975
Youngstown U5, Y1	3.725

STRIP, Hot-Rolled Alloy

Bridgeprt,Conn.(10) S15	6.05
Carnegie,Pa. S18	6.45
Fontana,Calif. K1	7.30
Gary,Ind. U5	6.10
Houston,Tex. S5	6.50
KansasCity,Mo. S5	6.70
Midland,Pa. C18	5.85
NewBritn.,Conn.(10) S15	6.05
Sharon,Pa. S3	6.45
Youngstown U5	6.10

STRIP, Cold-Rolled Carbon

Anderson,Ind.(40) G6	5.50
Bridgeptr,Conn.(10) S15	5.80
Butler,Pa. A10	5.10
Cleveland A7, J5	5.10
Dearborn,Mich. D3	6.05
Detroit D2	5.60
Detroit M1	5.45
Dover,O.(40) G6	5.50
Ecorse,Mich. G5	5.30
Follansbee,W.Va. F4	5.10
Fontana,Calif. K1	6.75
FranklinPark,Ill.(40) T6	5.35
Ind.Harbor,Ind. I-2	5.35
Lackawanna,N.Y. B2	5.10
LosAngeles C1	6.85
Mattapan,Mass. T6	5.95
Middletown,O. A10	5.10
NewBritain(10) S15	5.80

STRIP, Cold-Finished, Spring Steel (Annealed)

	0.26-0.40C	0.41-0.60C	0.61-0.80C	0.81-1.05C	1.0
Berea,O. C7	...	6.80	7.40	9.35	11.
Bridgeport,Conn.(10) S15	5.80	7.65	8.25	10.20	12.
Bristol,Conn. W1	...	...	8.55	10.50	..
Carnegie,Pa. S18	...	7.65	8.25	10.20	12.
Cleveland A7	5.10	7.30	8.25	10.20	12.
Dearborn,Mich. D3	6.05	7.90	8.50	....	..
Detroit D2	6.45	7.50	8.10	....	..
Dover,O. G6	5.70	7.65	8.25	10.20	12
FranklinPark,Ill. T6	5.45	7.45	8.40	10.35	12
Harrison,N.J. C18	...	...	8.55	10.50	12
Mattapan,Mass. T6	5.95	7.60	8.55	10.50	12
NewBritn.,Conn.(10) S15	5.80	7.65	8.25	10.20	12
NewCastle,Pa. B4	5.80	7.65	8.25	10.20	.
NewCastle,Pa. E5	5.80	7.65	8.25	10.20	12
NewHaven,Conn. D2	6.70	7.60	8.20	....	.
New York W3	...	7.95	8.55	10.50	12
Pawtucket,R.I. N8: Cleve.orPitts.Base	...	7.65	8.25	10.20	12
Worcester,Mass.,Base.	6.30	7.95	8.55	10.50	12
Sharon,Pa. S3	5.80	7.65	8.25	10.20	12
Trenton,N.J. R5	...	7.95	8.25	10.50	12
Wallingford,Conn. W2	6.30	7.60	8.20	10.15	12
Warren,O. T5	6.20	7.65	8.25	10.20	12
Weirton,W.Va. W6	5.80	7.65	8.25	10.20	12
Worcester,Mass. A7	5.40	7.60	8.55	10.50	12
Worcester,Mass. T6	5.95	7.60	8.55	10.50	12
Youngstown C8	...	7.65	8.25	10.20	1
Spring Steel (Tempered)					
Trenton,N.J. R5 (29)	...	...	10.30	12.50	15
Harrison,N.J. C18	...	...	10.30	12.50	15
New York W3	...	...	10.30*	12.50*	15.
Youngstown C8	...	...	10.30	12.50	15

* Plus 1.575 per 100 lb.

STRIP, Hot-Rolled Ingot Iron

Ashland,Ky.(8) A10	3.9
Warren,O. R2	4.3

STRIP, Cold-Rolled Ingot Iron

Warren,O. R2	5.

TIGHT COOPERAGE HOOP

Atlanta A11	4.
Riverdale,Ill. A1	4.
Sharon,Pa. S3	4.
Youngstown U5	4.

STRIP, Electro Galvanized

Dover,O. G6	5.5
Warren,O. T5	5.7
Weirton,W.Va. W6	5.1
Youngstown C8	5.7

STRIP, Cold-Rolled Alloy Ste

Bridgeprt,Conn.(10) S15	12.1
Carnegie,Pa. S18	12.0
Cleveland A7	11.4
Dover,O. G6	11.9
Fontana,Calif. K1	13.0
Harrison,N.J. C18	12.0
Midland,Pa. C18	12.0
NewBritn,Conn.(10) S15	12.1
Pawtucket,R.I.(11) N8	12.1
Pawtucket,R.I.(12) N8	12.4
Sharon,Pa. S3	12.0
Worcester,Mass. A7	11.7
Youngstown C8	12.4

'IRE, Merchant Quality
to 8 gage) An'ld. Galv.
labamaCity R2 ..6.075 6.325
liquippa J5 ....6.075 6.525‡
tlanta A11 .....6.325 6.675
artonville(19)K4 6.075 6.40
uffalo W12 ....5.225 ....
leveland A7 ....6.075 6.225
rawfordsvilleM8 6.175 6.475
onora,Pa. A7 ..6.075 6.225
uluth,Minn. A7 6.075 6.225
airfield T2 .....6.075 6.225
ouston,Tex. S5..6.475 6.80
ohnstown B2 ...6.075 6.45†
oliet,Ill. A7 ....6.075 6.225
ansasCy,Mo. S5 6.675 7.00
okomo C16 ....6.175 6.425
osAngeles B3 ..7.025 ....
innequa C10 ...6.325 6.70*
onessen P7 ....6.075 6.45
almer W12 ....5.525 ....
itts.,Calif. C11..7.025 7.175
rtsmth.(18)P12..6.475 ....
ankin A7 .....6.075 6.225
o.Chicago R2 ..6.075 6.325
o.S.Fran, C10 ..7.025 7.40*
parrowsPt. B2..6.175 6.55†
terling,Ill.(1)N15 6.075 6.375
truthers,O. Y1 ..6.075 6.475
orrance,Cal. C11 7.025 ....
Vorcester A7 ...6.375 6.525

Based on 14c zinc; †14.50c
nc; ‡17.5 zinc.

Anl'd. Galv.
'IRE (16 gage) Stone Stone
(Add 4.7% on base and extras)
liquippa J5 ....10.15 12.15
artonville(19)K410.25 12.00*
leveland A7 ....10.25 11.55
rawfrdsville M8 10.73 12.51
ostoria,O. S1 ..10.40 13.00
ohnstown B2 ..10.73 12.58§
okomo C16 10.625† 12.325§
innequa C10..10.40 12.425*
almer,Mass.W12 10.25 12.15
itts.,Cal. C11 ..10.60 11.90
parrowsPt. B2 10.84 12.68§
terling(1) N15 10.73† 12.15†
aukegan A7 ....10.25 11.55
Vorcester A7 .....11.55 ....

Based on 14c zinc; §14.50c
nc, †Includes 4.7% increase.

'IRE, Manufacturers Bright,
Low Carbon
labamaCity,Ala. R2 ..5.225
liquippa,Pa. J5 (42)...4.85
tlanta A11 .....5.475
lton,Ill. L1 .....5.45
artonville,Ill. K4 ....5.325
uffalo W12 .....5.225
hicago W13 .....5.475
leveland A7, C20....5.225
rawfordsville,Ind, M8 5.325
onora,Pa. A7 .....5.225
uluth,Minn. A7 .....5.225
airfield,Ala T2 .....5.225
ostoria,O. (24) S1 ...5.725
ouston S5 .....5.625
ohnstown,Pa. B2 ....5.225
oliet,Ill. A7 .....5.225
ansasCity,Mo. S5 ....5.825
okomo,Ind. C16 ....5.325
osAngeles B3 .....6.175
innequa,Colo. C10 ...5.475
onessen,Pa. P7 .....5.475
ewark 6-8 ga I-1 ....5.88
o.Tonowanda B11 ...5.225
almer,Mass. W12 ....5.525
ittsburg,Calif. C11 ...6.175
ortsmouth,O. P12 ....5.625
ankin,Pa. A7 .....5.225
o.Chicago,Ill R2 .....5.225

So.SanFrancisco C10 ..6.175
SparrowsPoint,Md. B2..5.325
Sterling,Ill. (1) N15 ...5.225
Struthers,O. Y1 .....5.225
Torrance,Calif. C11 ...6.175
Waukegan,Ill. A7 ....5.225
Worcester,Mass. A7 ....5.525

WIRE, Cold-Rolled Flat
Anderson,Ind. G6 .....6.20
Buffalo W12 (43) 6.35
Cleveland A7 (43) 5.85
Crawf'sville,Ind.M8(48) 5.70
Dover,O. G6 .....6.20
Fostoria,O. S1 (43) 6.00
Kokomo,Ind. C16 (43)..5.70
FranklinPark,Ill. T6(43) 6.20
Massillon,O. R8 (43) ...5.85
Monessen,Pa. P16 (43)..6.35
Monessen,Pa. P7 (43) ..6.10
Pawtkt,R.I.(12) N8 (43)6.85
Trenton,N.J. R5 (43) ...6.15
Worcester,Mass. A7 (43).6.15
Worcester,Mass. T6 (43).6.50
Worcester,Mass.W12(43) 6.65

WIRE, Galv'd ACSR for Cores
Bartonville,Ill. K4 ....8.90
Monessen,Pa. P16 (43)..8.50
Muncie,Ind. I-7 (43) ...8.70
Roebling,N.J. R5 (43) ..8.80
SparrowsPt.,Md. B2(43)..8.60
Johnstown,Pa. B2 (43)..8.50

ROPE WIRE
Alton,Ill. L1 (43) 8.75
Bartonville,Ill. K4 .....8.95
Buffalo W12 (43).....8.55
Fostoria,O. S1 (43) 8.85
Johnstown,Pa. B2 (43)..8.55
Monessen,Pa. P16 (43)..8.55
Monessen,Pa. P7 (43) ..8.80
Muncie,Ind. I-7 (43) ...8.75
Palmer,Mass W12 (43).8.85
Portsmouth,O. P12 (43).8.55
Roebling,N.J. R5 (43) ..8.85
SparrowsPt. B2 (43) 8.65
Struthers,O. Y1 (43) ...8.55
Worcester J4, T6 (43) ..8.85

(A) Plow and Mild Plow; add 0.25c for improved plow.

WIRE, MB Spring, High Carbon
Aliquippa,Pa. J5 (43) ..6.25
Alton,Ill. L1 (43) 6.55
Bartonville,Ill K4 .....6.64
Buffalo W12 (43) 6.25
Cleveland A7 (43).....6.25
Donora,Pa. A7 (43) 6.25
Duluth,Minn. A7 (43) ..6.25
Fostoria,O. S1 (43) 6.25
Johnstown,Pa. B2 (43)..6.25
Millbury(12) N6 (43) ...8.05
Minnequa,Colo. C10(43).6.50
Monessen,Pa. P7 (43) ..6.25
Monessen,Pa. P16 .....6.75
Muncie,Ind. I-7 (43) ...6.45
Palmer,Mass. W12(43)..6.55
Pittsburg,Calif. C11(43).7.20
Roebling,N.J. R5 (43)...6.55
Portsmouth,O. P12(43)..6.25
So.Chicago,Ill. R2 (43)..6.25
So.SanFran. C10 (43) ..7.20
SparrowsPt.,Md. B2 (43)6.35
Struthers,O. Y1 (43) ...6.25
Trenton,N.J. A7 (43) ...6.55
Waukegan,Ill. A7 (43) ..6.25
Worcester A7, T6 (43)..6.55
Worcester,Mass. W12(43)6.55
Worcester,Mass. J4 (43).6.75

WIRE, Upholstery Spring
Aliquippa,Pa. J5 .....6.275
Alton,Ill L1 .....6.50
Buffalo W12 .....6.275
Cleveland A7 .....6.275
Donora,Pa. A7 .....6.275
Duluth,Minn. A7 .....6.275
Johnstown,Pa. B2 ....6.275

LosAngeles B3 .....7.225
Minnequa,Col C10 ....6.525
Monessen,Pa. P7 .....6.275
Monessen,Pa. P16(42) ..6.40
NewHaven,Conn. A7 ..6.575
Palmer,Mass. W12 ....6.575
Pittsburg,Calif. C11 ...7.225
Portsmouth,O. P12 ....6.275
Roebling,N.J. R5 ....6.575
So.Chicago,Ill R2 ....6.275
So.SanFrancisco C10 ..7.225
SparrowsPoint,Md. B2..6.375
Torrance,Calif. C11 ...7.225
Trenton,N.J. A7 .....6.575
Waukegan,Ill. A7 ....6.275
Worcester,Mass. A7 ...6.575

WIRE, Fine & Weaving (8"Coils)
Alton,Ill. L1 (43) 9.20
Bartonville,Ill. K4 .....9.42
Buffalo W12 (43) 8.90
Chicago W13 .....9.32
Cleveland A7 (43) 8.90
Crawf'sville,Ind. M8(43) 8.90
Fostoria,O. S1 (43) 8.90
Johnstown,Pa. B2 (43)..8.90
Kokomo,Ind. C16 (43)..8.90
Monessen,Pa. P16 (43)..8.90
Muncie,Ind. I-7 (43) ...9.10
Palmer,Mass. W12 (43).9.20
Roebling,N.J. R5 (43) ..9.20
Waukegan,Ill. A7 (43) ..8.90
Worcstr,Mass. A7,T6(43)9.20

WIRE, Tire Bead
Bartonville,Ill. K4 ....11.51
Monessen,Pa. P16 (43).11.40
Roebling,N.J. R5 (43)..11.55

WOVEN FENCE, 9-15½ Ga. Col.
AlabamaCity,Ala R2 .. 135
Ala.City,Ala.,17-18ga.R2 222
Aliqu'pa,Pa.9-14½ga.J5 139‡
Atlanta A11 140
Bartonville,Ill.(19) K4 ..137
Crawfordsville,Ind. M8 ..138
Donora,Pa. A7 133
Duluth,Minn. A7 133
Fairfield,Ala. T2 133
Houston,Tex. S5 145
Johnstown,Pa. B2 138
Johnstown 17ga.,6" B2 ..229
Joliet,Ill. A7 133
KansasCity,Mo. S5 149
Kokomo,Ind. C16 140
Minnequa,Colo. C10 ....146*
Monessen,Pa. P7 138
Pittsburg,Calif. C11 156
Rankin,Pa. A7 133
So.Chicago,Ill. R2 135
Sterling,Ill. (1) N15.....136

*Based on 14c zinc; ‡17.5c zinc.

FENCE POSTS Col.
ChicagoHts.,Ill. C2 140
Duluth,Minn. A7 133
Franklin,Pa. F5 145
Huntington,W.Va. W7 ...148
Johnstown,Pa. B2 148
Marion,O. P11 140
Minnequa,Colo. C10 138
Moline,Ill R2 136
So.Chicago,Ill R2 140
Tonawanda,N.Y. B12 ...148
Williamsport,Pa. S19 ...158

WIRE, Barbed Col.
AlabamaCity,Ala. R2 ...144
Aliquippa,Pa. J5 .....148‡
Atlanta A11 149
Bartonville,Ill.(19) K4 ..146
Crawfordsville,Ind. M8 ..147
Donora,Pa. A7 142
Duluth,Minn. A7 142
Fairfield,Ala. T2 142
Houston,Tex S5 154
Johnstown,Pa. B2 145

Joliet,Ill. A7 142
KansasCity,Mo. S5 158
Kokomo,Ind. C16 149
Minnequa,Colo. C10 ....153*
Monessen,Pa. P7 147
Pittsburg,Calif. C11 162
Rankin,Pa. A7 142
So.Chicago,Ill. R2 144
So.SanFran.,Calif. C10..167*
SparrowsPoint,Md. B2 ..147
Sterling,Ill.(1) N15 145

*Based on 14c zinc; ‡17.5c zinc.

BALE TIES, Single Loop Col.
AlabamaCity,Ala. R2 ...132
Atlanta A11 135
Bartonville,Ill.(19) K4 ..132
Crawfordsville,Ind. M8 ..132
Donora,Pa. A7 132
Duluth,Minn. A7 132
Fairfield,Ala. T2 132
Joliet,Ill. A7 132
KansasCity,Mo. S5 144
Kokomo,Ind. C16 134
Minnequa,Colo. C10 137
Pittsburg,Calif. C11 156
So.Chicago,Ill. R2 132
So.SanFran.,Calif. C10 ..156
SparrowsPoint,Md. B2 ..134
Sterling,Ill.(1) N15 132

TRACK BOLTS (20) Treated
KansasCity,Mo. S5(46)..9.85
Lebanon,Pa. (31) B2 ...9.85
Minnequa,Colo. C10 ....9.85
Pittsburgh O3, P14 ....9.85

AXLES
Ind.Harbor,Ind. S13 ....5.65
Johnstown,Pa. B2 .....5.65

NAILS, Stock
To dealers & mfrs. (7) Col.
AlabamaCity,Ala. R2 ...127
Aliquippa,Pa. J5 127
Atlanta A11 130
Bartonville,Ill. (19) K4 ..127
Chicago,Ill. W13 127
Cleveland A9 (44) 125
Crawfordsville,Ind. M8 ..127
Donora,Pa. A7 127
Duluth,Minn. A7 127
Fairfield,Ala. T2 127
Galveston,Tex. D7 135
Houston,Tex. S5 135
Johnstown,Pa. B2 127
Joliet,Ill. A7 127
KansasCity,Mo. S5 139
Kokomo,Ind. C16 129
Minnequa,Colo. C10 (44).123
Monessen,Pa. P7 127
Pittsburg,Calif. C11 146
Portsmouth,O. P12 132
Rankin,Pa. A7 127

So.Chicago,Ill. R2 127
SparrowsPt.,Md. B2 129
Sterling,Ill.(1) N15 147
Torrance,Calif. C11 147
Worcester,Mass. A7 133

STAPLES, Polished, Stock
To dealers & mfrs. (7) Col.
AlabamaCity,Ala. R2 ...126
Aliquippa,Pa. J5 126
Atlanta A11 129
Bartonville,Ill. (19) K4..126
Chicago W13 127
Crawfordsville,Ind. M8 ..128
Donora,Pa. A7 126
Duluth,Minn. A7 126
Fairfield,Ala. T2 126
Johnstown,Pa. B2 126
Joliet,Ill. A7 126
Kokomo,Ind. C16 128
Minnequa,Colo. C10 (45)..123
Monessen,Pa. P7 127
Pittsburg,Calif. C11 145
Portsmouth,O. P12 132
Rankin,Pa. A7 126
So.Chicago,Ill. R2 126
SparrowsPt.,Md. B2 128
Sterling,Ill.(1) N15 126
Torrance,Calif. C11 146
Worcester,Mass. A7 132

NAILS, Cut (100 lb keg)
To dealers (33)
Conshohocken,Pa. A3 ..$7.80
Wheeling,W.Va. W10 ...7.80

TIE PLATES
Fairfield,Ala. T2 .....4.775
Gary,Ind. U5 .....4.775
Ind.Harbor,Ind. I-2 ...4.775
Lackawanna,N.Y. B2 ..4.775
Minnequa,Colo. C10..$95.50*
Pittsburg,Calif. C11 ...4.925
Seattle B3 .....4.925
Steelton,Pa. B2 .....4.775
Torrance,Calif. C11 ...4.925
* Per net ton.

JOINT BARS
Bessemer,Pa. U5 .....4.925
Fairfield,Ala. T2 .....4.925
Ind.Harbor,Ind. I-2 ...4.925
Joliet,Ill. U5 .....4.925
Lackawanna,N.Y. B2 ..4.925
Minnequa,Colo. C10 ...4.925
Steelton,Pa. B2 .....4.925

STANDARD TRACK SPIKES
Ind.Harbor,Ind. I-2, Y1.6.65
KansasCity,Mo. S5 .....6.90
Lebanon,Pa. B2 .....6.65
Minnequa,Colo. C10 ....6.65
Pittsburgh J5 .....6.65
Seattle B3 .....7.15
So.Chicago,Ill. R2 .....6.65
Struthers,O. Y1 .....6.65
Youngstown R2 .....6.65

RAILS	Std. No. 1	Std. No. 2	All No. 2	Std. Tee Rails 60 lb Under
Bessemer,Pa. U5	3.775	3.675	3.725	4.25
Ensley,Ala. T2	3.775	3.675	....	4.25
Fairfield,Ala. T2	....	....	....	4.25
Gary,Ind. U5	3.775	3.675	3.725	...
Huntington,W.Va. W7	....	....	....	5.25
IndianaHarbor,Ind. I-2	3.775	3.675	3.725	...
Johnstown,Pa. B2	....	....	...(16)	4.25
Lackawanna,N.Y. B2	3.775	3.675	....	4.25
Minnequa,Colo. C10	$75.50*	$73.50*	....	4.75
Steelton,Pa. B2	3.775	3.675	....	...
Williamsport,Pa. S19	....	....	....	5.00

* Per net ton.

TOOL STEEL

(Prices subject to 4.7% increase)

Grade	$ per lb
Regular Carbon	0.230
Extra Carbon	0.270
Special Carbon	0.325
Oil Hardening	0.350
5% Cr Hot Work	0.350
Hi-Carbon-Cr	0.635

Grade by Analysis

W	Cr	V	Co	
18	4	1	....	1.505
18	4	2	....	1.65-1.66
20.25	4.25	1.6	12.25	3.535-3.675
19	4	2	7	2.460
18.25	4.25	1	4.75	2.125
18	4	2	9	2.445-2.45
13.5	4	3	....	1.6025
9	3.25	0.5	....	1.01

W	Cr	V	Mo	
6.4	4.5	1.9	5	0.96-0.965
6	4	3	6	1.190
1.5	4	1	8.5	0.810

Tool steel producers include: A4, A8, B2, B8, C4, C9, C13, C18, D4, F2, J3, L3, M14, S8, U4, V2 and V3.

FOOTNOTES
(1) Chicago base.
(2) Angles, flats, bands.
(3) Merchant.
(4) Reinforcing.
(6) Chicago or Birm. base.
(7) To jobbers, 3 cols. lower.
(8) 16 gage and heavier.
(9) 6 in. and narrower.
(10) Pittsburgh base.
(11) Cleveland & Pitts. base.
(12) Worcester, Mass. Base.
(13) Add 0.50c for 17 Ga. & heavier.
(15) ⅛" and thinner.
(16) 40 lb and under.
(17) Flats only.
(18) To dealers.
(19) Chicago & Pitts. base.
(20) 0.25c off for untreated.
(21) New Haven Conn., base.
(22) Del. San Francisco Bay area
(23) 20 Ga. 36" wide.
(24) Deduct 0.20c, finer than 15 Ga.
(25) Bar mill bands.
(26) Reinforcing, mill lengths, to fabricators; to consumers, 5.05c.
(27) Bar mill sizes.
(28) Bonderized.
(29) Add $31.50 per ton.
(30) Sheared; add 0.35c for universal mill.
(31) Not annealed.
(32) Rd. or square edge.
(33) To jobbers, deduct 20c.
(34) 7.85c for cut lengths.
(35) 72" and narrower.
(36) 54" and narrower.
(37) 15 gage & lighter: 60" & narrower.
(38) 14 gage & lighter: 48" & narrower.
(39) 48" and narrower.
(40) Lighter than 0.035"; 0.035" and heavier, 0.25c higher.
(41) 9.10c for cut lengths.
(42) Plus 0.375c per 100 lb.
(43) Plus 4.7% on base and extras.
(44) Plus 45c per 100 lb.
(45) Plus 40c per 100 lb.
(46) Plus 2.2 per cent.
(26) Reinforcing, mill

Key to Producers

M1 McLouth Steel Corp.
M4 Mahoning Valley Steel
M5 Medart Co.
M6 Mercer Tube & Mfg. Co.
M8 Mid-States Steel & Wire
M12 Moltrup Steel Products
M13 Monarch Steel Co.
N2 National Supply Co.
N3 National Tube Div.
N5 Nelsen Steel & Wire Co.
N6 NewEng.-HighCarb.Wire
N8 Newman-Crosby Steel
N12 Niles Rolling Mill Div.
N14 Nrthwst. Steel Roll. Mills
N15 Northwestern S.&W. Co.
N16 New Delphos Mfg. Co.
O3 Oliver Iron & Steel Corp.
O4 Oregon Steel Mills
P1 Pacific States Steel Corp.
P2 Pacific Tube Co.
P4 Phoenix Iron & Steel Co.
P5 Pilgrim Drawn Steel
P6 Pittsburgh Coke & Chem.
P7 Pittsburgh Steel Co.
P9 Pittsburgh Tube Co.
P11 Pollak Steel Co.
P12 Portsmouth Division, Detroit Steel Corp.
P13 Precision Drawn Steel
P14 Pitts. Screw & Bolt Co.
P15 Pittsburgh Metallurgical
P16 Page Steel & Wire Div., Amer. Chain & Cable
P17 Plymouth Steel Co.
R1 Reeves Steel & Mfg. Co.
R2 Republic Steel Corp.
R3 Rhode Island Steel Corp.
R5 Roebling's Sons, John A.
R6 Rome Strip Steel Co.
R7 Rotary Electric Steel Co.
R8 Reliance Div., Eaton Mfg.
S1 Seneca Wire & Mfg. Co.
S3 Sharon Steel Corp.
S4 Sharon Tube Co.
S5 Sheffield Steel Corp.
S6 Shenango Furnace Co.
S7 Simmons Co.
S8 Simonds Saw & Steel Co.
S9 Sloss-Sheffield S.&I. Div.
S13 Standard Forgings Corp.
S14 Standard Tube Co.
S15 Stanley Works
S16 Struthers Iron & Steel
S17 Superior Drawn Steel Co.
S18 Superior Steel Corp.
S19 Sweet's Steel Co.
S20 Southern States Steel
S24 Seidelhuber Steel
T2 Tenn. Coal & Iron Div.
T3 Tenn. Prod. & Chem.
T4 Texas Steel Co.
T5 Thomas Strip Division, Pittsburgh Steel Co.
T6 Thompson Wire Co.
T7 Timken Roller Bearing
T9 Tonawanda Iron Div., Am. Rad. & Stan. San.
U4 Universal Cyclops Steel
U5 United States Steel Corp.
V2 Vanadium-Alloys Steel
V3 Vulcan Crucible Steel Co.
W1 Wallace Barnes Co.
W2 Wallingford Steel Co.
W3 Washburn Wire Co.
W4 Washington Steel Corp.
W6 Weirton Steel Co.
W7 W. Va. Steel & Mfg. Co.
W8 West.Auto.Mach.Screw
W9 Wheatland Tube Co.
W10 Wheeling Steel Corp.
W12 Wickwire Spencer Steel Div., Colo. Fuel & Iron
W13 Wilson Steel & Wire Co.
W14 Wisconsin Steel Div. International Harvester
W15 Woodward Iron Co.
W18 Wyckoff Steel Co.
Y1 Youngstown Sheet & Tube

Some 9,500 people were in South Amboy, N. J., that drizzly evening in 1950. At the waterfront, longshoremen were transferring the last of 12 freight cars of ammunition to lighters that would carry it to a waiting vessel in Raritan Bay.

But the City Hall clock never got to 7:27—and the freighter's deadly cargo never got loaded. Explosions shattered windows over a radius of 12 miles; and hundreds of people looked at their arms and legs and saw that flying daggers of glass had stabbed them.

At dawn, 312 of the injured had been counted.

★ ★ ★

Such disasters have happened many times before in America. They could happen again. And *if* they do—and *when* they do—there must be blood plasma on hand to take care of the injured. For blood saves lives!

But blood cannot be mined or manufactured. It must come from the veins of healthy men and women. Men and women who feel concern for a suffering neighbor. So give blood—now!

Whether your blood goes for Civil Defense needs, to a combat area, or to a local hospital—this priceless, painless gift will some day save an American life!

A PUBLIC SERVICE PROJECT · THE ADVERTISING COUNCIL

Give Blood Now

CALL YOUR RED CROSS TODAY!

National Blood Program

Business Executives!

✓Check These Questions!

If you can answer "yes" to most of them, you—and your company—are doing a needed job for the National Blood Program.

- ☐ Have you given your employees time off to make blood donations?
- ☐ Do you have a Blood Donor Honor Roll in your company?
- ☐ Have you set up a list of volunteers so that efficient plans can be made for scheduling donors?
- ☐ Have you arranged to have a Bloodmobile make regular visits?
- ☐ Has your management endorsed the local Blood Donor Program?
- ☐ Have you informed employees of your company's plan of co-operation?
- ☐ Was this information given through Plant Bulletin or House Magazine?
- ☐ Has your company given any recognition to donors?
- ☐ Have you conducted a Donor Pledge Campaign in your company?

Remember, as long as a *single* pint of blood may mean the difference between life and death for *any* American . . . the need for blood is *urgent!*

UTTWELD STANDARD PIPE, T & C

Carload discounts from list, %

ze—Inches	½		¾		1		1¼		1½		2		2½		3	
st Per Ft.	8.5c		11.5c		17c		23c		27.5c		37c		58.5c		76.5c	
ounds Per Ft.	0.85		1.13		1.68		2.28		2.73		3.68		5.82		7.62	
	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv
liquippa, Pa. J5 (‡)	32.5	15.25	35.5	18.25	38	20.75	38.5	20.5	39	21	39.5	21.5	40	21.25	40	21.25
lton, Ill. L1 (†)	29.5	10.5	32.5	14.5	35	18	35.5	18.5	36	19.5	36.5	20	37	20.5	37	20.5
enwood, W. Va. W10	32.5	13.25	35.5	17.25	38	20.75	38.5	20.5	39	21.5	39.5	22	40	21.75	40	21.75
tna, Pa. N2 (†)	32.5	13.25	35.5	17.25	38	20.75	38.5	20.5	39	22.25	39.5	22	40	21.75	40	21.75
ontana, Calif. K1 (†)	19.5	0.25	22.5	4.25	25	7.75	25.5	7.5	26	8.5	26.5	9	27	8.75	27	8.75
d. Harbor, Ind. Y1 (†)	31.5	14.25	34.5	18.25	37	21.75	37.5	21	38	22	38.5	22.25	39	21.75	39	21.75
orain, O. N3 (*)	32.5	22.25	35.5	26.25	38	29.75	38.5	27.25	39	28.25	39.5	28.75	40	26.25	40	26.25
aaron, Pa. M6	32.5	14.25	35.5	18.25	38	21.25	38.5	20.50	39	21.00	39.5	21.50	40	20.75	40	20.75
arrows Pt., Md. B2	30.5	11.25	33.5	15.25	36	18.75	36.5	18.5	37	19.5	37.5	20	38	19.75	38	19.75
oungstown R2 (**)	32.5	16.25	35.5	20.25	38	23.75	38.5	22.75	39	23.75	39.5	24.25	40	23.25	40	23.25
oungstown Y1 (‡)	32.5	15.25	35.5	19.25	38	22.75	38.5	22.00	39	23.00	39.5	23.50	40	22.75	40	22.75
heatland, Pa. W9	32.5	13.25	35.5	16.25	38	18.75	38.5	19	39	19.5	39.5	20	40	20.25	40	20.25

EAMLESS STANDARD PIPE, T & C

Carload discounts from list, %

ze—Inches	2		2½		3		3½		4		5		6	
st Per Ft.	37c		58.5c		76.5c		92c		$1.09		$1.48		$1.92	
ounds Per Ft.	3.68		5.82		7.62		9.20		10.89		14.81		19.18	
	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv
liquippa, Pa. J5 (‡)	24	6	27	8.25	27	8.25	29	10.25	29	10.25	33.75	15	33.75	15
mbridge, Pa. N2	24	6	27	8.25	27	8.25	29	10.25	29	10.25	33.75	15	33.75	15
orain, O. N3 (*)	24	12.75	27	12.75	27	12.75	29	14.75	20	14.75	33.75	19.5	33.75	19.5
oungstown Y1 (‡)	24	7.50	27	9.25	27	9.25	29	11.25	29	11.25	33.75	16	33.75	16

LECTRIC WELD STANDARD PIPE, T & C

oungstown, R2 (**)	24	8.25	27	9.75	27	9.75	29	11.75	29	11.75	33.75	16.5	33.75	16.5

UTTWELD STANDARD PIPE, T & C

Carload discounts from list, %

ze—Inches	⅛		¼		⅜		3½		4	
st Per Ft.	5.5c		6c		6c		92c		$1.09	
ounds Per Ft.	0.24		0.42		0.57		9.20		10.89	
	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv	Blk	Galv
enwood, W. Va. W10	29.5	+0.25	23.25	+3.5	17.75	+7.75	33	14.25	33	14.25
utler, Pa. F6 (†)	30.5	1.25	25	+1.75	20	+5.5	..	....	..	....
tna, Pa. N2 (†)	30.5	1.25	25	+1.75	20	+5.5	33	14.25	33	14.25
aaron, Pa. M6 (‡)	29.5	—1.75	23	+2.25	18	+5.25	..	....	..	....
aaron, Pa. S4 (†)	30.5	1.25	25	+1.75	20	+5.5	..	....	..	....
arrows Pt., Md. B2	28.5	+0.75	23	+3.75	18	+7.50	..	....	..	....
oungstown R2 (**)	....	....	....	....	....	....	33	15.75	33	15.75
heatland, Pa. W9	28.5	+0.75	23	+3.75	18	+7.50	..	....	..	....

alvanized pipe discounts based on zinc price of: (†), 14c; (‡), 12.50c; (**), 11.50c; (*), , with discounts adjusted depending on price of zinc at time of shipment.

CLAD STEELS

(Cents per pound; add 4.7% to base price and extras)

	Plates		Sheets		
adding	Carbon Base		Carbon Base		Copper Base
ainless	10%	20%	10%	20%	Both Sides
02	....	....	19.75	26.24-27.50	77.00
4	25.00	29.50	24.50	27.50-27.77	77.00
09	30.50	35.00	....	....	....
10	36.50	41.00	....	....	144.00
16	29.50	34.00	26.00	35.92-36.50	....
17	34.50	39.00	....	....	....
18	33.50	38.00	....	....	....
21	26.50	31.00-32.00	23.00	33.00	111.00
47	27.50	32.00	24.00	33.50-33.83	130.00
05	21.25	27.75	....	....	....
10	20.75	27.25	....	....	....
ickel	33.55	45.15	....	....	....
nconel	41.23	54.18	....	....	165.00
onel	34.93	46.28	....	....	....
opper*	....	....	....	44.00	....

	Strip			
	Carbon Base			
	Cold-Rolled		Hot-Rolled	
	10%	Both Sides	10%	Both Sides
ickel	41.00	54.00	....	....
opper*	23.70	26.65	20.20	26.40

* Deoxidized. Production points for carbon base products: Stainless plates, sheets, Conshohocken, Pa. A3 and New Castle, Ind. I-4; stainless-clad plates, Claymont, Del. 22, Coatesville, Pa. L7 and Washington, Pa. J3; nickel, nconel, monel-clad plates, Coatesville L7; nickel, copper-ad strip, Carnegie, Pa. S18; Production point for copper-ase sheets is Carnegie, Pa. A13.

OLTS, NUTS

CARRIAGE, MACHINE BOLTS

F.o.b. midwestern plants; er cent off list for less than ase lots to consumers)

in. and shorter:	
½-in & smaller diam	15
⅝-in. & ⅝-in.	18.5
¾-in. and larger	17.5
onger than 6 in.:	
All diams.	14
ag bolts, all diams.:	
6 in. and shorter	23
over 6 in. long	21
bbed Necked Carriage	18.5
lank	34
low	34
tep, Elevator, Tap and Sleigh Shoe	21
ire Bolts	21
oller & Fitting-Up Bolts	31

NUTS

	Reg.	Hvy
.P. & C.P. square:		
½-in. & smaller	15	15
⅝-in. & ⅝-in.	12	6.5
¾-in.-1½-in.	9	1
1⅝-in. & larger	7.5	1
.P. Hex.:		
½-in. & smaller	26	22
⅝-in. & ⅝-in.	16.5	6.5
¾-in.-1½-in.	12	2
1⅝-in. & larger	8.5	2
C.P. Hex.:		
½-in. & smaller	26	22
⅝-in. & ⅝-in.	23	17.5
¾-in. & 1½-in.	19.5	12
1⅝-in. & larger	12	6.5

SEMIFINISHED NUTS

American Standard

(Per cent off list for less than case or keg quantities)

	Reg.	Hvy.
½-in. & smaller	35	28.5
⅝-in. & ⅝-in.	29.5	22
¾-in.-1½-in.	24	15
1⅝-in. & larger	13	8.5
		Light
⅞-in. & smaller		35
½-in. to ⅝-in.		28.5
¾-in. to 1½-in		26

SQUARE HEAD SET SCREWS

(Packaged; per cent off list)

1 in. diam x 6 in. and shorter	38
1 in. and smaller diam. x over 6 in.	26

COAL, CHEMICALS

Spot, cents per gallon, ovens

Pure benzol 36.00
Toluol, one deg...30.00-33.00
Industrial xylol ..30.00-33.50
Per ton, bulk, ovens
Sulphate of ammonia..$44-45;
Birmingham area, $49.50.
Cents per pound, ovens
Phenol, 40 (carlots, non-returnable drums) ..17.25

FLUORSPAR

Metallurgical grade, f.o.b. shipping point, in Ill., Ky., net tons, carloads, effective CaF_2 content 70%, $43; 60%, $40.
Imported, net ton, duty paid. metallurgical grade, $30-$35.

METALLURGICAL COKE

Price net ton

BEEHIVE OVENS

Connellsvl.fur. .$14.50-15.00
Connellsvl.fdy. ..16.50-17.50
New River foundry ... 20.80
Wise county, foundry.. 15.95
Wise county, furnace.. 15.20

OVEN FOUNDRY COKE

Kearney, N. J. ovens.$24.00
Everett, Mass., ovens
New England. del...*26.05
Chicago ovens 24.50
Chicago, del. 26.00
Terre Haute, ovens .. 24.05
Milwaukee, ovens 25.25
Indianapolis, ovens .. 24.25
Chicago, del. 28.12
Cincinnati, del. 25.85
Painesville, O., ovens. 25.50
Cleveland, del. 27.43
Erie, Pa., ovens 25.00
Birmingham, ovens .. 21.65
Cincinnati, del. 26.58
LoneStar,Tex., ovens.. 18.50
Philadelphia, ovens .. 23.95
Swedeland, Pa., ovens 23.85
St. Louis, ovens
St. Louis, del. 26.00
Portsmouth, O., ovens 24.00
Cincinnati, del. 26.62
Detroit, ovens 25.50
Detroit, del. 26.50
Buffalo, del. 28.08
Flint, del. 28.23
Pontiac, del. 27.06
Saginaw, del. 28.58

*Or within $4.55 freight zone from works.

NOTE: Current prices on boiler tubes, electrodes and rivets appeared on page 159, Mar. 2.

STAINLESS STEEL

(Add 4.7% on base price and extras)

Type	Sheets	C.R. Strip	Bars Wire Structurals
301...	41.00	34.00	31.25
302...	41.25	36.75	31.50
303...	43.25	40.25	34.00
304...	43.25	38.75	33.00
309...	56.00	55.00	44.75
316...	57.00	59.00	49.25
321...	49.25	48.25	37.00
347...	53.75	52.25	41.50
410...	36.50	30.50	25.75
416...	37.00	37.00	26.25
420...	44.00	47.00	31.25
430...	39.00	31.00	26.25
501...	27.50	26.00	14.25
502...	28.50	27.00	15.25

Balt., Types 301-347 and 430 sheets, except 303 and 309 E2.
Brackenridge, Pa. sheets A4 quotes slight variations on Types 301-347.
Bridgeville, Pa., bars, wire, sheets & strip U4.
Butler, Pa. sheets and strip except Types 303, 309, 416, 420, 501 & 502, A10.
Carnegie, Pa., sheets and strip except Types 303, 416, 501 & 502 S18.
Cleveland, strip A7.
Detroit, strip M1 quotes 34.00c on Type 301; 36.50c, 302; 38.50c, 304; 58.50c, 316; 52.00c, 347; 30.50c, 410; 31.00c, 430.
Dunkirk, N. Y., bars, wire A4 quotes slight variations on Types 301-347.
Duquesne, Pa., bars U5.
Fort Wayne, Ind., bars and wire,except Types 501 & 502 J6 quotes slight variations on Types 301-347.
Gary, Ind., sheets except Type 416 U5.
Harrison, N. J., strip and wire C18.
Harrison, N. J., wire, Type 302, 33.00c; Type 304, 34.50c; Type 316, 51.50c, including 4.7% increase on base price.
Massillon, O., all items, R2.
McKeesport, Pa., strip, Type 410; bars & wire, Types 410 through 430 and 31.25c on Type 302, 33.75c on 303, 32.75c on 304, 48.75c on 316, 36.75c on 321, 41.25c on 347 F2.
McKeesport, Pa., bars, sheets except Type 416 U5.
Middletown, O., sheets and strip except Types 303, 416, 420, 501 and 502 A10.
Midland, sheets & strip C18.
Munhall, Pa., bars U5.
Muncie, Ind., wire I-7 quotes types 302, 304, 430.
Pittsburgh, sheets C18.
Reading, Pa., strip except 34.25c on Type 301 and 56.00c on 309; bars, except 31.50c on Type 301 and 45.25c on 309 C4.
Sharon, Pa., strip, except Types 303, 309, 416, 501, 502 and 34.25c on Type 301 S3.
So. Chicago, Ill., bars & structurals U5.
Syracuse, N. Y., bars, wire & structurals C18.
Titusville, Pa., bars U4.
Wallingford, Conn., strip W2 quotes 0.25c higher.
Washington, Pa., bars, sheets & strip, except 0.25c higher on Type 301 J3.
Washington, Pa., Types 301 through 347 sheets & strip except 303, 309; 316 sheets 62.00c, strip 64.00c W4.
Watervliet, N. Y., structurals & bars A4 quotes variations on Types 301-347.
Waukegan, bars & wire A7.
West Leechburg, Pa., strip, A4 quotes slight variations on Types 301-347.
Youngstown, strip except Types 303, 309, 316, 416, 501 and 502 and 34.25c on Type 301 C8.

METAL POWDERS

(Per pound, f.o.b. shipping point in ton lots for minus 100 mesh, except as otherwise noted)

	Cents
Sponge iron:	
98+% Fe, annealed	18.00
Unannealed	14.50
Swedish, c.l.f. N.Y., c.l., in bags	10.90
Electrolytic iron:	
Annealed, 99.5% Fe.	42.50
Unannealed (99+% Fe)	36.50
Unannealed (99+% Fe) (minus 325 mesh)	53.50
Powder Flakes	48.50
Carbonyl Iron:	
97.9-99.8% size 5 to 10 microns	.83.00-148.00
Aluminum:	
Carlots, freight allowed	31.00
Atomized, 500 lb drums, freight allowed	33.00
Antimony, 500 lb lots.	71.00
Brass, 20-ton lots.	31.00-34.25
Bronze, 10-ton lots	51.25-60.00
Phosphor-Copper, 20-ton lots	50.00
Copper:	
Electrolytic	37.25
Reduced	35.25
Lead	7.50*
Magnesium	.75.00-85.00
Manganese:	
Minus 100 mesh	57.00
Minus 35 mesh	52.00
Minus 200 mesh	62.00
Nickel unannealed	86.00
Nickel-Silver 5-ton lots	46.00
Silicon	38.50
Solder	8.50*
Stainless Steel, 302	83.00
Zinc, 10-ton lots.	18.00-31.00
Tungsten	Dollars
Melting grade, 99% 60 to 200 mesh:	
1000 lb and over	5.85
Less than 1000 lb	6.00
Molybdenum:	
99.9%, minus 200 mesh	3.24
Chromium, electrolytic 99.9% Cr min.	3.50

* Plus cost of metal.

"... More than 50% of our employees are on the Payroll Savings Plan ..."

PAUL W. JOHNSTON
President, Erie Railroad

"We on the Erie Railroad are extremely proud that 50% of our employees are on the Payroll Savings Plan for U.S. Defense Bonds. These thousands of employees are regularly providing for their own future security and at the same time contributing to the strength of our national defense. The American habit of thrift and regular purchase of U.S. Defense Bonds Shares in America are evidences of good, sound citizenship."

Good, sound citizenship . . . the American habit of thrift . . . a belief that a strong America is a secure America . . . a management that makes the Payroll Savings Plan available to *all* its employees—these are the reasons why more than 50% of Erie Railroad employees are enrolled in the Payroll Savings Plan.

For the same four reasons, more than 7,500,000 employed men and women in thousands of other companies are active members of the Payroll Savings Plan —their take-home savings in the form of U.S. Defense Bonds total more than $150,000,000 per month.

Is your company in the "more than 50% participation" group? If it isn't, please bring this page to the attention of your top executive. Point out to him—

Two Simple Steps to a Successful Payroll Savings Plan

1. Phone, wire or write to Savings Bond Division, U.S. Treasury Department, Suite 700, Washington Building, Washington, D. C.
2. Your State Director, Savings Bond Division, will show your company how to conduct a simple person-to-person canvass that will put a Payroll Savings Application Blank in the hands of *every* employee.

That is all management has to do. Your employees will do the rest. They, like the employees of the Erie Railroad, want to provide for their personal security and at the same time do their part in helping to keep America strong.

The United States Government does not pay for this advertisement. It is donated by this publication in cooperation with the Advertising Council and the Magazine Publishers of America.

STEEL
The Weekly Magazine of Metalworking

WAREHOUSE STEEL PRODUCTS

presentative prices, cents per pound, subject to extras, f.o.b. warehouse. City delivery charges are 20 cents per 100 lb except: New York, 30 cents; Philadelphia, 25 cents; Birmingham, Cincinnati, San Francisco, St. Paul, 15 cents.)

	SHEETS			STRIP		BARS			Standard Structural Shapes	PLATES	
	H.R. 18 Ga., Heavier*	C.R.	Gal. 10 Ga.†	H.R.*	C.R.*	H.R. Rds.	C.F. Rds.‡	H.R. Alloy 4140††[5]		Carbon	Floor
dimore	5.81	7.17	8.32	6.42	...	6.41	7.18	11.17	6.47	6.47	7.70
ton	6.51	7.36	8.49	6.55	...	6.42	7.47	11.18	6.56	6.75	7.98
falo	5.80	6.65	8.41	6.21	...	5.90	6.95	11.07	6.08	6.30	7.67
ningham ...	5.80	6.65	7.70[2]	5.80	...	5.80	8.65	...	5.95	6.10	8.65
cago	5.80	6.65	7.95	5.83	...	5.83	6.56	10.65	5.95	5.95	7.18
cinnati	6.08	6.67	8.21	6.09	...	6.08	7.11	11.02	6.37	6.42	7.55
veland	5.80	6.65	8.09	6.00	...	5.89	6.66	10.79	6.28	6.12	7.51
roit	6.23	6.46	8.44	6.08	7.495	6.12	7.10	10.92	6.42	6.47	7.52
ston	6.74	...	8.67	6.89	...	6.98	...	...	6.82	6.78	8.16
seyCity,N.J..	6.35	7.27	8.47	6.75	...	6.59	7.78	9.54	6.39	6.60	8.01
Angeles ...	6.60	8.45	9.55	6.75	11.20	6.60	8.35	12.05	6.60	6.65	8.90
waukee	5.97	6.82	8.12	6.00	...	6.00	6.83	10.82	6.12	6.12	7.35
ine, Ill.	6.16	7.00	8.30	6.19	...	6.18	6.91	...	6.30	6.30	...
wark, N. J...	6.62	7.41	8.58	6.72	...	6.79	7.46	...	6.70	6.78	7.18
w York	6.36	7.37	8.47	6.56	...	6.69	7.63	11.14	6.49	6.70	8.11
folk, Va. ..	7.60	...	...	...	...	6.44	8.70	...	7.25	6.64	7.33
adelphia ...	6.16	7.18	8.30	6.50	8.30	6.47	7.50	10.84	6.22	6.29	7.42
sburgh	5.80	6.65	7.95	5.94	...	5.83	6.66	10.65	5.95	5.95	7.18
land, Oreg..	7.80	9.05	9.75	7.60	...	7.35	9.40	...	7.30	7.30	9.25
mond, Va. .	6.14	6.95	8.68	6.53	...	6.30	7.63	...	6.58	6.68	7.80
Louis	6.10	6.94	8.25	6.14	...	6.13	6.96	10.95	6.35	6.40	7.58
Paul	6.47	7.31	8.61	6.50	...	6.49	7.32	...	6.61	6.61	7.84
Francisco..	6.85	8.15	9.45	6.70	...	6.60	8.40	12.00	6.45	6.70	8.85
ttle-Tacoma.	7.16	8.24	9.30	7.45	...	6.88	9.37	11.90§	6.63	7.04	8.90
kane (city).	7.60	9.40	10.66	7.65	...	7.10	9.70	11.90	7.00	7.10	9.15
shington	6.31	7.61	8.90	6.89	...	6.90	8.03	...	6.93	6.95	8.17

Prices do not include gage extras; † prices include gage and coating extras, except Birmingham (coating extra excluded) and Los Angeles (gage a excluded); ‡ includes 25-cent special bar quality extra; § as rolled; †† as annealed. Base quantities, 2000 to 9999 lb except as noted. Cold-ed strip, 2000 lb and over; cold-finished bars, 2000 lb and over; [2]—500 to 1499 lb; [5]—1000 to 1999 lb.

Ores

Lake Superior Iron Ore

ss ton, 51½% (natural), lower lake ports.
range bessemer $9.45
range nonbessemer 9.30
abi bessemer 9.20
abi nonbessemer 9.05
h phosphorus 9.05
fter adjustment for analysis, prices will be eased or decreased as the case may be for eases or decreases after Dec. 1, 1950, in olicable lake vessel rates, upper lake rail ights, dock handling charges and taxes reon.

Eastern Local Iron Ore

Cents per unit del. E. Pa.
ndry and basic 56-62% concentrates ntract 17.00

Foreign Iron Ore

Cents per unit, c.i.f. Atlantic ports
dish basic, 60 to 68%:
pot ..... nom.
ong-term contract 24.00
th African hematites (spot) .. 26.00-28.00
zilian iron ore, 67-69% (spot) 32.00

Tungsten Ore

Net ton unit, duty paid
eign wolframite and scheelite, per et ton unit $65.00
nestic scheelite, mines 65.00

Manganese Ore

nganese, 48% nearby, $1.18-1.22 per long t unit, c.i.f. U. S. ports, duty for buyer's ount; shipments against old contracts for 4% ore are being received from some sources 85c-87c.

Chrome Ore

ss ton, f.o.b. cars, New York, Philadel-a, Baltimore, Charleston, S. C., plus ocean ght differential for delivery to Portland, g., or Tacoma, Wash.

Indian and African

48% 2.8:1 ..... $39.00-$42.00
48% 3:1 ..... 44.00-45.00
48% no ratio 30.00-32.00

South African Transvaal

48% no ratio ..... $27.00-$28.00
48% no ratio 34.00-35.00

Brazilian

48% 2.5:1 lump ..... nom.

Domestic
(Rail nearest seller)

48% 3:1 ..... $39.00

Molybdenum

phide concentrates per lb. molyb-enum content, mines $1.00

REFRACTORIES

Fire Clay Brick

High-Heat Duty: Pueblo, Colo., $89.00; Ashland, Grahn, Hayward, Hitchins, Haldeman, Olive Hill, Ky., Athens, Troup, Tex., Beech Creek, Clearfield, Curwensville, Lochhaven, Lumber, Orviston, West Decatur, Pa., Bessemer, Ala., Farber, Mexico, St. Louis, Vandalia, Mo., Ironton, Oak Hill, Parral, Portsmouth, O., Ottawa, Ill., Stevens Pottery, Ga., Woodbridge, N. J., $99.30 Salina, Pa., $104.55; Niles, O., $109; Los Angeles, Pittsburg, Calif., $132.30.

Silica Brick

Standard: Alexandria, Claysburg, Mt. Union, Sproul, Pa., Ensley, Ala., Portsmouth, O., $99.30; Hays, Pa., $105.10; Niles, O., $107; E. Chicago, Ind., Joliet, Rockdale, Ill., $109.70; Cutler, Utah, $116.55; Los Angeles, $122.85.

Insulating Fire Brick

2300° *F:* Massillon, O., $178.50; Clearfield, Pa., $179.55; Augusta, Ga., Beaver Falls, Zelienople, Pa., Mexico, Mo., $186.90.

Ladle Brick

Dry Pressed: Bessemer, Ala., $64.60; Alsey, Ill., Chester, New Cumberland, W. Va., Freeport, Johnstown, Merrill Station, Pa., Wellsville, O., $69.30; Mexico, Mo., $73.50; Clearfield, Pa., Portsmouth, O., $83; Perla, Ark., $92.40; Los Angeles, $110.25; Pittsburg, Calif., $111.30.

Sleeves

Reesdale, Pa., $127; Johnstown, Pa., $127.30; Clearfield, Pa., $135; St. Louis, $138; Athens, Tex., $140.90.

Nozzles

Reesdale, Pa., $203.20; Johnstown, Pa., $208.40; Clearfield, Pa., $219.45; St. Louis, $224.65; Athens, Tex., $225.20.

Runners

Reesdale, Pa., $158.20; Johnstown, Pa., $161.70; Clearfield, Pa., $168.60; St. Louis, $170.30; Athens, Tex., $174.40.

High-Alumina Brick

50 *Per Cent:* Clearfield, Pa., St., Louis, Mexico, Mo., $166.30; Danville, Ill., $169.30.
60 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., $210.20; Danville, Ill., $213.20.
70 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., $244.85; Danville, Ill., $247.85; Clearfield, Pa., $252.

CALCIUM ALLOYS

Calcium-Manganese-Silicon: (Ca 16-20%, Mn 14-18% and Si 53-59%). Contract, carload, lump, bulk 20.0c per lb of alloy, carload packed 20.8c, ton lot 22.3c, less ton 23.3c. Delivered. Spot add 0.25c..

Calcium-Silicon: (Ca 30-33%, Si 60-65%, Fe 1.50-3%). Contract, carload, lump, bulk 10.0c per lb of alloy, carload packed 20.2c, ton lot 22.1c, less ton 23.6c. Deld. Spot add 0.25c.

ZIRCONIUM ALLOYS

12-15% Zirconium Alloy: (Zr 12-15%, Si 30-43%, Fe 40-45%, C 0.20% max.). Contract, c.l. lump, bulk 7.0c per lb of alloy, c.l. packed 7.75c, ton lot 8.5c, less ton 9.35c. Delivered. Spot, add 0.25c.

35-40% Zirconium Alloy: (Zr 35-40%, Si 47-52%, Fe 8-12%, C 0.50% max.). Contract, carload, lump, packed 20.25c per lb of alloy, ton lot 21c, less ton 22.25c. Freight allowed. Spot add 0.25c.

BRIQUETTED ALLOYS

Chromium Briquets: (Weighing approx. 3¾ lb each and containing exactly 2 lb or Cr). Contract, carload, bulk, 14.50c per lb of briquet, carload packed 15.2c, ton 16.0c, less ton 16.9c. Deld. Add 0.25c for notching. Spot, add 0.25c.

Ferromanganese Briquets: (Weighing approx. 3 lb and containing exactly 2 lb of Mn). Contract, carload, bulk 12.45c per lb of briquet, c.l. packaged 13.25c, ton lot 14.05c, less ton 14.95c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Silicomanganese Briquets: (Weighing approx. 3½ lb and containing exactly 2 lb of Mn and approx. ½ lb of Si). Contract, c.l. bulk 12.65c, per lb of briquet, c.l. packed 13.45c, ton lot 14.25c, less ton 15.15c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Silicon Briquets: (Large size — weighing approx. 5 lb and containing exactly 2 lb of Si). Contract, carload, bulk 6.95c per lb of briquet, c.l. packed 7.75c, ton lot 8.85c, less ton 9.45c. Delivered. Spot, add 0.25c.

(Small size—weighing approx. 2½ lb and containing exactly 1 lb of Si). Carload, bulk 7.1c, c.l. packed 7.9c, ton lot 8.7c, less ton 9.6c. Delivered. Add 0.25c for notching, small size only. Spot, add 0.25c.

Molybdic-Oxide Briquets: (Containing 2½ lb of Mo each) $1.14 per pound of Mo contained, f.o.b. Langeloth, Pa.

Note: Current prices on chromium, silicon, vanadium, boron and tungsten alloys appeared on page 161, Mar. 2 issue; manganese and titanium alloys and "other" ferroalloys, page 147, Feb. 16.

IRON AND STEEL SCRAP

Open market prices as reported to STEEL, Mar. 5, 1953; gross tons, except as noted. Changes shown in *italics*.

STEELMAKING SCRAP COMPOSITE

Mar. 5	$45.00
Feb. 26	43.00
Feb. 1953	43.00
Mar., 1952	43.00
Mar., 1948	40.21

Based on No. 1 heavy melting grade at Pittsburgh, Chicago and eastern Pennsylvania.

PITTSBURGH

(Including brokers' Commission)

No. 1 heavy melting...	44.00*
No. 2 heavy melting...	44.00*
No. 1 bundles	45.00*
No. 2 bundles	42.00*
No. 1 busheling	45.00*
Machine shop turnings.	30.00-31.00*
Mixed borings, turnings	36.00-37.00*
Short shovel turnings..	36.00-37.00*
Cast iron borings	38.00-39.00*
Cut structurals	48.00-51.00*
Heavy turnings	44.00*
Punchings & plate scrap	47.50*
Electric furnace bundles	46.00*
Cast Iron Grades (Delivered)	
No. 1 cupola	47.00-49.00
Charging box cast	45.00-46.00
Heavy breakable cast..	45.00
Unstripped motor blocks	43.00-44.00
No. 1 machinery cast..	51.00-52.00
Railroad Scrap	
No. 1 R.R. heavy melt.	47.00
Rails, 2-ft. and under.	53.00
Rails, 18-in. and under	55.00
Rails, random lengths.	49.00

*Plus applicable freight spring-boards from other areas.

CLEVELAND

(Delivered consumer plant; including broker's commission)

No. 1 heavy melting...	44.00-44.50*
No. 2 heavy melting...	43.00-43.50*
No. 1 bundles	44.00-44.50*
No. 2 bundles	43.00-43.50*
No. 1 busheling	44.00-44.50*
Machine shop turnings.	31.00-32.00*
Mixed borings, turnings	35.50-36.00*
Short shovel turnings..	35.50-36.00*
Cast iron borings	35.50-36.00*
Low phos.	49.00-50.00*
Alloy free, short shovel turnings	37.00-38.00
Electric furnace bundles	46.00-46.50*
Cast Iron Grades	
No. 1 cupola	49.00
Charging box cast	47.00
Stove plate	46.00
Heavy breakable cast..	45.00
Unstripped motor blocks	38.00-38.50
Brake shoes	41.00
Clean auto cast	52.00
No. 1 wheels	47.00
Burnt cast	41.00
Drop broken machinery	52.00
Railroad Scrap	
No. 1 R.R. heavy melt.	46.00-47.00
R. R. Malleable	50.00-51.00
Rails, 3-ft. and under.	51.00-52.00
Rails, 18-in. and under	53.00-54.00
Rails, random lengths.	49.00-50.00
Cast steel	51.00-52.00
Railroad specialties	51.00-52.00
Uncut tires	51.00-52.00
Angles, splice bars	51.00-52.00
Rails, rerolling	53.50-54.00

*Plus applicable freight spring-boards from other areas.

YOUNGSTOWN

(Delivered consumer plant; including broker's commission)

No. 1 heavy melting...	45.00-45.50*
No. 2 heavy melting...	44.00-44.50*
No. 1 bundles	45.00-45.50*
No. 2 bundles	44.00-44.50*
Machine shop turnings.	32.00-33.00*
Short shovel turnings..	36.50-37.00*
Cast iron borings	36.50-37.00*
Low phos.	50.00-51.00*
Electric furnace bundles	47.00-47.50*
Railroad Scrap	
No. 1 R.R. heavy melt.	46.00-47.00

*Plus applicable freight spring-boards from other districts.

NEW YORK

(Brokers' Buying Prices)

No. 1 heavy melting...	$40.50
No. 2 heavy melting...	35.50
Machine shop turnings.	25.50
Mixed borings, turnings	29.50
Cast Iron Grades	
No. 1 cupola	40.00
Unstripped motor blocks	32.00-33.00

PHILADELPHIA

(Delivered consumer plant)

No. 1 heavy melting...	48.50‡
No. 2 heavy melting...	43.00-43.50
No. 1 bundles	48.50‡
No. 2 bundles	nominal
No. 1 busheling	44.50
Machine shop turnings.	33.50-34.00
Mixed borings, turnings	37.50-38.00
Short shovel turnings..	37.50-38.00
Cast Iron Grades	
No. 1 cupola	44.00-45.00
Charging box cast	45.00
Heavy breakable cast..	47.50-48.00
Unstripped motor blocks	39.00
Drop broken machinery	50.00

‡Including low phos. differential.

CINCINNATI

No. 1 heavy melting...	42.00
No. 2 heavy melting...	42.00
No. 1 bundles	43.00
No. 2 bundles	42.00
No. 1 busheling	43.00
Machine shop turnings.	33.00
Mixed borings, turnings	37.00
Short shovel turnings..	37.00
Cast iron borings	37.00
Cast Iron Grades (F.o.b. Shipping Point)	
No. 1 cupola	49.00
Charging box cast	47.00
Stove plate	46.00
Heavy breakable cast.	45.00
Unstripped motor blocks	43.00
Brake shoes	41.00
Clean auto cast	52.00
Drop broken machinery	52.00
Railroad Scrap	
No. 1 R.R. heavy melt.	45.00
Malleable	55.00
Rails, 18-in. and under	53.00
Rails, random lengths.	47.00
Rails, rerolling	52.00

DETROIT

No. 1 heavy melting...	39.00-40.00
No. 2 heavy melting...	38.00-39.00
No. 1 bundles	40.00-41.00
No. 2 bundles	38.00-39.00
No. 1 busheling	40.00-41.00
Machine shop turnings.	26.00-27.00
Mixed borings, turnings	28.00-29.00
Short shovel turnings..	28.00-29.00
Punchings & plate scrap	44.00-46.00
Cast Iron Grades	
No. 1 cupola	47.50
Charging box cast	40.00-42.00
Stove plate	45.00
Unstripped motor blocks	32.00-35.00
Clean auto cast	50.00
Malleable	48.00

BUFFALO

No. 1 heavy melting...	$43.00-44.00
No. 2 heavy melting...	42.00-43.00
No. 2 bundles	42.00-43.00
No. 1 bundles	43.00-44.00
No. 1 busheling	43.00-44.00
Machine shop turnings.	32.50-33.00
Mixed borings, turnings	36.50-37.00
Short shovel turnings.	36.50-37.00
Low phos.	48.50-49.00
Cast Iron Grades (F.o.b. Shipping Point)	
No. 1 cupola	42.50-43.00
Drop broken machinery	45.50-46.00

BOSTON

(Brokers' Buying Prices; f.o.b. shipping points)

No. 1 heavy melting...	34.17
No. 2 heavy melting...	31.17
No. 1 bundles	33.17
No. 2 bundles	31.17
Machine shop turnings.	24.17
Mixed borings, turnings	22.17
Short shovel turnings..	28.17
No. 1 cast	35.00-36.00
Mixed cupola cast	32.00-33.00
No. 1 machinery cast..	47.00-49.00

CHICAGO

(Including broker's commission)

No. 1 heavy melting...	42.50
No. 2 heavy melting...	40.50
No. 1 bundles	43.50
No. 2 bundles	39.00
No. 1 busheling	43.50
Machine shop turnings.	29.00-39.00
Mixed borings, turnings	31.50-32.50
Short shovel turnings..	31.50-32.50
Cast iron borings	31.50-32.50
Cut structurals	46.50
Heavy turnings	41.50
Electric furnace bundles	45.50
Cast Iron Grades	
No. 1 cupola	42.00-44.00
Stove plate	42.00-43.00
Unstripped motor blocks	38.00-40.00
Clean auto cast	48.00-50.00
Drop broken machinery	46.00-48.00
Railroad Scrap	
No. 1 R.R. heavy melt.	45.50-47.50
R.R. Malleable	46.00-48.00
Rails, 2-ft. and under.	51.50
Rails, 18-in. and under	53.50
Angles, splice bars	50.50
Rails, rerolling	52.50-54.50

BIRMINGHAM

No. 1 heavy melting...	38.00
No. 2 heavy melting...	38.00
No. 1 bundles	39.00
No. 2 bundles	38.00
No. 2 busheling	35.00
Machine shop turnings.	29.00
Mixed borings, turnings	33.00
Short shovel turnings..	30.00-32.00
Cast iron borings	30.00-32.00
Cut structurals	42.00
Heavy turnings	38.00
Punchings & plate scrap	41.50
Electric furnace bundles	41.00
Cast Iron Grades (F.o.b. Shipping Point)	
No. 1 cupola	44.00-45.00
Charging box cast	39.00-40.00
Stove plate	42.00
Heavy breakable cast.	36.00-37.00
Unstripped motor blocks	35.00-36.00
Brake shoes	41.00
Clean auto cast	52.00
No. 1 wheels	47.00
Burnt cast	41.00
Drop broken machinery	42.00-43.00
Railroad Scrap	
No. 1 R.R. heavy melt.	41.00
Malleable	55.00
Rails, 3-ft. and under.	46.00
Rails, 18-in. and under	49.00
Rails, random lengths.	49.00-51.00
Cast steel	44.00
Uncut tires	43.00
Angles, splice bars	46.00
Rails, rerolling	48.00

ST. LOUIS

No. 1 heavy melting...	40.00
No. 2 heavy melting...	40.00
Machine shop turnings.	28.00
Short shovel turnings..	32.00
Cast Iron Grades	
No. 1 cupola	43.00-45.00
Charging box cast	39.00-41.00
Heavy breakable cast..	36.00-38.00
Unstripped motor blocks	33.00-35.00
Brake shoes	41.00
Clean auto cast	46.00-47.00
Burnt cast	37.00-39.00
Railroad Scrap	
Malleable	40.00
Rails, 3-ft. and under.	55.00-57.00
Rails, random lengths.	52.00-54.00
Uncut tires	48.00
Angles, splice bars	49.00
Rails, rerolling	50.00-52.00

SEATTLE

(Delivered consumer plant)

No. 1 heavy melting...	34.00
No. 2 heavy melting...	29.00
No. 1 bundles	33.00
No. 2 bundles	27.00
Machine shop turnings.	25.00
Mixed borings, turnings	25.00
Short shovel turnings.	25.00
Electric furnace, No. 1	40.41
Cast Iron Grades (F.o.b. Shipping Point)	
No. 1 cupola	40.00
Heavy breakable cast.	36.00-38.00
Unstripped motor blocks	28.41
No. 1 wheels	47.00
Railroad Scrap	
Rails, random lengths.	38.41

SAN FRANCISCO

No. 1 heavy melting...	30.00
No. 2 heavy melting...	26.00
No. 1 bundles	29.00
No. 2 bundles	24.00
No. 1 busheling	30.00
Machine shop turnings.	12.00
Mixed borings, turnings	29.00
Short shovel turnings..	29.00
Cast iron borings	29.00
Cut structurals	38.00
Heavy turnings	34.00
Punchings & plate scrap	37.50
Electric furnace bundles	37.00
Cast Iron Grades	
No. 1 cupola	37.50
Charging box cast	47.00
Stove plate	46.00
Heavy breakable cast.	45.00
Unstripped motor blocks	41.00
Brake shoes	41.00
Clean auto cast	52.00
No. 1 wheels	47.00
Burnt cast	41.00
Drop broken machinery	52.00
Railroad Scrap	
No. 1 R.R. heavy melt.	37.00
Malleable	55.00
Rails, 3-ft. and under.	42.00
Rails, 18-in. and under	45.00
Rails, random lengths.	39.00
Cast steel	40.00
Uncut tires	39.00
Angles, splice bars	42.00
Rails, rerolling	44.00

LOS ANGELES

No. 1 heavy melting...	30.00
No. 2 heavy melting...	26.00
No. 1 bundles	29.00
No. 2 bundles	24.00
Machine shop turnings.	12.00
Cast Iron Grades (F.o.b. Shipping Point)	
No. 1 cupola	44.00

HAMILTON, ONT.

(Delivered Prices)

Heavy Melt.	$35.00
No. 1 Bundles	35.00
No. 2 Bundles	35.00
Mechanical Bundles	31.00
Mixed Steel Scrap	31.00
Mixed Borings, Turnings	28.00
Rails, Remelting	35.00
Rails, Rerolling	38.00
Busheling	28.00
Busheling new factory: Prep'd	33.00
Unprep'd	31.00
Short Steel Turnings	28.00
Cast Iron Grades†	
No. 1 Machinery Cast..	50.00

† F.o.b., shipping point.

OLD CEILING BASE PRICES

Basing point ceiling prices per gr ton from which maximum shipp prices are computed on scrap dealer and industrial origin; from which ceiling on-line and ing delivered prices are compu on scrap of railroad origin.

Basing Point	Grade 1 No. 1 Bundles Dealer, Industrial	No. 1 He Me Ra ro
Alabama City, Ala.	$39.00	$4
Ashland, Ky.	42.00	4
Atlanta, Ga.	39.00	4
Bethlehem, Pa.	42.00	4
Birmingham, Ala.	39.00	4
Brackenridge, Pa.	44.00	4
Buffalo, N. Y.	43.00	4
Butler, Pa.	44.00	4
Canton, O.	44.00	4
Chicago, Ill.	42.50	4
Cincinnati, O.	43.00	4
Claymont, Del.	42.50	4
Cleveland, O.	43.00	4
Coatesville, Pa.	42.50	4
Conshohocken, Pa.	42.50	4
Detroit, Mich.	41.15	4
Duluth, Minn.	40.00	4



Self-Contained, Triple Compression

LOGEMANN SCRAP PRESSES

...give you compact, high density bales...at low cost!

OGEMANN

Also specializes in

VASTE PAPER BALERS

for Industrial Applications

and in

IGH PRESSURE PUMPS

. for pressures from 2000 to ,000 p.s.i. for press opera- n, hydrostatic tests, and nilar applications.

You Conserve Floor Space and Piping with this Compact Installation

Here is a combination of tried and tested units expertly assembled to reduce floor space requirements to a minimum. Features include a big box, high speed operation, and high density bales. Various box sizes are available to meet maximum scrap and minimum bale dimensions.

Also available are various sizes and types of pumps and operating valves to meet output requirements. Logemann Scrap Presses can be equipped with loading hopper in which the scrap charge can be prepared while the press is going through the operations on the preceding bale. Compressed bales are delivered at floor level for ejection to conveyor, steel chute, or into accumulation pit.

Write for Complete Details

LOGEMANN BROTHERS CO.

3126 W. BURLEIGH STREET • MILWAUKEE 10, WISCONSIN

They

KEEP PLANTS RUNNING!

Bunting Precision Bronze Bars

Protection against shut-downs is constantly provided, right in your own community, by your Bunting Distributor and Bunting Precision Bronze Bars. Factory machined on all surfaces, Bunting Bronze Bars save you 25% of purchased metal, 50% of machining time and wear on costly tools.

The Bunting Distributor

Your Bunting Distributor is an industrial distributor or a specialist in certain industrial items. You will find him listed in the classified section of your telephone book—most likely under the heading Bars, bronze or Bearings, bronze. If he is the leading distributor, he almost certainly is the Bunting Distributor. He carries in stock, for your money saving convenience, completely machined and finished Bunting Standard Stock Industrial Bearings, Electric Motor Bearings and Precision Bronze Bars in a complete range of sizes meeting all your usual production and maintenance needs. Ask him for catalog.

N E W S

DISTRIBUTORS EVERYWHERE

Bunting®

BRONZE BEARINGS • BUSHINGS • PRECISION BRONZE BARS

THE BUNTING BRASS & BRONZE COMPANY • TOLEDO 1, OHIO • BRANCHES IN PRINCIPAL CITIES

Order may not return to copper market for 60 days. Don't expect a realistic price level until all allocation controls are off and consumers' pressing demands are met

T LEAST 60 days will pass before rder returns to the copper market. No realistic price level will come ll allocation controls come off and ressing demands from consumers are et. That's trade consensus at the oment, though a surprising number experts won't even venture a guess n future trends.

Actually copper, copper wire and ass markets have shown remarkble recuperation in the 12 days since rice walls were blasted, considering e artificial structure had been built p in over two years of control.

Rambling Rates — Multiplicity of rices under control was bush league ompared to the present colossus. very seller has his own idea of copper price, and until a definite trend established, he'll sit tight. Present ange of copper extends from 27.50 nts to 32 cents for domestic and p to 36.50 cents for foreign metal. ake copper isn't even quoted. Some ales of domestic metal have been eported at above 32 cents, but they re exceptional cases now.

Lowest domestic quotation was set y Kennecott at 27.50, in an apparent ttempt to set a conservative market one. Phelps Dodge lists 28.50 and naconda 32.00. None of Anaconda's omestic copper is sold on the maret though; for 30 years its entire J. S. output has gone to its subsidary American Brass Co. Custom melters' prices are about standard t 32.00 cents; one company posted 6.00 cents for two days but came ack to earth when it saw which ay the wind was blowing.

Out in the Cold—Independent fabricators should make friends with copper salesmen if they want domestic metal. Now that the 60-40 breakdown of domestic-foreign authorizations is defunct, domestic producers will certainly take care of their fabricating affiliates first. Independents may be forced to get all their supplies from abroad.

Another complication is the current practice of pricing copper at date of delivery, making it tough for manufacturers to quote firm selling prices in trying to land new orders. Some brokers are making capital of this situation by offering fixed prices on nearby and forward shipments. Dealers' price is 33.75 for April and 32.50 for May-June deliveries.

Follow the Leader—Brass mills and copper wire mills all have new and higher price lists. Anaconda Wire & Cable Co. and American Brass Co. base quotations on an average copper price of 33.80 cents. Kennecott Wire & Cable Co. and Chase Brass & Copper Co. calculate on an average of 31.10 cents. Phelps Dodge Copper Products Corp. bases price increases on an average price of 32.10 cents.

Such large independent brass mills as Bridgeport Brass Co., Revere Copper & Brass Inc. and Scovill Mfg. Co. followed the price trend set by Chase. Full listings of new prices on copper and brass rolled, drawn and extruded products can be found on the following page.

STEEL'S Metal Price Averages for Feb., 1953

(Cents per pound)

Electrolytic Copper, del. Conn.	25.14
Lead, St. Louis	13.30
Prime Western Zinc, E. St. Louis	11.43
Straits Tin, New York	121.50
Primary Aluminum Ingots, del.	20.50
Antimony, f.o.b. Laredo, Tex.	34.50
Nickel, f.o.b. refinery	60.00
Silver, New York	85.25

Free Trading Nears in Copper

Return of free trading in copper on the London Metal Exchange isn't far off. The U. K. must give Rhodesian producers 6-months' notice of termination of buying agreement before it's done though. Several thousand tons of Rhodesian copper have been diverted to the U. S. to take advantage of the price differential. The British Ministry of Materials holds large tonnage of copper —estimated at close to 150,000 tons.

Zinc Tumbles Again

The price of zinc has declined a quarter of a cent per pound to 11 cents in E. St. Louis. And prime western demand is soft, but automotive activity sustains special high grade at a good level. Foreign zinc still undersells domestic metal by a half-cent or more, and there's plenty of zinc from overseas to dispose of. Imports last year of 504,067 tons topped 1951 by 152,646 tons and the year was close to record 1943.



Furnaces Anneal Brass

When close control of physical properties is essential, special lots of brass that have been slit to narrow widths are annealed in these bell-shaped furnaces in the Chase Brass & Copper Co. plant at Waterbury, Conn.

Lithium Supply To Rise

More commercial compounds of lithium, lightest known metal, will be available to industry. Foote Mineral Co. is constructing at Sunbright, Va., the world's largest lithium plant, designed to process 1500 tons monthly of spodumene, a silicate of lithium and aluminum. Ore output from the company's mines at Kings Mountain, N. C., will be tripled. Chief user of the lithium compounds is the ceramics industry.

Nonferrous Briefs

Because lead from abroad undersold U. S. metal by more than half a cent, producers were forced to drop prices by 0.50-cent to 12.80, St. Louis and 13.00, New York. They had hoped to hold the price line until spring when battery makers enter the market in force. Last week's move was the year's fourth drop.

NONFERROUS METALS

(Cents per pound, carlots, except as otherwise noted)

Primary Metals

Copper: Electrolytic 27.50c-32.00c, Conn. Valley; Lake nom., delivered.

Brass Ingots: 85-5-5-5 (No. 115) 29.50c; 88-10-2 (No. 215) 41.75c; 80-10-10 (No. 305) 35.00c; No. 1 yellow (No. 405) 24.00c.

Zinc: Prime western 11.00c; brass special 11.25c, intermediate 11.50c; East St. Louis; high grade 12.35c, and special high grade 12.50c, delivered.

Lead: Common 12.80c; chemical 12.90c; corroding, 12.90c, St Louis.

Primary Aluminum: 99% plus, ingots 20.50c, pigs 19.50c. Base prices for 10,000 lb and over. Freight allowed on 500 lb or more but not in excess of rate applicable on 30,000 lb c.l. orders.

Secondary Aluminum; Piston alloys 23.00-23.50; No. 12 foundry alloy (No. 2 grade) 22.25-22.75; steel deoxidizing grades, notch bars, granulated or shot: Grade 1, 23.00-24.00; grade 2, 22.50-23.00; grade 3, 21.25-22.25; grade 4, 21.00-22.00.

Magnesium: Commercially pure (99.8%) standard ingots, 10,000 lb and over 24.50c, f.o.b. Freeport, Tex.

Tin: Grade A, prompt 121.50c.

Antimony: American 99-99.8% and over but not meeting specifications below 34.50c; 99.8% and over (arsenic 0.05% max., other impurities 0.1% max.) 35.00c; f.o.b. Laredo, Tex., for bulk shipments.

Nickel: Electrolytic cathodes, 99.9%, base sizes at refinery, unpacked, 60.00c; 25-lb pigs, 62.65c; "XX" nickel shot, 63.65c; "F" nickel shot or ingots, for addition to cast iron, 60.00c. Prices include import duty.

Mercury: Open market, spot, New York, $200-$204, per 76-lb flask.

Beryllium-Copper: 3.75-4.25% Be, $37.72 per lb of contained beryllium, f.o.b. Reading, Pa.

Cadmium: "Regular" straight or flat forms, $2 del; special or patented shapes $2.15.

Cobalt: 97.99%, $2.40 per lb for 500 lb (kegs); $2.42 per lb for 100 lb (case); $2.47 per lb under 100 lb.

Gold: U. S. Treasury, $35 per ounce.

Silver: Open market, New York 85.25c per oz.

Platinum: $90-$93 per ounce from refineries.

Palladium: $23-$24 per troy ounce.

Iridium: $175-185 per troy ounce.

Titanium (sponge form): $5 per pound.

Rolled, Drawn, Extruded Products

COPPER AND BRASS

(Cents per pound, f.o.b. mill, effective Feb. 27, 1953. Listings are lowest quotations.)

Sheet: Copper 48.98; yellow brass 42.03; commercial bronze, 95% 48.49; 90% 47.46; red brass, 85% 45.91; 80% 44.89; best quality, 43.09; nickel silver, 18%, 58.52; phosphor-bronze grade A, 5%, 68.57.

Rod: Copper, hot-rolled 45.33; cold-drawn 46.58; yellow brass free cutting, 35.92; commercial bronze 95% 48.18; 90% 47.15; red brass 85%, 45.60; 80%, 44.58.

Seamless Tubing: Copper 48.92; yellow brass 44.94; commercial bronze, 90%, 50.02; red brass, 85%, 48.72.

Wire: Yellow brass 42.32; commercial bronze, 95%, 48.78; 90%, 47.75; red brass, 85%, 46.20: 80%, 45.18; best quality brass, 43.78. (Base prices, effective Feb. 26, 1953)

Copper Wire: Bare, soft, f.o.b. eastern mills, 100,000 lb lots, 35.24; 30,000 lb, lots, 35.27; l.c.l. 35.77, Weatherproof, 100,000 lb, 35.35; 30,000 lb, 35.60; l.c.l., 36.10. Magnet wire del., 15,000 lb or more, 41.00; l.c.l., 41.85.

ALUMINUM

(30,000 lb base; freight allowed on 500 lb or more, but not in excess of rate applicable on 30,000 lb c.l. orders. Effective Jan. 22, 1953.)

Sheets and Circles: 2s and 3s mill finish c.l.

Thickness Range Inches	Widths or Diameters, In., Inc.	Flat Sheet Base*	Coiled Sheet Base	Coiled Sheet Circle† Base
0.249-0.136	12-48	32.9	...	...
0.135-0.096	12-48	33.4	...	...
0.095-0.077	12-48	34.1	31.8	36.3
0.076-0.061	12-48	34.7	32.0	36.5
0.060-0.048	12-48	35.0	32.2	36.8
0.047-0.038	12-48	35.5	32.6	37.1
0.037-0.030	12-48	35.9	33.0	37.8
0.029-0.024	12-48	36.5	33.3	38.3
0.023-0.019	12-36	37.1	34.0	39.0
0.018-0.017	12-36	37.9	34.6	39.9
0.016-0.015	12-36	38.8	35.4	41.1
0.014	12-24	39.8	36.4	42.4
0.013-0.012	12-24	40.9	37.1	43.4
0.011	12-24	41.9	38.3	45.0
0.010-0.0095	12-24	43.1	39.4	46.6
0.009-0.0085	12-24	44.3	40.7	48.5
0.008-0.0075	12-24	45.8	41.9	50.3
0.007	12-18	47.3	43.4	52.6
0.006	12-18	48.9	44.8	57.6

* Lengths 72 to 180 inches. † Maximum diameter, 26 inches.

Screw Machine Stock: 5000 lb and over.

Dia. (in.) or distance across flats	—Round— 17S-T4	Hexagonal 17S-T4
0.125	56.8	...
0.156-0.0188	48.0	...
0.219-0.313	45.3	...
0.375	43.7	52.4
0.406	43.7	...
0.438	43.7	52.4
0.469	43.7	...
0.500	43.7	52.4
0.531	43.7	...
0.563	43.7	49.2
0.594	43.7	...
0.625	43.7	49.2
0.688	43.7	49.2
0.750-1.000	42.6	46.4
1.063	42.6	44.8
1.125-1.500	41.0	44.8
1.563	40.5	...
1.625	39.8	43.2
1.688-2.000	39.8	...

LEAD

(Prices to jobbers f.o.b. Buffalo, Cleveland, Pittsburgh) Sheets: Full rolls, 140 sq ft or more $18.50 per cwt; add 50c cwt 100 sq ft to 140 sq ft. Pipe: Full coils $18.50 per cwt. Traps and bends: List prices plus 43%.

ZINC

Sheets 23.00c, f.o.b. mill 36,000 lb and over. Ribbon zinc in coils, 19.50-20.50c, f.o.b. mill, 36,000 lb and over. Plates, not over 12-in., 20.75-21.75c; over 12-in., 20.75-21.75c.

"A" NICKEL

(Base prices f.o.b. mill, effective Feb. 13, 1953) Sheets, cold-rolled 83.00c. Strip, cold-rolled 89.00c. Rods and shapes, 79.00c. Plates, 81.00c. Seamless tubes 112.00c.

MONEL

(Base prices f.o.b. mill, effective Feb. 13, 1953) Sheets, cold-rolled 66.50c. Strip, cold-rolled 69.50c. Rods and shapes, 63.50c. Plates 65.50c. Seamless tubes, 99.50c. Shot and blocks, 58.00c.

MAGNESIUM

Extruded Rounds 12 in. long, 1.31 in. in diameter, less than 25 lb, 55.00-62.00c; 25 to 99 lb, 45.00-52.00c; 100 lb to 5000 lb, 41.00c.

TITANIUM

(Prices per lb, 10,000 lb and over, f.o.b. mill) Sheets, $15; sheared mill plate, $12; strip, $15; wire, $10; forgings, $6; hot-rolled and forged bars, $6.

DAILY PRICE RECORD

1953	Copper	Lead	Zinc	Tin	Aluminum	Antimony	Nickel	Silver
Mar. 2-5	27.50-32.00	12.80	11.00	121.50	20.50	34.50	60.00	85.25
Feb. 25-28	27.50-28.50	13.30	11.25	121.50	20.50	34.50	60.00	85.25
Feb. 3-24	24.50	13.30	11.50	121.50	20.50	34.50	60.00	85.25
Feb. 2	24.50	13.30	12.00	121.50	20.50	34.50	60.00	85.25
Jan. 27-31	24.50	13.80	12.00	121.50	20.50	34.50	60.00	85.25
Jan. 22-26	24.50	13.80	12.50	121.50	20.50	34.50	60.00	85.25
Jan. 16-21	24.50	13.80	12.50	121.50	20.00	34.50	60.00	85.25
Jan. 15	24.50	13.80	12.50	121.50	20.00	34.50	60.00	84.75
Jan. 14	24.50	13.80	12.50	121.50	20.00	34.50	60.00	84.25
Jan. 13	24.50	13.80	13.00	121.50	20.00	34.50	56.50	83.75
Jan. 12	24.50	13.80	13.00	121.50	20.00	34.50	56.50	83.25
Jan. 7-10	24.50	14.30	13.00	121.50	20.00	34.50	56.50	83.25
Feb. 1953 Avg.	25.136	13.30	11.431	121.50	20.50	34.50	60.00	85.25
Jan. 1953 Avg.	24.50	13.838	12.596	121.50	20.173	34.50	58.654	84.442
Feb. 1952 Avg.	24.50	18.80	19.50	121.50	19.00	50.00	56.50	88.00
Feb. 1948 Avg.	21.50	14.825	12.00	94.00	15.00	33.00	33.75	74,625

NOTE: Copper: Electrolytic, del. Conn. Valley; Lead, common grade, del. St. Louis; Zinc, prime western, E. St. Louis; Tin, Straits, del. New York; Aluminum primary ingots, 99%, del.; Antimony, bulk f.o.b. Laredo, Tex.; Nickel, electrolytic cathodes, 99.9% base sizes at refinery unpacked. Silver, open market, New York. Prices, cents per pound; except silver, cents per ounce.

Plating Materials

Chromic Acid: 99.9% flakes, f.o.b. Philadelphia, carloads 27.00c; 5 tons and over 27.50c; 1 to 5 tons, 28.00c; less than 1 ton 28.50c.

Copper Anodes: Base 2000 to 5000 lb; f.o.b. shipping point, freight allowed: Flat, rolled, 42.18c; oval 41.68c.

Nickel Anodes: Rolled oval, carbonized, carloads, 74.50c; 10,000 to 30,000 lb 75.50c; 3000 to 10,000 lb 76.50c; 500 to 3000 lb 77.50c; 100 to 500 lb, 79.50c; under 100 lb, 82.50c; f.o.b. Cleveland.

Nickel Chloride: 36.50c in 100 lb bags; 34.50c in lots of 300 lb through 10,000 lb; 34.00c over 10,000 lb, f.o.b. Cleveland, freight allowed on 300 lb or more.

Sodium Stannate: 25 lb cans only, less than 100 lb to consumers 86.7c; 100 or 350 lb drums only, 100 to 600 lb 71.60c; 700 to 1900 lb, 69c; 2000 to 9900 lb, 67.3c. Freight allowed east of Mississippi and north of Ohio and Potomac rivers.

Tin Anodes: Bar, 1000 lb and over, $1.42; 500 to 999 lb, $1.425; 200 to 499 lb, $1.43; less than 200 lb, $1.445. Freight allowed east of Mississippi and north of Ohio and Potomac.

Zinc Cyanide: 100 lb drums, less than 10 drums 54.30c, 10 or more drums, 52.30c, f.o.b. Niagara Falls, N. Y.

Stannous Sulphate: 100 lb kegs or 400 lb bbl, less than 2000 lb $1.11; more than 2000 lb, $1.09. Freight allowed east of Mississippi and north of Ohio and Potomac rivers.

Stannous Chloride (Anhydrous): In 400 lb bbl, $1.25; 100 lb kegs $1.26, f.o.b. Carteret, N. J., freight allowed on 100 lb or more.

Scrap Metals

Brass Mill Allowances

(Prices in cents per pound for less than 15,000 pounds, f.o.b. shipping point. Listings are lowest quotations.)

	Clean Heavy	Rod Ends	Clean Turnings
Copper	27.125	27.125	26.375
Yellow Brass	20.625	20.375	19.500
Commercial Bronze			
95%	25.750	25.500	25.000
90%	24.875	24.625	24.125
Red Brass			
85%	24.000	23.750	23.250
80%	23.000	22.750	22.250
Best Quality (71-80%)	21.500	21.250	20.750
Muntz metal	19.375	19.125	18.625
Nickel silver, 10%	24.375	24.125	12.1875
Phos. Bronze, A	29.125	28.875	27.875
Naval Brass	19.25	19.00	18.50
Manganese Bronze	19.25	19.00	18.50

REFINERS' BUYING PRICES

(Cents per pound, delivered refinery, carload lots)

No. 1 copper 28.50; No. 2 copper 26.50; light copper 25.00; refinery brass (60% copper) per dry copper content 25.50.

DEALERS' BUYING PRICES

(Cents per pound, New York, in ton lots)

Copper and brass: Heavy copper and wire, No. 1 24.00 nom.; No. 2 23.00 nom.; light copper 22.00-22.50; No. 1 composition red brass 19.00 nom.; No. 1 composition turnings 18.50 nom.; mixed brass turnings 13.50 nom.; new brass clippings 18.50; No. 1 brass rod turnings 15.00-15.50; light brass 12.50 nom.; heavy yellow brass 14.50 nom.; new brass rod ends 17.50; auto radiators, unsweated 15.00 nom.; cocks and faucets 16.50 nom.; brass pipe 17.50 nom.

Aluminum: Clippings 2S 13.00; old sheets 10.00; crankcase 10.00; borings and turnings 8.00; pistons and struts 6.50.

Tin: No. 1 pewter 70.00; block tin pipe 100.00; No. 1 babbitt 60.00.

Lead: Heavy 10.25-10.75; battery plates 5.25-5.50; linotype and stereotype 12.00-12.50; electrotype 10.25-10.50; mixed babbitt 13.75-14.00.

Zinc: Old zinc, 5.00; new die cast scrap, 5.00; old die cast scrap, 4.00.

Nickel: Sheets and clips 58.00-60.00; rolled anodes 58.00-60.00; turnings 55.00; rod ends 58.00-60.00.

Monel: Clippings 33.00; old sheet 30.00; turnings 25.00; rods 33.00.

Steel Bars . . .

Bar Prices, Page 177

New York—Hot carbon bar demand is well sustained, with prospects in for the placing of much, if any, unrated work in first half. Bars, ranging 1½ inches and larger, appear definitely out of reach for non-rated consumers over remainder of this period, due primarily to shell requirements. Even the smaller sizes appear in more active demand, reflecting, in part, the needs of the automotive and agricultural equipment industries.

Boston—Only in smaller sizes, cold-drawn, including low-carbon screw stock, are bars slightly more plentiful. Part of this comes from space openings with converters where hot stock is available. Prospects for any substantial unrated tonnage for second quarter are dim.

Philadelphia—Increasing amount of shell work is placing a tighter squeeze on carbon bars.

Pittsburgh—Basis of distribution for hot-rolled bars in third quarter will largely depend upon the outlook at the time of complete decontrol.

Cleveland—Bar mills are booked full through second quarter and there is nothing in the market to indicate any early easing in supply conditions, especially in the larger sizes.

Sheets, Strip . . .

Sheet and Strip Prices, Page 177-178

Boston—Flat-rolled consumers are fishing around for more open-end sheet tonnage for second quarter with fair prospects of getting part of estimated tonnage filled. Those producers, sparingly taking first quarter commitments, operating on carryovers, may satisfy part of this demand. With exception of galvanized, notably at warehouse level, buying has shifted heavily to carbon sheets, notably cold-rolled.

Philadelphia—Increasing activity is noted in sheets. Automotive requirements are particularly pressing and risk demand prevails for most household appliances. Broadening use of pressed metal for bathtubs, washers and dryers, especially in heavier gages, 14 to 16, is reflected in an active demand for enameling stock.

New York—Pressure for hot and cold-rolled sheets continues strong. Also electrical sheets and enameling stock are in demand. There appears to be little likelihood of any tonnage being obtained for shipment in first half without CMP tickets.

Pittsburgh — Demand for long ternes and electrical sheets is expected to be strong for the entire second quarter. Warehouse demand is good for most sheet items, except galvanized, which at present seems to be building up, and for hot rolled strip. Hot rolled is reaching a saturation point with warehouses. Inquiries for this material are falling off, and the reason given is the good inventories that most warehouses have built up.

Cleveland — With the approach of spring, producers of galvanized sheets are anticipating a pickup in demand, which over the winter months has lagged noticeably in some areas. Pressure for other grades of sheets is undiminished, with hot and cold-rolled in especially tight supply. Producers are booked into second quar-

For better grinding it's well worth having!

SIMONDS ABRASIVE CO.

Grinding Wheels

It's Simonds Abrasive Company bulletin ESA 191 "Cylindrical Grinding Wheels" with recommended specifications—plus facts about feeds, speeds and wheel sizes. It's part of a *complete* library on Simonds products including wheels for rough grinding, finishing, cutting off, sharpening . . . abrasive polishing grain . . . mounted wheels and points . . . surfacing segments . . . everything *you* need for productive, economical grinding, factually described and supplemented with helpful hints. Write for ESA 191 . . . or for information on Simonds wheels for other grinding jobs. We'll also send name of your Simonds distributor.

SIMONDS ABRASIVE CO., PHILADELPHIA 37, PA. BRANCH WAREHOUSES: CHICAGO, DETROIT, BOSTON

DISTRIBUTORS IN PRINCIPAL CITIES

Division of Simonds Saw and Steel Co., Fitchburg, Mass. Other Simonds Companies: Simonds Steel Mills, Lockport, N. Y. Simonds Canada Saw Co., Ltd., Montreal, Que. and Simonds Canada Abrasive Co., Ltd., Arvida, Que.



tubes

Uniform strength, accurate dimensions and high ductility are three of the many qualities found in Murray boiler tubes. Welded or seamless tubes in sizes ranging from ⅝- to 8-inch OD are available for immediate shipment from warehouse stocks.

If you have a tubing problem, the experience of our specialists and the research facilities of our suppliers are at your service.

Other Murray products include carbon and stainless steel tubing and pipe for pressure and mechanical purposes; welding and screw type pipe and tube fittings. Tube bending, upsetting, swaging.

ter as far as they desire to go, and indications are there will be little, if any, open tonnage before third quarter at earliest.

Chicago—Sheetmakers are of the opinion that were they to open their books for third quarter now it would be necessary to continue customer quotas. The intense demand is coming from all quarters and is baffling in view of essentially unchanged defense requirements and the increase in sheet productive capacity.

Fluorspar . . .

Fluorspar Prices, Page 181

Cleveland—With steel mill operations being pressed at capacity pace demand for flourspar is strong and sellers have little difficulty disposing of their output. Domestic grade metallurgical spar, however, is meeting increasing competition from imported material, especially that coming in from Mexico. Last year something like 130,000 tons of Mexican spar came into this country as against 50,000 to 60,000 tons annually previously. This Mexican spar is quoted around $30 per net ton, duty paid, as against a domestic price of $40 to $43. With freight from the Gulf to Pittsburgh $18.38 the Pittsburgh delivered price on Mexican spar runs around $48 to $49. Spar delivered Pittsburgh from Illinois takes a freight of $10 pushing the delivered price to $53.

Ferroalloys . . .

Ferroalloy Prices, Page 183

Washington—The government has revised its purchase program for small manganese producers to include manganese in the form of furnace slags as well as ores and concentrates. To be accepted under the program, slag must meet the same specifications as ores and concentrates.

Plates . . .

Plate Prices, Page 177

Philadelphia — Plate demand still exceeds supply. Some producers haven't opened books for entire second quarter, but anticipate no difficulty filling schedules on rated orders. This points to the probability no new non-rated tonnage can be handled in the first half as result of the recent open-ending of the Controlled Materials Plan.

Boston—Improved supply of narrow-thin plates is broadening in size ranges, up to 84-inch and 1½-inch thick. Without high ratings heavier plates are not available for second quarter. Application of narrower and odd size plate is limited and some consumers, including warehouses, are holding up strip mill shipments.

New York — Plate producers are confronted with all the rated tonnage they can supply in first half. Some haven't opened their books for the entire period.

Los Angeles—With plate supplies tightening fabricators are displaying interest in Janpanese tonnage made to American gages of good quality at $135 per metric ton laid down at Los Angeles harbor. European plate at $160 per metric ton is not competitive.

UPSON-WALTON turnbuckles

ENGINEERED FOR SAFETY


Turnbuckle heads are drilled and tapped in perfect alignment, so that end fittings pull evenly, and assure maximun strength and safety.
All threads are American National Coarse series, class 2 fit, and will readily assemble with any end fitting threaded to this standard.
Weldless, drop-forged steel, hex-end turnbuckle bodies are made in accurate dies to assure uniformity, dependability, and safety.

See Your NEARBY DISTRIBUTOR for prompt service from stock. Write for free catalog on wire rope fittings.

THE UPSON-WALTON CO.
12500 ELMWOOD AVENUE
CLEVELAND 11, OHIO
New York • Chicago • Pittsburgh
YOU CAN DEPEND ON UPSON-WALTON'S LONG EXPERIENCE—ESTABLISHED 1871
Manufacturers of ALL THREE
FITTINGS • WIRE ROPE • TACKLE BLOCKS

Wire . . .

Wire Prices, Page 179

Boston—Limited unrated open tonage will be available in June, mostly n finer sizes, but not until third uarter will wire distribution, outde defense, be in the hands of producers.

Tin Plate . . .

Tin Plate Prices, Page 178

Pittsburgh — While the tin plate narket has strengthened some from s former shaky state, the principal an manufacturers are not going to et relaxation of controls inhibit narket expansion plans. Both Amerean Can Co. and Continental Can o. are casting a covetous eye at the oft beverage market. Cans are now eing produced for large scale conumer testing this summer.

Tubular Goods . . .

Tubular Goods Prices, Page 181

Washington—Only limited amounts f additional steel will be made vailable during second quarter to oil nd gas operators as result of the pen-ending of the Controlled Maerials Plan. Second quarter allotnents by the Petroleum Administraion for Defense and other defense gencies will largely, if not wholly, bsorb expected output of line pipe, teel plate, structural shapes and ther items used in the oil and gas ndustries.

Boston—Competition has forced a eduction on smaller sizes of carbon lectric welded tubing, leading producers lowering prices 10 per cent. A new mill has started operation at Boston and surplus tonnage is offered by district and New York producers. Stainless tubing is firm. Demand is more in balance with supply.

Structural Shapes . . .

Structural Shape Prices, Page 177

Cleveland — Surge in construction activity is expected with the coming of spring. Structural steel supplies continue tight, especially wide flange beams, but conditions are expected to improve steadily as the weeks pass permitting a large volume of projected work to go ahead.

Currently, public jobs are outstanding in the market. These include contracts totaling $66,070,563 for a proposed $78 million bridge across the Straits of Mackinac in Michigan awarded through the Mackinac Bridge Authority. Merritt-Chapman & Scott Corp. was the successful bidder for the substructure, which involves 34 water piers. American Bridge Division, U.S. Steel Corp., was awarded the contract for the steel superstructure which includes 9304 feet of truss spans and a suspension bridge 8614 feet in length. This latter contract amounts to $41,544,563.

Boston—District fabricating shops are picking up wanted sizes more readily, but deliveries are slightly more extended by heavier bookings, July in more instances. Foreign steel is a factor in fill-in buying. Larger shops are more extended on girder than beam work, November-December and September-October respec-

You name the material, the surfaces and the conditions under which they are to be marked and you'll find a Markal Paintstik that will efficiently do the job. In those rare cases where conditions are out of the ordinary and no stock Paintstik is available, one will be developed to meet your needs.

Markal Paintstiks are a quality product that produce permanent markings—made especially to meet the needs and special conditions of industry.

Write today for an easy selector chart, then order Paintstiks from your nearest jobber. If he should not have them write direct to the address below.

Markal COMPANY

THE MARK OF QUALITY
MARKAL PAINTSTIKS

3094 WEST CARROLL AVENUE, CHICAGO 12, ILLINOIS

tively. Structural mills are not yet absorbing freight.

New York—Several new jobs for the New York state thruway feature structural inquiry. Work includes projects involving 1800 tons, 1700 tons, 1400 tons and 800 tons, bids opening Mar. 26. An outstanding industrial award involves 1110 tons for a manufacturing building for the Tube Reducing Corp., Wallington, N. J.

January structural awards, according to the American Institute of Steel Construction, involved 268,163 tons, increase of 14 per cent over December, 1952, and 26 per cent over the corresponding month last year. Shipments totaled 234,234 tons, up 4 per cent over the previous month. January shipments were below the like month last year, but 6 per cent greater than the average monthly rate of 222,021 tons shipped during 1952. Backlog as of Jan. 31 was 2,179,777 tons.

San Francisco—Construction is expected to begin shortly on a $62 million bridge, Richmond to San Rafael.

Reinforcing Bars . . .

Reinforcing Shape Prices, Page 177

Ft. Worth, Tex.—Texas Steel Co. announced effective with all shipments leaving its plant on Feb. 23, concrete reinforcing bars in stock length were invoiced to all its fabricator and warehouse customers at the following base prices: Rail steel, $5.05, mill zone Tarrant and Dallas counties, $4.85, f.o.b. mill; billet steel, $5.25 mill zone, Tarrant and Dallas counties, $5.05 f.o.b. mill.

Pig Iron . . .

Pig Iron Prices, Page 176

Pittsburgh—If a great demand for pig iron were to develop, some users might feel a temporary pinch. Currently three blast furnaces in the Pittsburgh district are out for relining: For Jones and Laughlin, its the Eliza blast furnace; for U. S. Steel, No. 7 at Edgar Thomson Works, and No. 3 at Duquesne Works. However, foundry activity is slow to reflect any seasonal pickup that might result from spring building activities and a corresponding rise in hardware and plumbing demand.

Cleveland — Merchant pig iron is moving steadily into consumption from the furnaces but demand pressure is off with spotty foundry operations still reported. Over recent weeks foundries on automotive work have been more active and have been taking more iron. To some extent shops turning out castings for the appliance industry also are consuming iron in larger volume. Over-all, however, the situation in the foundry trade is not much changed from earlier in the year and pig iron supply appears adequate for all current needs.

Boston—Although the melt is restricted, shipments of pig iron hold close to production of the Everett furnace. Foundries taking in iron are for the most part correcting their inventory position. Textile equipment shops, operating well below capacity, are taking most of the iron. Machine shops require a steady volume of castings.

A-1033

EASTON



EASTON experience covers small and large capacity furnace cars for every requirement.

Furnace Cars

Electric furnace car mounted on electric transfer car for completely automatic continuous heat treating system.



EASTON CAR & CONSTRUCTION COMPANY • EASTON, PA. • NEW YORK • PHILADELPHIA • PITTSBURGH

Buffalo—Merchant pig iron producers plan to take advantage of one of the earliest openings of the lake navigation season on record. Although demand is equal to current output, merchant iron is being piled as producers await vessels for shipment to upper lake points. General improvement in foundry demand is noted. Sixteen of the district's 17 blast furnaces are active.

Chicago — Most foundries are operating at higher levels. Virtually every user of gray iron castings has ambitious production plans extending beyond first half. Automotive and household appliances are pushing hard and now farm implements are experiencing renewed life. This is keeping pig iron supply nip-and-tuck. No shortage of iron is anticipated, however.

Iron Ore . . .

Iron Ore Prices, Page 183

Cleveland — Navigation is getting under way on the lower lakes for the 1953 shipping season and expectations are one of the earliest openings of the ore shipping season will be seen this year. Automobile cargoes are coming by vessel into Cleveland harbor two weeks ahead of the normal shipping season opening. At the same time a vessel cleared Cleveland harbor last week with a cargo of pig iron for the Ford Motor Co., Detroit.

Scrap . . .

Scrap Prices, Page 184

Philadelphia — Prices are buoyant on high grade steel scrap. Buying in volume for Morrisville, Pa., has been done around $48.50 delivered on No. 1 heavy melting steel and No. 1 bundles with the consumer at this point paying a low phos differential. Railroad lists also reflect strength in the premium grades. The Baltimore & Ohio list of 20,000 tons brought higher than former OPS ceilings on all grades offered and on some grades prices were substantially higher. For instance, crop rail, 18-inches and under, brought $66 delivered to line points, against the former OPS ceiling of $54. Wheels, couplers and knuckles brought $54 against $51. The New York Central obtained $61.50 on crop rail and $54.50 on wheels, couplers and knuckles. Most district steel consumers of open-hearth steel will likely be entering the market shortly as shipments against old contracts are running out. The next few days should somewhat clarify the muddled situation that now exists. Currently No. 2 heavy melting is holding around $43 to $43.50 delivered and No. 1 busheling at $44.50 delivered. The market on No. 2 bundles is weak and purely nominal. Machine shop turnings are quotable at $33.50 to $34 delivered and mixed borings and turnings and short shovel turnings at $37.50 to $38 delivered. The Bethlehem, Pa. consumer is temporarily holding up shipments on No. 2 heavy melting and bundles. Leading cast grades are unchanged, except for drop broken machinery which is off $2 per ton to $50 delivered.

Pittsburgh—The scrap market is described as in an uncertain position but the price picture is beginning to clear up. The trend seems to be to keep prices of better grades about

pointing problems?

Torrington Swaging Machines produce pointed ends on both solid and tubular work to close tolerances. The swager, delivering 4000 hammer blows a minute, works rapidly and gives the metal toughness and resiliency. Swaging is economical, too, for there is no stock waste.



"The Torrington Swaging Machine" tells the story on the art of swaging, and describes the complete line of Torrington machines. This informative booklet is yours for the asking.

THE TORRINGTON COMPANY
Swager Department
556 Field Street • Torrington, Conn.
Makers of
TORRINGTON NEEDLE BEARINGS

where they have been, and bid down prices on inferior material. Better grades are moving at former ceiling prices. One of the largest consumers last week announced a substantial purchase of No. 2 bundles at $42, and this generally was considered a representative quotation on this grade despite the fact some buyers were continuing to pay $44. Some indications are that short shovel and mixed turnings may drop to $36 to $37, but no strong purchases are reported to firmly establish the market at that level. Machine shop turnings are quoted $1 lower at $30 to $31, with few takers.

Boston—Re-establishment of old differentials between heavy melting steel and bundle grades with continued weakness in cast mark scrap transactions in this area. In the case of heavy melting, No. 1 is quoted $1 higher and No. 2 heavy melting is off $2, making the spread $3. No. 2 bundles are now $31.17, shipping point. There is little buying of cast at soft prices.

New York—Brokers have revised their buying prices slightly on No. 2 heavy melting steel to $35.50, on machine shop turnings to $25.50, and on mixed borings and turnings to $29.50. Cast iron grades are unchanged.

Buffalo—Confusion prevails over prices in the scrap market here with leading buyers placing business on a delivered basis. Meanwhile, the area's second largest consumer continues to buy at the former government ceiling levels. On a delivered basis local dealers within the switching area realize from $1 to $1.50 per ton more for steelmaking grades. New business placed did not include premium prices for No. 1 material which was placed on the same basis as No. 2. Machine shop turnings also were excluded from new business but borings and turnings were accepted. Cast grades continue weak.

Small quantities of the best grade of steel scrap were reported purchased here last week at $48 per ton, advance of $5 over the former ceiling.

Washington—Export quota of 49,579 short tons of iron and steel scrap has been established for first quarter, the Office of International Trade announced last week. Of this amount, 41,315 short tons are steelmaking scrap, 6164 tons are scrap for lead smelting, and 2100 short tons are copper precipitation scrap. Almost all the scrap exported under this quota is shipped to Mexico. The 49,579 tons compares with a quota of 36,000 tons for each of the third and fourth quarters, 1952.

Cleveland—Some of the uncertainty in the scrap market over prices is clearing away but definite trend of the market remains to be determined by representative new purchases. Steelmaking grades are showing strength, especially quality material.

Detroit—Scrap dealers are growing increasingly optimistic. Deals are reported in which No. 1 grades are offered without price increase on the stipulation No. 2 grades be purchased without decrease. This is tending to hold prices relatively stable. Dealers report scrap is coming into their yards at a greater rate than at any time recently.

Youngstown — Some buying of

MUNDT

a name with over 83 years experience ready to serve the industry at all times with the

PERFORATED

requirements necessary for your equipment, machinery or parts in any form or types of

METAL

or fibre, cardboard, paper, soundboards and other materials in a workmanlike manner that

MEANS

lasting performance, better quality, and above all a product that will give you a

PERFECT

job for the particular purpose for which it is to be used, without defects, burrs or camber to

SCREENS

because our up-to-date equipment, plus our engineering counsel gives you nothing but the best.

Specially Fabricated for **ALL INDUSTRIES** BY

CHARLES MUNDT & SONS

53 FAIRMOUNT AVE.
JERSEY CITY 4, N. J.
PHONE—DELAWARE 3-6200
Send for Illustrated Catalog

when it's accuracy and control that counts

it's a

LINDBERG

G-10 LABORATORY FURNACE

Fun is fun—and a joke is a joke . . . but when a busy laboratory technician has to fuss for an hour over the setting and control of a furnace —*that's no joke.*

Use the Lindberg G-10 Laboratory Furnace—just set it and forget it! The G-10 is electronically controlled to operate at a preset temperature within a plus or minus 5°F. limit. The electronic indicating and controlling pyrometer, an integral part of the G-10, saves many man hours of supervision in the modern laboratory. Its 3000°F. top heat is available for intermittent operation—and you can run it for a week at 2500°F. It's compact—2'x3'x5'—completely self contained . . . all controls and equipment are in the furnace housing, just hook it up. It's a current saver—the electronic controller applies current only to adjust or maintain heat. It's tough—10 oversize Globars and an 8 KW transformer produce optimum low watt density and long element life.

It's a natural for *your laboratory.* Ask your laboratory equipment dealer for full details, or write Lindberg Engineering Company, 2441 West Hubbard Street, Chicago 12, Illinois. *Ask for Bulletin No. 980.*

LINDBERG—*for a complete line of the finest*
LABORATORY HEATING APPARATUS

Available!

HEAVY DUTY-MILL TYPE ALL STEEL GONDOLAS

furnished with either 70 or 50 ton capacity trucks

Rebuilt for exceptional heavy duty service, these cars are in excellent condition and can withstand severe abuse, particularly where clam shell buckets or magnetic cranes are used for loading and unloading.

Each car is reconstructed with an inside height of 2 feet 6 inches to reduce the possibility of overloading breakdowns. Whether used for railroad interchange, industrial service or mill type service, these cars will prove efficient and economical to operate.

CFC Gondola cars are reconditioned to include these special features:

- New welded steel floors up to ½" in thickness as specified by customer
- New steel sides and ends up to ⅜" in thickness as specified by customer
- New side and end top chord angles
- Double fish belly type center sills built of steel plate and angles 17" deep at body bolster to end sill and 24" deep at the center of the car. Center sills are continuous.
- Fish belly type side sills 24" deep at center of car
- AB, KC type or straight train line air brakes as specified.

Each car is put into first class operating condition by skilled workmen in Chicago Freight Car's own shops. Built in 1926 these gondola cars will give many years of rugged service. They are priced to give you exceptional value and are ready for prompt delivery.

GENERAL SPECIFICATIONS

Capacity, nominal	100,000 lbs.
Light weight, approx.	48,000 lbs.
Load limit	121,000 lbs.
Inside length	38 ft. 4 in.
Inside width	9 ft. 0 in.
Inside Height	2 ft. 6 in.
Length over strikers	40 ft. 6 in.

Write for specification sheet giving complete data.

MAIN OFFICE: 228 North LaSalle Street, Chicago 1, Illinois

ap has developed here but no im-
tant changes in prices are noted
ept for a decline of $2 per ton
No. 2 bundles. U. S. Steel Corp.
ced some orders, but purchases
re of only normal tonnages, and
prices paid were former OPS
lings, except for No. 2 bundles
ich were down $2 to $42 including
oker's commission. No. 1 bundles
re purchased at $45, while No. 1
d No. 2 heavy melting moved at

Chicago — Several downward and
nificant scrap price changes es-
olished in transactions last week
ggest the market here is going to
abilize without disruptive confu-
n. The readjustments foreshadow
urn to normal price differentials
tween grades. Last week's sales
opped No. 2 heavy melting by $2
ton, No. 2 bundles by $1.50 and
achine shop turnings by close to
. The mill which set the pattern
ntinues the $43.50 ceiling for No.
factory bundles from industry but
gs the same type bundles from
aler yards at $41.

St. Louis — First post-decontrol
ying by major scrap consumers
sclosed calculated downward pres-
re on prices. Laclede Steel, for ex-
ple, paid ceiling and $2 spring-
ard but placed very small orders
nong many brokers. It passed up
ndles entirely, on which there has
en special pressure. The technique
buying the least possible until
ices drop below ceiling has been
ded by heavy shipments. Mills for
e first time in two months are re-
iving more than daily melt.

Seattle—A leading scrap buyer
nounced last week that all prices
e now gross, delivered plant. No
eight from remote locations will
absorbed as was done during the
ortage last year. Sufficient ma-
rial is arriving from the immediate
ea to supply current consumption
nd provide a surplus. New mill
ices are $34 for No. 1 heavy melt-
g, $29 for No. 2, $33 for No. 1
ndles, $27 for No. 2, turnings and
brings $25.

Warehouse . . .

Warehouse Prices, Page 183

Boston — More steel is reaching
arehouses, and, while inventories
equently approximate 60 per cent
f normal, the missing 40 per cent is
products and sizes in heaviest de-
and, namely carbon sheets in most
ages, heavy bars, wide plates and
tructurals.

Philadelphia—Warehouse operators
ook for March business to show fur-
ner improvement. Usually, March
nd April are among the most active
nonths of the year. Most distribu-
ors report February volume exceed-
d that in January on a day-to-day
asis. Increasing demand for hot and
old-rolled sheets is noted.

STRUCTURAL SHAPES . . .

STRUCTURAL STEEL PLACED

205 tons, sub-station work, American Gas & Electric Corp., to Bethlehem Steel Co., Bethlehem, Pa., work comprises 850 tons at Madison, Ind., 735 tons, Cheshire, O., and 620 tons at New Richmond, O.

110 tons, manufacturing building, Tube Reducing Corp., Wallington, N. J., to B. Katchen Iron Works, Newark, N. J.

25 tons, four bridges and underpass, Amesbury-Salisbury, Mass., to Groisser & Schlager Iron Works, Somerville, Mass., through A. V. Taurasi Co., Boston, general contractor.

430 tons, state bridge work, Schenectady county, New York, through Grandview Construction Co., to Ernst Iron Works, Buffalo.

400 tons, hangar, Ft. Sill, Okla., to Capitol Steel & Iron Co., Oklahoma City, Okla., through Harman Construction Co., Oklahoma City, general contractor.

375 tons, freight terminal, Adley Express Co., Bridgeport, Conn., at Cambridge, Mass., to A. O. Wilson Structural Co., Cambridge, Leo F. Caproni, New Haven, engineer.

365 tons, race track grandstand, Talleyvale, Del., to the Southern Iron Works, Alexandria, Va.

345 tons, 3-span continuous girder bridge, Souhegan river, Daniel Webster highway, Merrimack, N. H., to Groisser & Schlager Iron Works, Somerville, Mass., through E. D. Sweet, Winchester, N. H., general contractor.

285 tons, building No. 55, Electro-Metallurgical Sales Co., Marietta, O., to Bethlehem Steel Co., Bethlehem, Pa.

275 tons, manufacturing building, Jordon Refrigerator Co., Philadelphia, to Bethlehem Steel Co., Bethlehem, Pa.

245 tons, hangar and shop, Robins Airfield, Georgia, to Decatur Iron & Steel Co., Decatur, Ill., through Christian & Bell Co., Atlanta, Ga.

200 tons, in addition to 300 tons previously reported, shop addition, Jones & Lamson, Springfield, Vt., to West End Iron Works, Cambridge, Mass.

200 tons, store, Lerner Shops, Indianapolis, Ind., to Geiger & Peters Inc., that city.

160 tons, dormitory group, Syracuse University, Syracuse, N. Y., to Empire Structural Steel Fabricating Co., Syracuse, through Edmond J. Rappoli Co., Inc., Cambridge, Mass., general contractor.

118 tons, state bridge work, Columbia county, New York, through Charter Oak Construction Co., to Pine Brook Iron Works, Scranton, Pa.

100 tons, Spaulding school, Newton, Mass., shapes and bars, to Security Steel & Wire Co., Boston; Rich Bros. Construction Co., Boston, general contractor.

STRUCTURAL STEEL PENDING

12,000 tons, 163 galvanized steel towers and accessories, Chief Joseph-Snohomish transmission 345-KV line; Bethlehem Pacific Coast Steel Corp., San Francisco, low $2,844,406 to Bonneville Power Administration, Portland, Oreg.

5000 tons, bridge, Missouri river, Jefferson City, Mo.; bids Mar. 16 to Apr. 2, State Highway Commission, Jefferson City, Mo.

3985 tons, including 1935 tons, silicon, bridge, Kingman Lake and Anacostia river, East Capitol street extension, Washington, D. C.; bids Apr. 2, director of highways, District of Columbia.

1500 tons, repair shop, naval station, Lakehurst, N. J., Aufderaheide-Aragoma, Newark, N. J., low on general contract.

725 tons, structural shapes and piling, substructure, Sakonnet river bridge, Portsmouth-Tiverton, R. I.; bids Mar. 18, Providence; state purchased direct approximately 1140 tons additional H-piling.

285 tons, bar shapes, Corps of Engineers, Pittsburgh.

200 tons, Little Porcupine power plant, Montana, bids to Bureau of Reclamation, Denver, Colo., postponed to June 2; Spec. DC-3882.

105 tons, structurals and bars, state bridge, Bradford, Vt., bids in.

100 tons, intake machinery, Lucky Peak dam; rebids to U. S. Engineer, Seattle, Mar. 11; low first bidder, Berger Engineering Co., Seattle, $91,998, rejected.

REINFORCING BARS . . .

REINFORCING BARS PLACED

2600 tons, two warehouses, Robins Airfield, near Macon, Ga., to Hall Steel Co., and Southern General Fireproof Co., both Atlanta, Ga., through R. P. Fransworth Co., New Orleans, La., general contractor.

350 tons, dormitory group, Syracuse University, Syracuse, N. Y., to Bethlehem Steel Co., Boston, through Edmond J. Rappoli Co., Inc., Cambridge, Mass., general contractor.

270 tons, occupational therapy building, state hospital, Norwich, Conn., to Scherer Steel Co., Hartford, Conn., through Felix Buzzi & Sons, Torrington, Conn., general contractor.

100 tons, bars and structurals, school, Northbridge, Mass., to Joseph T. Ryerson & Son Inc., and West End Iron Works, both Cambridge, Mass., through John A. Volpe Construction Co., Malden, Mass., general contractor.

REINFORCING BARS PENDING

2000 tons, Little Porcupine power plant, Montana; bids to Denver, Colo., June 2.

1800 tons, New York state thruway, C. T. 53-6, Orange county, New York, bids Mar. 26.

1700 tons, state thruway, O. T. 53-6, Genesee county, New York, bids Mar. 26.

1400 tons, state thruway, O. T. 53-5, Genesee county, New York, bids Mar. 26.

850 tons, bridge, Kingman Lake and Anacostia river, East Capitol street extension, Washington, D. C.; bids, director of highways, District of Columbia.

800 tons, state thruway, C. T. 53-5, Albany county, New York, bids Mar. 26.

660 tons, bridge, Missouri river, Jefferson City, Mo.; bids Mar. 16 to Apr. 2, State Highway Commission, Jefferson City, Mo.

625 tons, Garden State parkway, contract 36, section 7, New Jersey, bids Mar. 26.

600 tons, Garden state parkway, contract No. 35, section No. 7, Middlesex and Monmouth counties, New Jersey, bids Mar. 19.

580 tons, substructure, Sakonnet river bridge, Portsmouth-Tiverton, R. I.; bids Mar. 18, Providence, R. I.

525 tons, Bartley diversion dam, Missouri river basin project, near Indianola, Nebr.; bids Mar. 10, Bureau of Reclamation, Arapahoe, Nebr.

440 tons, Sly Park dam, American river division, Central Valley Project, California; bids in to Department of Interior, Folsom, Calif.

200 tons, ammunition magazine and warehouses, Bangor, Wash., naval base; Hall-Atwater Co., Seattle, low $1,397,500 and $1,343,000 respectively two schedules, to Thirteenth Naval District, Seattle.

160 tons, state thruway, M. T. 53-5, Montgomery county, New York, bids Mar. 26.

160 tons, mat reinforcement, state highway, New Haven-East Haven, Conn.

140 tons, drainage and pavement, Tolland, Conn.; M. A. Gammino Construction Co., Providence, R. I., low.

PLATES . . .

PLATES PLACED

1540 tons, three tanks, Hartol Petroleum Corp., Baltimore, to Bethlehem Steel Co., Bethlehem, Pa.

700 tons, diesel engine requirements, American Locomotive Co., Schenectady, N. Y., to Bethlehem Steel Co., Bethlehem, Pa.

625 tons, tank work, Copeland Oil Co., Plattsburg, N. Y., to Bethlehem Steel Co., Bethlehem, Pa.

300 tons, 1-million gallon water storage tank, Richmond Highlands, to Chicago Bridge & Iron Co., Seattle, low $142,830 to city of Seattle.

200 tons, standpipe, Chattanooga, Tenn., to Chicago Bridge & Iron Works, Chicago.

PLATES PENDING

150 tons, petroleum storage, conical roof, 15,000-barrel capacity, Corps of Engineers, Galveston, Tex.

100 tons, also other steel items, classified project for Atomic Energy Commission, Arco, Idaho; general contract to Utah Construction Co., Salt Lake City, Utah; sub awards pending.

PIPE . . .

STEEL PIPE PENDING

100 tons or more, 210,000-ft. 6-inch, seamless, Corps of Engineers, Pittsburgh.

RAILS, CARS . . .

RAILROAD CARS PLACED

Gulf, Mobile & Ohio, 450 freight cars, with 400 gondolas going to American Car & Foundry Co., New York, and 50 hopper cars to the Pullman-Standard Car Mfg. Co., Chicago.



THIS part is ours

We have two gloves, especially designed to lower glove costs in your business.

SURETY TRIPL-PALM

Made with an extra abrasion-resisting coating applied to the palm for longer wearing and more cushion.

SURETY ARMOR GRIP

Made with closed, flexible metal zippers permanently bonded in rubber to palms and fingers providing greater resistance to cutting, unusual gripping action and the maximum wearing qualities of any coated glove.

THIS part is yours

Try either glove or both in your own plant under actual working conditions. Convince yourself that SURETY can really lower your glove costs.

MAIL THIS COUPON TODAY

OK, Convince me. Send me TRIPL-PALM ☐ ARMOR GRIP ☐

on memo billing, and I'll give them a fair trial.

NAME _____

COMPANY _____

ADDRESS _____

CITY _____ STATE _____

THE SURETY RUBBER CO.

Carrollton, Ohio

Dept. S

To Lower your Overhead..
BROWNING ELECTRIC TRAVELING CRANES AND HOISTS
up to 125-TON CAPACITY
VICTOR R. BROWNING & CO., INC.
WILLOUGHBY (Cleveland), OHIO

MOVED

to 8524 Vincennes Ave., Chicago 20

March 1st, 1953

SMEETH-HARWOOD COMPANY

8524 Vincennes Ave., Chicago 20

H&G Insert Chaser DIE HEADS



famous for accuracy and straightness of threads, low chaser costs, less downtime, more pieces per day.

THE EASTERN MACHINE SCREW CORP., 22-42 Barclay Street, New Haven, Conn.
Pacific Coast Representative: *A. C. Berbringer, 334 N. San Pedro St., Los Angeles, California.* Canada: *F. F. Barber Machinery Co., Toronto, Canada*

OHIO LOCOMOTIVE CRANES

25 TO 50 TON CAPACITY



DIESEL • GASOLINE • ELECTRIC • STEAM

THE OHIO LOCOMOTIVE CRANE CO
BUCYRUS, OHIO

STAINLESS STEEL

—PERFORATED—
TO YOUR REQUIREMENTS
SEND US YOUR DWGS FOR PRICE

ALL SIZE AND SHAPE HOLES ALL METALS
ARCHITECTURAL GRILLES

SEND FOR CATALOG NO. 35

DIAMOND MFG. CO.

BOX 32 WYOMING, PA.

THEORY AND PRACTICE OF ROLLING STEEL . . By Wilhelm Tafel

312 Pages
Price Postpaid
$4.50

Covers every angle of the design, construction and operation of the steel rolling mill.

THE PENTON PUBLISHING CO.

Book Department, 1213 W. 3rd St., Cleveland 13, O.

Metalworking Notes



esting the Skysweeper

ysweeper, newest and most effective answer of Army Ordnance to the menace high-speed low-flying aircraft, goes through initial tests at the Aetna-Stand- l Engineering Co., Ellwood City, Pa. The lethal package combines a 75 mm tomatic rapid-fire gun, tracking radar set and computer on one carriage

esky Buys Ward Heater

Kresky Mfg. Co., Petaluma, Calif., rchased the Ward Heater Co., Los geles.

ys Canadian Company

Affiliated Gas Equipment Inc., veland, acquired the Toronto rdware Mfg. Co. Ltd., Toronto, t.

points Southern Distributor

Kurt Orban Co. Inc., New York, ap- inted G. D. Machine Tool Co., Tuck- Ga., as distributor of the com- ny's German-made machine tools in southern states.

bsidiary Company Formed

Commercial Shearing & Stamping ., Youngstown, started a subsidiary mpany, Commercial Shearing Ltd., amilton, Ont., to handle its Can- ian business.

oover Enters New Plant

Hoover Products Inc., plastic toys anufacturer, moved Youngstown op- ations into a new $150,000 plant.

ans Manufacturing Center

A Pasadena, Calif., electronic in- ruments company, Consolidated En- neering Corp., plans to develop a 20- re instrument manufacturing cen- ter with a "campus atmosphere" near its present plant.

Warehouse for Western States

Standard Pressed Steel Co., Jenkintown, Pa., opened a warehouse near Los Angeles, to service 11 states and British Columbia.

Rubber Research Planned

U. S. Rubber Co. plans to create a research center on an 80-acre site in Emerson, N. J.

Heads Metal Lath Group

G. J. Casey was elected to his second term as president of the Metal Lath Manufacturers Association at the annual meeting in Cleveland. Mr. Casey has spent 30 years with Truscon Steel Division of Republic Steel Corp., the last 11 years as sales manager of the corporation's metal lath division.

Plans Canadian Mining

North Range Mining Co., Negaunee, Mich., is planning development of an iron mining area at Sapawe, Ont.

Old Town Stock Purchased

James H. McGraw Jr., former chairman and president of McGraw-Hill Publishing Co. Inc., purchased a majority of the common stock of Old

MOREY
COMPLETE MACHINE TOOL CATALOG
Please write on your business letterhead.
MOREY MACHINERY CO., INC.
Manufacturers • Merchants • Distributors
410 BROOME STREET • NEW YORK 13, N. Y.
CANAL 6-7400 • CABLE ADDRESS WOODWORK, N Y

SEE
New Products!
New Ideas!
1953 HANNOVER
GERMAN
INDUSTRIES FAIR
APRIL 26—MAY 5

Plan *now* to visit West Germany's Hannover Fair! See over 4,000 exhibits that include *Materials & Equipment for these industries:*

- Mining, Milling, Metalworking Machinery —Motors & Engines
- Electrical Manufacturing & Construction
- Tools
- Chemical & Other Processing
- Electronics
- Textile Machinery
- Automotive
- Office Supplies . . . and products for every industry!

Get full FREE facts. Call or write:
GERMAN-AMERICAN TRADE PROMOTION
350 Fifth Avenue, New York 1, N.Y.
Wisconsin 7-0727

DRILL HOLES AS SMALL AS .030" IN ANY METAL OF ANY HARDNESS OR THICKNESS!

The M-300 Elox Electron Drill* combines the best in the 'arc machining' process. In addition to drilling holes as small as .030" it is adjustable for machine finishes ranging from *coarse, fine, extra fine and super fine* ...on any metals from magnesium to cemented carbide. The M-300 with exclusive Elox Automatic Feed allows for continuous operation with much of the human element removed. Using electrodes costing less than 3¢ per inch, with 'super fine' cutting, 1" of electrode will cut as much as 33" of hardened steel! Here indeed, is a dual-purpose machine that is being used for production machining of hardened steels and for removing broken drills in salvage. Write today for details and list of users.



ELOX CORPORATION OF MICHIGAN

721 N. ROCHESTER RD. • CLAWSON, MICHIGAN

BALL BEARINGS ARE UNIFORMLY CARBURIZED IN THESE AGF ROTARY FURNACES



This is part of an actual battery of AGF No. 2GA Batch Furnaces for uniform carburizing of Ball Bearings.

For absolute uniformity of large production hardening or other controlled atmosphere treatment of small parts, you can always depend on AGF equipment.

Write for Bulletin No. 1211A.

AMERICAN GAS FURNACE CO.
996 LAFAYETTE STREET, ELIZABETH 4, N. J.

The *Cleveland Steel Tool Co.*
• PUNCHES • DIES • CHISELS • RIVET SETS •
IF IT'S *RIVETED* YOU KNOW IT'S SAFE
WE FEATURE SPECIAL PUNCHES & DIES
660 E. 82nd ST., CLEVELAND, O.

HOT DIP GALVANIZING

JOSEPH P. CATTIE & BROTHERS, INC.
Office: 2520 East Hagert Street
Plant: Gaul, Letterly, Almond & Hagert Streets
Phone: Re-9-8911 Philadelphia 25, Pa.

359 MIDLAND AVE. • DETROIT 3, MICH.

DETROIT STAMPING COMPANY

Especially geared for light to medium heavy stamping and high volume runs of small, intricate "Multi-Stampings. We invite your inquiry or write for Stamping Brochure

★ . . . for any information about bearings and bearing metals, consult with the A. W. Cadman Mfg. Co., master makers of fine bearing metals since 1860.

PITTSBURGH .....28th and Smallman Streets
PHILADELPHIA .....18 W. Chelten St. .....
CHICAGO .....Manhattan Bldg. .....
NEW YORK .....150 Nassau St. .....

INTRODUCTION TO THE STUDY OF HEAT TREATMENT OF METALLURGICAL PRODUCTS

By Albert Portevin

Fundamental knowledge and essential principles of heat treatment of steel are presented in simple and understandable manner. Research engineers, metallurgical students and steel plant metallurgists engaged in metallurgical investigations and the heat treatment of ferrous and non-ferrous metals will find this book of inestimable value.

246 pages 4 tables
69 illustrations Price $5.00 Postpaid

THE PENTON PUBLISHING CO.
Book Department, 1213 W. 3rd St., Cleveland 13, O.

own Corp., New York manufacturer typewriter ribbons, carbons and duplicating equipment.

eads Road Builders

Robert M. Reindollar, consulting engineer of Baltimore, was elected president of the American Road Builders' Association at its convention in Boston.

pens Dallas Sales Office

Maintenance Engineering Corp. will open a Dallas office to be sales representative in northern Texas for Lukens Steel Co., Coatesville, Pa.

merican Sterilizer Buys Site

American Sterilizer Co., Erie, Pa., is buying 56 acres of property in Erie to erect a $1 million plant over a period of five years. The company produces hospital and surgical equipment.

ppoints Chain Distributor

Atlas Chain & Mfg. Co., Philadelphia, appointed Warren M. Pike Associates Inc., Boston, as master distributors of Atlas Chain for metropolitan Boston.

o Build in Los Angeles

Associated Coil Spring Co., New York, will build a factory in Los Angeles on a 60,000-square-foot site.

arehouse To Serve Texas

Industrial Tape Corp., New Brunswick, N. J., opened new warehousing facilities in Dallas to serve markets in Texas and surrounding areas.

oronto Plant Begun

Canadian Stackpole Ltd., subsidiary of Carbon Co. Inc., St. Marys, Pa., began construction of a plant in Toronto, Ont., to produce electronic components for radio and television.

llis-Chalmers Names Agent

Roche & Hull Inc., Baltimore, was named by Allis-Chalmers Mfg. Co., Milwaukee, as a distributor for its pumps.

enada Aluminum Expands

Benada Aluminum Co., Girard, O., is undergoing an expansion program which will add 87,000 square feet of floor space and triple company personnel within one year.

tlas Buys Office Site

Atlas Powder Co., Wilmington, Del., acquired about 45 acres of land near Wilmington, to construct an office building.

nstalls Lining Facilities

The plant of Frederic B. Stevens Inc., New Haven, Conn., installed complete facilities for rubber or Koroseal lining all types of plating tanks.

More Fabricating Facilities

Engineering Corp. of America, designers and builders of special mechanical and process equipment, with offices at Westfield, N. J., acquired additional plant fabricating facilities in Garwood, N. J.

Foundry Passes Tests

The Utica Radiator Corp. foundry, Utica, N. Y., has undergone a successful trial operation but regular operation will not be underway until mid-March or early April.

Cambridge Opens New Office

Cambridge Wire Cloth Co., Cambridge, Md., opened a new southern sales territory with headquarters in Atlanta.

Award Bridge Contract

The Northern Pacific Railroad awarded the second phase of the $4 million Columbia river bridge raising project to Kansas City Bridge Co. and Massman Construction Co., Kansas City, Mo., for moving the spans to new piers and replacing the draw-span.

Luria Builds Warehouse

Luria Engineering Co. is erecting a 12,000-square-foot warehouse for the Wilmington Paper & Twine Co. in Wilmington, Del.

Names Rochester Representative

Rivett Lathe & Grinder Inc., Boston, appointed Genesee Machine Builders Inc., Rochester, N. Y., as representative in the Rochester area.

Joins Trade Association

Marve Narramore joined the Drop Forging Association, Cleveland, a national trade association representing interests of the commercial drop forging industry. Mr. Narramore is staff assistant.

New Division of Remington Rand

Engineering Research Associates of St. Paul and Arlington, Va., is now a division of Remington Rand Inc., New York.

Sylvania Plans Construction

Sylvania Electric Products Inc. plans to build a $1.4 million engineering laboratory near Williamsport, Pa., with construction starting in May or June.

Appoints New Distributor

Clearing Machine Corp., Chicago manufacturer of hydraulic and mechanical presses, appointed the Sater-

If your workers "can't hear themselves think," chances are *you'll* hear about it in lowered production and damaged hearing.

Loud industrial noises sap energy, interfere with job concentration, and sometimes result in serious hearing loss. M.S.A. Ear Defenders block out these costly noises, yet allow wearer to hear warning signals, speech, and telephone conversation.

M.S.A. Ear Defender design insures comfortable fit; complete closure of ear canal; easy to insert, remove. Ear Defenders are easily cleaned with soap and water. Convenient carrying case keeps them clean in pocket. Write for details.

MSA SAFETY EQUIPMENT HEADQUARTERS

Mine Safety Appliances Co.
Braddock, Thomas & Meade Sts.
Pittsburgh 8, Pa.

Every state in the Union boasts one hotel that's head and shoulders above all others. In Maryland, it's Baltimore's Lord Baltimore Hotel.



Rolling Water Tower

When the Bedford Rural District Council, England, decided to move a 1900-ton water tower 300 yards, steel balls and a Caterpillar D7 diesel tractor made possible the hard pull. The tower was rolled to its new location on steel bearings rolling in a race made from ordinary bullhead section railroad lines laid on their sides and resting on a movable precast concrete block. The D7 pulled the tower through a 10-to-one block and tackle reduction to exert a 50-ton pull

lee Co., Minneapolis, as a distributor in that area.

Begins Oxygen Deliveries

Air Reduction Sales Co.'s newly completed liquid oxygen plant in Butler, Pa., has begun delivery of oxygen to industrial customers.

Sheridan Purchases Yard

Sheridan Scrap Iron & Metal Co. purchased the scrap yard of the Columbia Metal & Iron Scrap Co., Pittsburgh.

Error Noted

An item in these pages in the Feb. 9 issue erroneously reported that Twin Coach Co., Buffalo, plans to install about $1 million worth of new machinery in 1953 to handle a multi-million dollar aircraft order. Twin Coach contemplates purchasing replacement equipment only during 1953.

Adds to Geigy Plant

Luria Engineering Co. finished construction of a 12,000-square-foot addition to the Leland, Miss., factory of Geigy Co. Inc.

Lehigh Plans Conference

Eight national organizations will join Lehigh University's department of mechanical engineering in sponsoring a two-day conference on trends in year-round residential air conditioning. The sessions will begin Apr. 24 at the Bethlehem, Pa., school.

To Open California Plant

Lindberg Engineering Co., Chicago, will open a new plant in Downey, Calif., Mar. 25.

Westinghouse Plant Projected

Westinghouse Electric Corp. has plans for a multi-million dollar plant to produce atomic equipment. The plant, to be operated by the Westinghouse atomic equipment department, will be located near Pittsburgh.

Opens Indiana Plant

Pittsburgh Plate Glass Co.'s fiber glass division began production in its new facilities at Shelbyville, Ind.

Buys Plant Site

A 25-acre plot was purchased by Cleveland Cap Screw Co. as a site for a new Cleveland plant.

Employs Long Conveyor

U. S. Steel Corp. put one of the world's longest single-flight rubber and fabric constructed conveyor belts into operation between the coking plant and blast furnaces at its Fairless Works in Morrisville, Pa. The belt, measuring 5500 feet from the center of the head pulley to the center of the tail pulley, was built by Goodyear Tire & Rubber Co., Akron

Douglas Adds Facilities

Douglas Aircraft Co. Inc., Santa Monica, Calif., will add $2 million of facilities to its plant in Long Beach Calif.

Lockheed To Expand

Lockheed Aircraft Corp., Burbank Calif., will add $3 million of factory facilities to increase production of large aircraft. Construction is sched-

NEW PIPE
Warehouse Stocks of
STANDARD • MERCHANT
LAP WELD • SEAMLESS
BUTTWELD • SPIRAL WELD
L.B. FOSTER CO.
HOUSTON 2, TEX. CHICAGO 4, ILL.
PITTSBURGH 30, PA. NEW YORK 7, N.Y.

NEW AMERICAN MADE MACHINES
FOR QUICK DELIVERY:
10' x ¼" Shears
100 ton Press Brakes—various lengths
All sizes O.B.I. Presses
INDUSTRIAL SALES COMPANY
1507 M Street, N.W., Washington 5, D. C.
Chicago, Philadelphia, Baltimore
& Greensboro, N. C.

FOR SALE
Planer, Niles-Bement-Pond Table 60" wide, 20 ft. long, 36" high from table to cross rail. Direct Motor Drive-DC current through AC-DC Motor Generator Set. May be seen operating on either day shift or early evening night shift. ($9750.00.) Write Box 678, STEEL, Penton Bldg., Cleveland 13, Ohio.

FOR SALE
Two Salem Gas Annealing Furnaces—Model 501. 1 H.P. Induction Motor drives metal conveyor 21" wide with electric control panels. Each unit occupies a space 7½ ft. wide x 26 ft. long. Capacity—3,475,000 BTU or 3,000 cu. ft. per hr. Each unit is connected to conveyor 13½" wide x 10 ft. long. Excellent condition. Priced to sell.
Contact:
W. Furlong, GIBSON MFG. CORP.,
Longmont, Colorado.

Consolidated Welding &
Engineering Co.
ENGINEERS
CONSULTANTS—DESIGNERS
Designers of Special Machinery,
Dies, Jigs & Fixtures.
Product Engineering
Cost Estimating
Plant Layout
Redesigning
Welding & Fabricating Consultants
On All Types
Ferrous & Non-Ferrous Materials
2450 S. Ashland Ave. Chicago, Ill.
Chesapeake 3-3270

RAILROAD EQUIPMENT—*FOR SALE*

USED **AS IS** **RECONDITIONED**

STANDARD GAUGE FREIGHT CARS

Box, Steel Sheathed, 40-Ton Capacity
Box, Double Sheathed, 50-Ton Capacity
Box, Single Sheathed, 50-Ton Capacity
Flat, 50-Ton, Steel Underframe, 40'6" Long
Gondolas, Composite, or All Steel 50-Ton and 70-Ton
Hoppers, Twin, All-Steel, 50-Ton, *Cross Dump*
Tank, 3,000-Gallon, High Pressure
Tank, 8,000-Gallon, Coiled and Non-Coiled

Hoppers, All-Steel, 70-ton, *Cross Dump*

EXTRA LONG FLAT CARS

40 & 50-Ton Capacity, Length 70' and 74'

CABOOSE CARS

Eight Wheel, Cupola Type

STANDARD GAUGE AIR DUMP CARS

Side Dump, 20-Yd., 40-Ton, Lift Door
End Dump, 20-Yd., 50-Ton Drop Door
Side Dump, 30-YD., 50-TON, DROP DOOR

OTHER EQUIPMENT

Jordan Spreader
Locomotive Cranes
Overhead Cranes
Railroad Track Scales

STANDARD GAUGE DIESEL-ELECTRIC ROAD SWITCHING LOCOMOTIVE

300 H.P., 70-Ton, Type 0-4-4-0
NEW AND RELAYING RAIL

Send us your inquiries **WE BUY FREIGHT CARS FOR DISMANTLING** ***Send us your offerings***

IRON & STEEL PRODUCTS, INC.

REPAIR PARTS For All Types of Freight Cars

General Office
13462 S. Brainard Ave.
Chicago 33, Illinois
Phone: BAyport 1-3456

New York Office
50-D. Church Street
New York 7, N. Y.
Phone: BEekman 3-8230

STORAGE TANKS
6,000 Gallon
8,000 Gallon
10,000 Gallon

"ANYTHING containing IRON or STEEL"

CLASSIFIED

Help Wanted

FOREMAN FOR PRODUCTION PARTS DEPARTMENT. Midwest location. Thoroughly experienced in forming and piercing steel plates and shapes. Requires knowledge of estimating machine time, tooling, jig and die design, quality control. In reply state age, experience and salary requirements. All replies confidential. Write Box 681, STEEL, Penton Bldg., Cleveland 13, Ohio.

SMALL FABRICATING PLANT ESTIMATOR. Must have experience in take off, estimating for component parts of ships, et cetera. Must have shop experience as to layout and production. Warrants good salary for capable man in small town North Florida. Replies held confidential. Applicant must have good references. Write Box 672, STEEL, Penton Bldg., Cleveland 13, Ohio.

Positions Wanted

REPRESENTATIVE, ENGINEERING BACKground, five years successful sales experience in and castings, desires to represent a progressive midwest steel foundry, making shell molding castings in both stainless and ordinary steel. Drawing account and commission. Write Box 680, STEEL, Penton Bldg., Cleveland 13, Ohio.

PLANT MANAGER: M.I.T. GRADUATE WITH 15 years' experience in Plant Management, including Production planning, machine and plant loading, Material and tool control, quality control, purchasing, incentives, standard costs, variable budgets, overhead analysis and breakeven charts, job evaluation, supervisory responsibility chart and labor relations. Capable administrator with excellent record. Write Box 671, STEEL, Penton Bldg., Cleveland 13, Ohio.

PITTSBURGH REPRESENTATION Industrial Sales, tri-state area. Complete coverage all types industry. Ten years' experience, college graduate. Salary. Write Box 681, STEEL, Penton Bldg., Cleveland 13, Ohio.

Available—one of the best TOOL STEEL SALESMEN in the state of Wisconsin. Write Box 682, STEEL, Penton Bldg., Cleveland 13, Ohio.

FOR CLASSIFIED RATES
And Further information write
STEEL, Penton Bldg., Cleveland 13, O.

AGE NO BARRIER

We seek a man long experienced in stainless steel production who can train men to operate a continuous strip mill for hot and cold stainless steel. Unusual opportunity for someone now retired or in semi-retirement. Position for two years at least. In attractive Niagara Peninsula. Send application or resume to Robert Teasdale, Atlas Steels Limited, Welland, Ontario.

Wanted
FORGE PLANT SUP'T.

With flat die forging experience in alloy and tool steels. Jobbing shop work. Must be capable of planning and expediting production and keeping modern equipment in good working condition. General knowledge of heat treating and rough turning, essential. Proven work record necessary. Salary open. Location: Ohio. Write stating details to

Box 668, STEEL
Penton Bldg., Cleveland 13, Ohio

WANTED

STRUCTURAL STEEL & PLATE SHOP EQUIPMENT

Air Compressor—2-stage
650 to 1500 C.F.M.
3-phase, 60 cycle, 440 current
Prefer direct drive synchronous motor.
Beam bender and straightener.
Beam shear.
Press brake, capacity ½" x 12'.

B. E. McKenzie
GLAZER STEEL CORP.
Knoxville, Tenn. Telephone: 4-8601

WANTED

5 Ton Crane for 80'

span cab operated.

Submit all details in writing to—

SONKEN-GALAMBA CORPORATION

2nd and Riverview (X-928)
Kansas City 18, Kansas

WANTED

1-½ to 3 TON ELECTRIC FURNACE, TOP OR SIDE CHARGE, WITH OR WITHOUT TRANSFORMER, ANY VOLTAGE.
Box 676, STEEL
Penton Bldg., Cleveland 13, Ohio

WANT TO PURCHASE

1 used 100 to 150 TON FORGING PRESS
CONTACT: A. Flores
LA CONSOLIDADA, S. A.
P. O. Box 120—Tel. 497, Eagle Pass, Texas

REBUILT AND NEW

***GUARANTEED* MOTORS**

M.G. SETS • GENERATORS

Hoists • Compressors • Transformers
Units of Every Size and Description

WE'LL SELL, BUY OR TRADE
PHONE CANAL 6-2900

CHICAGO *Electric Co.*

1334 W. CERMAK ROAD
CHICAGO 8, ILL.



Illustration shows work entering METALWASH overhead conveyor-type washer used by the General Electric Company.

This METALWASH machine cleans stainless steel freezer compartment parts.

Other METALWASH machines, also installed at General Electric, perform similar operations in the production of General Electric refrigerators.

Metalwash *engineering skill and experience are your assurance of lasting performance.*

Write on your company letterhead for our free, illustrated Full-Line Catalog.

METALWASH
MACHINERY CORPORATION

917 North Ave., Elizabeth 4, N. J.
Representatives in principal cities

uled by Mar. 1 and completion is planned early next year.

Changes Plant Location

The new location of Glazer Steel Corp.'s plant and offices in New Orleans is 1556 Tchoupitoulas St.

Welding Clinic Planned

Steel Sales Corp. of Chicago reports that a three-day welding clinic will be held in connection with the formal opening of its Indianapolis warehouse. The clinic will begin Apr. 15.

Hamilton Opens New Division

Hamilton Watch Co., Lancaster, Pa., set up an allied products division to develop, produce and market new products.

Canadian Expansion Planned

Chrysler Corp. of Canada Ltd. will begin a $17 million expansion program immediately at its works in Windsor, Ont.

Thor Adds New Products

Thor Corp., Chicago, added electric ranges to its appliance line through acquisition of Leeson Steel Products Co., New Albany, Ind.

Elected by Plate Fabricators

J. A. Stever Jr., executive vice president of National Tank & Mfg. Co., Los Angeles, was elected a regional vice president of the Steel Plate Fabricators Association in a recent meeting.

Plans Research Laboratory

Allied Chemical & Dye Corp.'s general chemical division plans to build a large research laboratory at Morristown, N. J.

Receive Management Awards

The American Institute of Management awarded certificates of management excellence for 1952 to six steel companies: Acme Steel Co., Inland Steel Co. and Signode Steel Strapping Co., all of Chicago; Allegheny Ludlum Steel Corp. and National Steel Corp., both of Pittsburgh, and Bethlehem Steel Corp., Bethlehem, Pa.

Heads Cast Iron Pipe Group

The Cast Iron Soil Pipe Institute elected J. W. Struve of Los Angeles as president for 1953.

Koehring Names Distributors

Koehring Co., Milwaukee, appointed distributors for territories in Wisconsin, California and Florida. The companies appointed are Kelbe Bros. Equipment Co., Milwaukee, Allied Equipment Inc., Miami, Fla. and Standard Machinery Co., San Francisco.

Prepares for Youngstown Plant

Metal Carbides Corp. is clearing a 17-acre site in Youngstown for construction of a $1 million plant.

Merging Resources

Sintering Machinery Corp., Netcong, N. J., and Equipment Development Co. Inc., Montclair, N. J., agreed to join in production and sale of filtration equipment to be marketed under the trade name of "Edco-Sintering."

Wins Achievement Award

H. Thomas Hallowell Jr., president of Standard Pressed Steel Co., Jenkintown, Pa., was named to receive the 1952 achievement award of the National Metal Trades Association for outstanding contributions in industrial relations.

Harbison-Walker Makes Change

The Warm Springs, Calif., plant of Harbison-Walker Refractories Co. is completely converted to production of chemically bonded basic refractories.

Champion Builds in Ohio

Champion Spark Plug Co. will build a $1.5 million plant employing between 200 and 400 persons in Cambridge, O.

Company Name Changed

Harry Harris & Co., Kearny, N. J., changed the company name to Harris Steel Co.

Becomes Inland Division

Inland Steel Container Co., Chicago, became a division of the parent company, Inland Steel Co., on Mar. 1. Inland Steel Container has been a wholly-owned subsidiary corporation of Inland Steel since 1939.

Harvell Undertakes Move

Harvell Mfg. Corp. is moving its offices and plants from LaPorte, Ind. to Hubbard, O., a suburb of Youngstown, the company announces. Harvell manufactures metal wastebaskets, wax paper and paper towel dispensers.

Lang Named Representative

Lang Co., steel fabricators and equipment suppliers in Salt Lake City, Utah, has been appointed exclusive industrial sales representative for Chiksan Co., Brea, Calif., in the states of Utah and Idaho.

To Enter Air Conditioning

Dayton Pump & Mfg. Co., Dayton O., announced it will enter the air conditioning field.

Advertising Index

ive Products, Inc. 173
a Synthetic Products Division Western Works 6
Wood Steel Co. 122
Research Products, Inc. 127
Steel & Conveyors, Inc. 85
n Co., The 129
can Broach & Machine Co., A Division Sundstrand Machine Tool Co. 120
can Gas Furnace Co. 198
can Welding & Manufacturing Co., The. 92
can Wheelabrator & Equipment Corp. 108, 109
Steel Corporation 59
Car & Mfg. Co., The 149

ck & Wilcox Co., The, Tubular Products Division ..... Inside Front Cover
Refractories, Inc. 7
State Abrasive Products Co. 106
rd Foundry & Machine Co., Inc. 140
hem Steel Co. 1
& Laughlin, Inc. 52
sport Brass Co. 158, 159
Brass Corporation, The 42
& Sharpe Mfg. Co. 17, 18, 19, 20
ung, Victor R., & Co., Inc. 196
t Chucking Grinder Co. 150, 151
lo Bolt Co., Division of Buffalo-Eclipse poration 132
ng Brass & Bronze Co., The 186
Manufacturing Co., The 168

an, A. W., Mfg. Co. 198
net & Hecla, Inc., Wolverine Tube Divi-n 136, 137
ar Screw & Mfg. Corp. 134
nfer Steel Co., The, Alloy Tube Division 48
, Joseph P., & Brothers, Inc. 198
e Brass & Copper Co. 138
ago Electric Co. 201
ago Freight Car & Parts Co. 194
ing Machine Corporation 103
eland Metal Abrasive Co., The 169
eland Steel Tool Co., The 198
Metal Products Co., The 74
rado Fuel & Iron Corporation, The, Wick-re Spencer Steel Division 91
Two Fire Equipment Co. 126
ble Steel Company of America 31
s Pneumatic Machinery Division of Curtis anufacturing Co. 55

aval Steam Turbine Co. 135
ark Corporation 125
a Power Tool Division, Rockwell Manu-cturing Co. 133
oit Stamping Co. 198
ond Mfg. Co. 196
rential Steel Car Co. 152
ge Manufacturing Corporation 46
o Corporation 43
Pont, E. I., de Nemours & Co., Inc. 41

ern Machine Screw Corp., The 196
on Car & Construction Co. 192
er Engineering Co. 53
ric Controller & Mfg. Co., The 60
ric Storage Battery Co., The 130, 131
Corporation of Michigan 198
ll-Parker Electric Co., The 145
Foundry Co. 155
ell-O Corporation 4, 5

teel Metallurgical Corp., Weiger-Weed & . Division 157
al Corporation, The ..... Inside Back Cover

Continued on following page

it's metal magic!

Hendrick Ornametal
TRADE MARK

Whether you require grilles for radiator enclosures, stove panels, kitchen cabinets, clothes and broom closets, lockers or similar applications — you can be sure there's a Hendrick Ornametal design to fit your job to a tee!

Hendrick Ornametal is a lightweight type of grille that is made of a special bright finish, cold rolled steel, suitable for painting or plating — and it's available in a wide range of stock size sheets and gauges.

For more complete information write for free folder.

Hendrick
MANUFACTURING COMPANY

SEE OUR CATALOG IN SWEET'S

30 DUNDAFF ST., CARBONDALE, PA. • ***Sales Offices In Principal Cities***

Perforated Metal • Perforated Metal Screens • Wedge-Slot Screens • Architectural Grilles • Mitco Open Steel Flooring • Shur-Site Treads • Armorgrids

make your PUNCH PRESSES *Automatic*

It's Easy...with WITTEK Roll Feeds and Reel Stands

Wittek Roll Feeds handle any type of coiled strip stock and are made in single roll, double roll, and compound types with straighteners, in models to feed in any of four directions. They are reliable and accurate with simple, quick adjustment of feed length. Standard sizes and models meet a wide variety of press size and capacity conditions.

Wittek Reel Stands facilitate handling coiled stock.

**Write for full particulars*

WITTEK Manufacturing Co.
4328 W. 24th Place, Chicago 23, Illinois

Automatic ROLL FEEDS AND REEL STANDS

. . or Released in an Instant


CLINCH TYPE

INSTRUMENT MOUNTING

SPLINE TYPE

THIN TYPE

STANDARD

Faster assembly . . . no more failures of fasteners. GREER STOP NUTS hold firm against jolts, shocks, shimmy, wobbles . . . any vibration, any kind.

Bolt threads are gripped tightly . . . these famous nuts *never* work loose. Yet an ordinary hand wrench gives instant release. The tough, built-in GREERCOID collar does it . . . and seals against fluid leakage, too!

Study *your* fastener problem. Over 3000 types and sizes. Consult GREER. Proved on thousands of products. Meets gov't and military specifications.

Write

GREER STOP NUT CO.

2620 Flournoy, Chicago 12, Ill.

Advertising Index

Concluded from preceding page

Federal Machine & Welder Co., The 124
Ferry Cap & Set Screw Co., The 26
Foster, L. B., Co. 200

General Refractories Co. 38, 39
German-American Trade Promotion 197
Gerrard Steel Strapping Division, United States Steel Corporation 54
Gisholt Machine Co. 27
Goodrich, B. F., Co., The 3
Greer Stop Nut Co. 204
Gregory Industries, Inc., Nelson Stud Welding Division 10

H & H Tube & Manufacturing Co. 153
Harnischfeger Corporation, Overhead Crane Division 142, 143
Harper, H. M., Co., The 156
Hendrick Manufacturing Co. 203
Heyl & Patterson, Inc. 11
Holliday, W. J., & Co., Inc. 154
Hyatt Bearings Division, General Motors Corporation 78

Industrial Filtration Co. 125
International Nickel Co., Inc., The 56
Iron & Steel Products, Inc. 201

Jeffrey Manufacturing Co., The 21
Jones & Lamson Machine Co. 13
Jones & Laughlin Steel Corporation 23

Kearney & Trecker Corporation, Walker-Turner Division 22
Kewanee-Ross Corporation **111**

Laminated Shim Co., Inc. 157
Landis Machine Co. 8
La Salle Steel Co. 119
Lindberg Engineering Co. 194
Loftus Engineering Corporation 146
Logemann Brothers Co. 185
Lord Baltimore Hotel 199
Luria Brothers & Co., Inc. 174

McKee, Arthur G., & Co. 116, 117

Manheim Manufacturing & Belting Co. 164
Markal Co. 191
Medart Co., The 139
Meehanite Metal Corporation 141
Metalwash Machinery Corporation 202
Milford Rivet & Machine Co., The 170
Mine Safety Appliances Co. 199
Molybdenum Corporation of America 128
Morey Machinery Co., Inc. 197
Morgan Construction Co. 73
Morgan Engineering Co., The 114
Mundt, Charles, & Sons 193
Murray, A. B., Co., Inc. 190

National Acme Co., The 15
National Forge & Ordnance Co. 40
National Roll & Foundry Co., The 113
National Steel Corporation 33
Nelson Stud Welding Division of Gregory Industries, Inc. 10
New Departure, Division of General Motors 81
Niagara Blower Co. .....
Norton Co. 44,

Ohio Locomotive Crane Co., The .....
Ohio Steel Foundry Co., The .....

Pacific Tube Co. .....
Parker-Kalon Corp. .....
Paxson Machine Co. .....
Pennsylvania Flexible Metallic Tubing Co. ..
Peterson Steels, Inc. .....
Philadelphia Gear Works, Inc. .....
Phillips Petroleum Co. .....
Pittsburgh Coke & Chemical Co. .....
Pittsburgh Crushed Steel Co. .....
Pusey & Jones Corp., The .....

Republic Steel Corporation .....
Reynolds Metals Co. 28,
Roebling's, John A., Sons Co. .....
Rollway Bearing Co., Inc. .....

Simmons Machine Tool Corporation .....
Simonds Abrasive Co. .....
Smeeth-Harwood Co. .....
Square D Co. .....
Stamco, Inc. .....
Standard Conveyor Co. .....
Standard Pressed Steel Co. .....
Steel Shot & Grit Co. .....
Superior Tube Co. .....
Surety Rubber Co., The .....
Surface Combustion Corporation .....

Timken Roller Bearing Co., The, Steel & Tube Division .....
Torrington Co., The, Swager Department ....
Treadwell Engineering Co. .....
Turner Bros., Inc. .....

Udylite Corporation, The .....
United Manufacturing Co., The .....
United States Steel Corp., Subsidiaries .....
Upson-Walton Co., The .....
U. S. Stoneware Co., The .....

Valley Mould & Iron Corp. .....
Vaughn Machinery Co., The .....
Victor Saw Works, Inc. .....

Walker-Turner Division, Kearney & Trecker Corporation .....
Warner & Swasey .....
Wean Engineering Co., Inc., The ..... Back
Weiger-Weed & Co., Division of Fansteel Metallurgical Corp. .....
Weirton Steel Co. .....
Western Felt Works, Acadia Synthetic Products Division .....
Wickwire Spencer Steel Division of The Colorado Fuel & Iron Corporation .....
Wittek Manufacturing Co. .....
Wolverine Tube Division of Calumet & Hecla Inc. 136,

Youngstown Sheet & Tube Co., The .....

~ ~ ~

Table of Contents, Page 5

Classified Advertising Pages 200, 201

FARVAL—*Studies in Centralized Lubrication* No. 140



YS TO ADEQUATE LUBRICATION—*Wherever you see the sign Farval—the familiar valve manifolds, dual lubricant lines and cen-al pumping station—you know a machine is being properly lubricated. rval manually operated and automatic systems protect millions of dustrial bearings.*

FARVAL SAVES ON BENDING ROLL LUBRICATION

	Lbs./yr. lube. 62 points	Hrs./yr. lube. 62 points	Annual Cost @ $1.50/hr. 62 points
GREASE GUN	20,592 lbs.	717 hrs.	$1,075.00
CENTRALIZED SYSTEM	5,304 lbs.	15 hrs.	$ 22.50
ANNUAL SAVINGS EFFECTED BY FARVAL	15,288 lbs.	702 hrs.	$1,051.50
COMBINED SAVING (LABOR AND LUBRICANT)			$2,579.50

AND IN ADDITION, FARVAL SAVES BEARING EXPENSE AND PRODUCTION TIME

eports of lubrication engineers show lubrication by grease gun kes .747 minutes per point—to clean dirt from nipples, grease, ove from point to point, and refill gun. With Farval it takes only 5 minutes every fourth day to refill Farval reservoir. In addition, arval saves 3 pounds of each 4 of lubricant used by other methods.

800 miles of pipe rolled on Baldwin Bending Roll lubricated by Farval

THIS first of a new type bending roll formed over 800 miles of 24″ and 30″ O.D. pipe its first operating year. At work in a large southern pipe mill, it shapes 31½ foot lengths of 78″ and 97″ skelp at rolling speeds up to 60 feet per minute.

To insure that the new design features for increased production would not be hamstrung by old-fashioned hand lubrication, the machine builder equipped the bending roll with Farval centralized lubrication.

At a single stroke Farval lubricates 62 main bearings on which depends the rugged job of shaping skelp. No stopping for time-consuming hand oiling! Lubricant savings run as high as 75%.

Farval is the original Dualine system of centralized lubrication that delivers oil or grease under pressure to a group of bearings from one central station, in exact quantities, as often as desired. The Farval valve has only two moving parts—is simple, sure and foolproof, without springs, ball-checks or pinhole ports to cause trouble. Indicators at every bearing tell that each valve has functioned.

Machinery builders and customers alike recognize that Farval centralized systems of lubrication save time, money and lubricant, as well as eliminate bearing expense and increase machine production.

There are Farval systems for your machines, big or small, with proportionate savings. And there's a Farval engineer near you, ready to solve your lubrication problems. Write for full details. Send for Bulletin 25 today. The Farval Corporation, 3270 East 80th Street, Cleveland 4, Ohio.

Affiliate of The Cleveland Worm & Gear Company, Industrial Worm Gearing. In Canada: Peacock Brothers Limited.



HEAVY PLATE LEVELERS

★

ELECTROLYTIC COATING EQUIPMENT

★

WEAN VACUUM CUP SHEET and PLATE LIFTERS

★

BONDERIZING EQUIPMENT







HI-SPEED SHE and TIN MIL SHEAR LINES

★

STAINLESS STEE PROCESSING LIN

★

CONTINUOUS STRIP PICKLING, SLITTING, SIDE TRIMMING and RECOILING LINES

The WEAN ENGINEERING COMPANY Inc.
WARREN, OHIO

SPECIALISTS IN SHEET, TIN AND STRIP MILL EQUIPM